

ITEM 448 - ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG76-22

THE COURSE AGGREGATE FOR THIS ITEM SHALL BE LIMITED TO AIR COOLED BLAST FURNACE SLAG OR LIMESTONE.

ITEM 407 - TACK COAT

THE RATE OF APPLICATION OF THE 407 - TACK COAT SHALL BE SUBJECT TO ADJUSTMENTS, AS DIRECTED BY THE ENGINEER. PLAN QUANTITIES INDICATE AN AVERAGE APPLICATION RATE OF 0.10 GAL/SQ.YD. FOR ESTIMATION PURPOSES ONLY.

ITEM 407 - TACK COAT FOR INTERMEDIATE COURSE

THE RATE OF APPLICATION OF THE TACK COAT FOR INTERMEDIATE COURSE SHALL BE SUBJECT TO ADJUSTMENT AS DIRECTED BY THE ENGINEER. PLAN QUANTITIES INDICATE AN AVERAGE APPLICATION RATE OF 0.05 GAL./SQ. YD. OF TACK COAT FOR INTERMEDIATE COURSE FOR ESTIMATING PURPOSES ONLY.

ITEM 617 - COMPACTED AGGREGATE, TYPE A

THIS ITEM SHALL BE USED ALONG THE SHOULDERS.

THE ACTUAL DEPTH USED WILL VARY DEPENDING UPON EXISTING CONDITIONS. FOR ESTIMATING PURPOSES, AN AVERAGE DEPTH OF 2 IN. WILL BE USED. WATER, IF NEEDED, SHALL BE APPLIED AS PER 617 AND INCLUDED UNDER ITEM 617 - COMPACTED AGGREGATE, TYPE A.

THE FOLLOWING ESTIMATED QUANTITY HAS BEEN INCLUDED IN THE GENERAL SUMMARY:

ITEM 617 - COMPACTED AGGREGATE, TYPE A . . . . . 300 CU.YD.

ITEM 448 - ASPHALT CONCRETE, SURFACE COURSE, TYPE 1, PG64-22, (DRIVEWAYS)

THIS ITEM OF WORK SHALL CONSIST OF PAVING ALL EXISTING DRIVEWAYS A DISTANCE OF 5 FT. FROM THE EDGE OF PAVED SHOULDER UNLESS OTHERWISE DIRECTED BY THE ENGINEER. THE PLAN QUANTITIES ARE BASED ON 16 FT. WIDE FOR RESIDENTIAL DRIVES AND 40 FT. FOR COMMERCIAL DRIVES. ASPHALT CONCRETE AVERAGE THICKNESS SHALL BE 2 IN. FOR AGGREGATE DRIVEWAYS, AND 1 IN. FOR IMPROVED DRIVEWAYS. ALL GRADING, TACK, TOOLS, EQUIPMENT, MATERIAL, AND INCIDENTALS REQUIRED TO LAYOUT AND CONSTRUCT THE DRIVEWAYS SHALL BE INCLUDED IN THE UNIT PRICE BID FOR ITEM 448 - ASPHALT CONCRETE, SURFACE COURSE, TYPE 1, PG64-22 (DRIVEWAYS)

PAYMENT FOR ALL THE ABOVE SHALL BE INCLUDED IN THE UNIT PRICE BID FOR ITEM 448 - ASPHALT CONCRETE, SURFACE COURSE, TYPE 1, PG64-22 (DRIVEWAYS).

THE FOLLOWING ESTIMATED QUANTITY SHALL BE CARRIED TO THE GENERAL SUMMARY TO BE USED AS OUTLINED ABOVE:

ITEM 448 - ASPHALT CONCRETE, SURFACE COURSE, TYPE 1, PG64-22 (DRIVEWAYS) . . 45 CU. YD.

ITEM 621 - RAISED PAVEMENT MARKER

RAISED PAVEMENT MARKERS SHALL BE INSTALLED IN ACCORDANCE WITH STANDARD DRAWINGS TC-65.10M AND TC-65.12M.

ITEM 828 - CENTER LINE

THE CONTRACTOR SHALL LAY OUT ALL CENTER LINES USING THE MOST RECENT COPY OF THE CENTER LINE LOG. COPIES OF THE CENTER LINE LOG MAY BE OBTAINED FROM THE DISTRICT 12 ROADWAY SERVICES DEPARTMENT. CENTER LINE QUANTITIES AT THE TIME OF CONSTRUCTION MAY VARY FROM PLAN QUANTITIES DUE TO REVISIONS AND UPDATES OF THE CENTER LINE LOG.

GENERAL NOTES

LAKE COUNTY  
LAK-84-19.11

PLOTTED FROM: I:\PROJECTS\121505\21505.dwg