

## SPECIFICATIONS FOR CONSTRUCTION ENTRANCE:

- 1. STONE SIZE-ODOT #2 (1.5-2.5 INCH) STONE SHALL BE USED, OR RECYCLED CONCRETE EQUIVALENT.
- LENGTH—THE CONSTRUCTION ENTRANCE SHALL BE AS LONG AS REQUIRED TO STABILIZE HIGH TRAFFIC AREAS BUT NOT LESS THAN 70 FT. (EXCEPT ON SINGLE RESIDENCE LOT WHERE A 30-FT. MINIMUM LENGTH APPLIES).
- 3. THICKNESS--THE STONE LAYER SHALL BE AT LEAST 6 IN, THICK FOR LIGHT DUTY ENTRANCES OR AT LEAST 10 INCHES FOR HEAVY DUTY USE.
- 4. WIDTH--THE ENTRANCE SHALL BE AT LEAST 14 FT. WIDE, BUT NOT LESS THAN THE FULL WIDTH AT POINTS WHERE INGRESS AND EGRESS OCCURS.
- 5. GEOTEXTILE—A GEOTEXTILE SHALL BE PLACED OVER THE ENTIRE AREA PRIOR TO PLACING STONE. IT SHALL BE COMPOSED OF STRONG ROT—PROOF POLYMERIC FIBERS AND MEET THE FOLLOWING SPECS

D OF STRONG KOT-PROOF POLY	MEMIC FIBERS AND MEE!
GEOTEXTILE SPECIFICATION FOR	CONSTRUCTION ENTRANCE
MINIMUM TENSILE STRENGTH	200 LBS.
MINIMUM PUNCTURE STRENGTH	80 PSI
MINIMUM TEAR STRENGTH	50 LBS.
MINIMUM BURST STRENGTH	320 PSI
MINIMUM ELONGATION	20%
EQUIVALENT OPENING SIZE	eos < 0.6 Mm.
marine of Paris Labor	S GUAN ST AND TOTAL

- 6: TIMING —THE CONSTRUCTION ENTRANCE SHALL BE INSTALLED AS SDOM AS IS PRACTICABLE BEFORE MAJOR GRADING ACTIVITIES:
- CULVERT—A PIPE OR CULVERT SHALL BE CONSTRUCTED UNDER THE ENTRANCE IF NEEDED TO
  PREVENT SURFACE WATER FLOWING ACROSS THE ENTRANCE FROM BEING DIRECTED OUT ONTO
  PAVED SURFACES.
- 8. WATER BAR—A WATER BAR SHALL BE CONSTRUCTED AS PART OF THE CONSTRUCTION ENTRANCE IF HEEDED TO PREVENT SURFACE RUNOFF FROM FLOWING THE LENGTH OF THE CONSTRUCTION ENTRANCE AND OUT ONTO PAVED SURFACES.

## DESCRIPTION:

A CONSTRUCTION ENTRANCE IS A STABILIZED PAD OF AGGREGATE OVER A GEOTEXTILE BASE AND IS USED TO REDUCE THE AMOUNT OF MUD TRACKED OFF-SITE WITH CONSTRUCTION TRAFFIC.

CONDITIONS WHERE PRACTICE APPLIES:

- A CONSTRUCTION ENTRANCE SHOULD BE USED:
- \* WHERE CONSTRUCTION VEHICLES LEAVE ACTIVE CONSTRUCTION AREAS ONTO SURFACES WHERE RUNOFF IS NOT CHECKED BY SEDIMENT CONTROLS;
- \* AT ALL POINTS OF EGRESS TO PUBLIC ROADS;
- \* WHERE FREQUENT VEHICLES AND EQUIPMENT INGRESS/EGRESS IS EXPECTED SUCH AS AT THE AT THE ENTRANCE OF INDIVIDUAL BUILDING LOTS:

## PLANNING CONSIDERATIONS:

THIS PRACTICE SHOULD NOT BE RELIED ON TO REMOVE MUD FROM CONSTRUCTION TRAFFIC. MOST MUD IS FLUNG FROM TIRES AS VEHICLES REACH SPEEDS HIGHER THAN IS REACHED ON SITE. THE BEST APPROACH TO PREVENTING OFF-SITE TRACKING IS TO KEEP VEHICLES THAT FREQUENTLY ENTER AND LEAVE A SITE, AWAY FROM MUDDLY AREAS IN THE FIRST PLACE. VEHICLES SHOULD BE RESTRICTED TO STABILIZED AREAS TO THE EXTENT PRACTICAL, AND AREAS WHERE FREQUENT MIGRESS/EGRESS IS EXPECTED SHOULD BE STABILIZED.

- 9. MAINTENANCE—TOP DRESSING OF ADDITIONAL STONE SHALL BE APPLIED AS CONDITIONS DEMAND. MUD SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC ROADS, OR ANY SURFACE WHERE RUNOFF IS NOT CHECKED BY SEDIMENT CONTROLS, SHALL BE REMOVED IMMEDIATELY. REMOVAL SHALL BE ACCOMPLISHED BY SCRAPING OR SWEEPING.
- 10. CONTRUCTION ENTRANCES SHALL NOT BE RELIED UPON TO REMOVE MUD FROM VEHICLES AND PREVENT OFF-SITE TRACKING. VEHICLES THAT ENTER AND LEAVE THE CONSTRUCTION-SITE SHALL BE RESTRICTED FROM MUDDY AREAS.
- 11. REMOVAL-- THE ENTRANCE SHALL REMAIN IN PLACE UNTIL THE DISTURBED AREA IS STABILIZED OR REPLACED

**LEGEND** O = IRON PIN FND = IRON PIN SET □ = MONUMENT BOX S = SANITARY MANHOLE (1) = STORM MANHOLE A FIRE HYDRANT = CURB INLET = OFFSET HUB = TELEPHONE PEDESTAL = ELECTRIC BOX E C = CABLE PEDESTAL FLOW DIRECTION ، پیشین SWALE -/-= INLET PROTECTION EXISTING GRADE PROPOSED GRADE OOO = PROP SILT FENCE

	an dada an anaman an a	45 C MARINE PRODUCE VALUE & MARINE VALUE DE LA CONTRACTION DEL CONTRACTION DE LA CON			The second second		<del>minimum menantur</del>
	2	5425 WARNER ROAD - SUITE 12 VALLEY VIEW; OHIO 44125	SITE DETAILS	-	1	1.500.53	
HORIZ. SCALE:	VERT. SCALE:	440-602-9071 FAX 216-369-0259	K. HOWNANIAN OSTER HOMES LLC.	<b>-</b>			
DEALUNI DV. KEG	DATE: 2-27-2014		8260 CAMBDEN CROSSING WAY S/L 38 IN THE		2.20 1		
DRAWN BY. NEG	VAYE	TECH	CAMBDEN CREEK ESTATES PHASE NO.2	<u> </u>			<u> </u>
CHECKED BY: SRL	DRAWING NO.: 20112519	ENGINEERING + SURVEYING	PLAT VOLUME 60, PAGE 15 CONCORD TOWNSHIP	1			-
JOB NO. 20112519	SHEET: 3 OF 3	Civil Engineering + Land Surveying		NO.	DATE	DESCRIPTION	BY