
SILT FENCE:
THIS SEDIMENT BARRIER UTILIZES STANDARD STRENGTH OR EXTRA STRENGTH SYNTHETIC FILTER FABRICS.
IT IS DESIGNED FOR SITUATIONS IN WHICH ONLY SHEET OR OVERLAND FLOWS ARE EXPECTED. SEE DIAGRAM

- 1 THE HEIGHT OF A SILT FENCE SHALL NOT EXCEED 36 INCHES (HIGHER FENCES MAY IMPOUND VOLUMES OF WATER SUFFICIENT TO CAUSE FAILURE OF THE STRUCTURE.)
- 2 THE FILTER FABRIC SHALL BE PURCHASED IN A CONTINUOUS ROLL CUT TO THE LENGTH OF THE BARRIER TO AVOID THE USE OF JOINT, WHEN JOINTS ARE NECESSARY, FILTER CLOTH SHALL BE SPLICED TOGETHER ONLY AT A SUPPORT POST, WITH A MINIMUM 6-INCH OVERLAP, AND SECURELY SEALED.
- 3 POSTS SHALL BE SPACED A MAXIMUM OF 10 FEET APART AT THE BARRIER LOCATION AND DRIVEN SECURELY INTO THE GROUND (MINIMUM OF 12 INCHES) WHEN EXTRA STRENGTH FABRIC IS USED WITHOUT THE WIRE SUPPORT FENCE, POST SPACING SHALL NOT EXCEED 6 FEET.
- 4 A TRENCH SHALL BE EXCAVATED APPROXIMATELY 4 INCHES WIDE AND 4 INCHES DEEP ALONG THE LINE OF POSTS AND UPSLOPED FROM THE BARRIER.
- 5 WHEN STANDARD STRENGTH FILTER FABRIC IS USED, A WIRE WESH SUPPORT FENCE SHALL BE FASTENED SECURELY TO THE UPSLOPE SIDE OF THE POSTS USING HEAVY DUTY WIRE STAPLES AT LEAST 1 INCH LONG, TIE WIRES OF HOG RINGS. THE WIRE SHALL EXTEND INTO THE TRENCH A MINIMUM OF 2 INCHES AND SHALL NOT EXTEND MORE THAN 36 INCHES ABOVE THE ORIGINAL GROUND SURFACE.
- 6 THE STANDARD STRENGTH FILTER FABRIC SHALL BE STAPLED OR WIRED TO THE FENCE, AND 8 INCHES OF THE FABRIC SHALL BE EXTENDED INTO THE TRENCH. THE FABRIC SHALL NO EXCEED MORE THAN 36 INCHES ABOVE THE ORIGINAL GROUND SURFACE. FILTER FABRIC SHALL NOT BE STAPLED TO THE EXISTING TREES.


 7 WHEN EXTRA STRENGTH FILTER FABRIC AND CLOSER POST SPACING ARE USED, THE WIRE MESH SUPPORT FENCE MAY SE EXIMINATED. IN SUCH CASE, THE FILTER FABRIC IS STAPLED OR WIRED DIRECTLY TO THE POSTS WITH ALL OTHER PROVISIONS OF ITEM NO. 5 APPLYING.
- 8 THE TRENCH SHALL BE BACK FILLED AND SOIL COMPACTED OVER THE FILTER FABRIC.
- 9 SILT FENCES SHALL BE REMOVED WHEN THEY HAVE SERVED THEIR USEFUL PURPOSE, BUT NOT BEFORE THE UPSLOPE AREA HAS BEEN PERMANENTLY STABILIZED.

MAINTENANCE 1 SET FENCES AND FILTER BARRIERS SHALL BE INSPECTED IMMEDIATELY AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL. ANY REQUIRED REPAIRS SHALL BE MADE IMMEDIATELY.

- 2 SHOULD THE FABRIC ON A SILT FENCE OF FILTER BARRIER DECOMPOSE OR BECOME INEFFECTIVE PRIOR TO THE END OF THE EXPECTED USABLE LIFE AND THE BARRIER IS STILL NECESSARY, THE FABRIC SHALL BE REPLACED PROMPTLY.
- 3 SEDIMENT DEPOSITS SHOULD BE REMOVED AFTER EACH STORM EVENT. THEY MUST BE REMOVED WHEN DEPOSITS REACH APPROXIMATELY DNE-HALF THE HEIGHT OF THE BARRIER.
- 4 ANY SEDIMENT DEPOSITS REMAINING IN PLACE AFTER THE SLIT FENCE OR FILTER BARRIER IS NO LONGER REQUIRED SHALL BE DRESSED TO CONFORM WITH THE EXISTING GRADE, PREPARED AND SEEDED.




CONCRETE WASHOUT PR NOT TO SCALE



3. Attach the filter fabric to the wire fence and extend it into the trench.


4. Back fill and compact the excavated soil.



2

Filter Fabric-Extension of fabric and wire into the trench.

NOT TO SCALE



- DIVERSION SHALL BE COMPACTED BY TRAVERSING WITH TRACKED EARTH MOVING EQUIPMENT.
- DIVERSIONS SHALL NOT BE BREACHED OR LOWERED TO ALLOW CONSTRUCTION TRAFFIC TO CROSS; INSTEAD THE TOP WIDTH MAY BE MADE WIDER AND SIDE SLOPES MADE FLATTER THAN SPECIFIED ABOVE.
- DIVERSIONS SHALL BE STABILIZED WITH VEGETATION AND CHECK DAMS OR THE FOLLOWING TREATMENTS:

PERMINENT DIVERS	ON STABILIZATION	TREATMENT	
DIVERSION SLOPE	< 2 ACRES	2 TO 5 ACRES	5 TO 10 ACRES
0 3%	MATTING	MATTING	MATTING
3 - 5%	MATTING	MATTING	MATTING
5 - 8%	MATTING	MATTING	MATTING
8 - 20%	MATTING	MATTING	ENGINEERED


DIVERSIONS WITH STEEPER SLOPES OR GREATER DRAINAGE AREAS ARE BEYOND THE SCOPE OF THIS STANDARD AND MUST BE DESIGNED FOR STABILITY.

SEED, STRAW AND MATTING USED SHALL MEET THE SPECIFICATIONS FOR TEMPORARY SEEDING, MULCHING AND MATTING.

SPECIFICATIONS FOR TEMPORARY DIVERSION DITCH

Maintenance

The contractor shall inspect the erosion and sediment controls every seven (7) days or within 24 hours of a 0.5" or greater rainfall event.



PROPERLY INSTALLED COMBINATION BARRIER (Cross <u>Section</u> NOT TO SCALE






(1) EXCAVATE THE TRENCH (2) INSTALL AND STAKE STRAW BALES * Trench shall be wide enough for bole plus silt fence.





(4) BACK FILL AND COMPACT THE EXCAVATED SOIL.

COMBINATION SEDIMENT BARRIER NOT TO SCALE



PLAN VIEW STONE CONSTRUCTION ENTRANC

NOT TO SCALE

SECTION B-B

HESS & ASSOCIATES ENGINEERING INC. 12121 KINSMAN ROAD NEWBURY, OHIO 44065

Telephone: (440) 564-8008 Fax: (440) 564-8176

PREPARED UNDER THE SUPERVISION OF:



REVISIONS

Plan Jr. Property Sediment Control P AILS Road of Oh Fony Debevc, Jr. I d Erosion and Sec DETAILS

State

County,

Site Address Parcel ID #01A0480000260 South Madison Road Madison Twp. Lake County - State of Ohio

bbreviated

Prepared For. Tany Debevo, Jr. 652 N. Creek Road Painesville, OH 44077

HESS Project #10-021 DESIGNED BY: MT DRAWN BY : CHECKED BY: : 8/2010 : NONE H. DATE SCALE

NOT TO SCALE