



Construction Entrance Detail



Silt Fence Detail



S/L 26

LAKE TERRACE ESTATES NO. 3
PROPOSED HOUSE
F.G. 630.14

GENERAL NOTES:

1. BENCHMARK - EX. HYDRANT, TOP OF FLANGE
ELEVATION = 632.06
LAKE TERRACE/BEACHFRONT INTERSECTION
2. SIDEWALK TO BE 4' WIDE, 4" THICK AND 6" THICK
AT DRIVES.
3. DRIVEWAY APRON TO BE 6" THICK CONCRETE.
4. ALL DOWN SPOUTS TO BE OUTLETED TO SPLASH
BLOCKS.
5. CONTRACTOR RESPONSIBLE FOR CONTACTING THE OHIO
UTILITY PROTECTION SERVICE 1 (800) 362-2764 AND
ALL UTILITY COMPANIES A MINIMUM OF 48 HOURS PRIOR
TO CONSTRUCTION.
6. THE LOCATION BOTH HORIZONTAL AND VERTICAL OF
EXISTING UNDERGROUND UTILITIES SHOWN HEREON, HAVE
BEEN OBTAINED BY A DILIGENT AND COMPREHENSIVE
SEARCH OF AVAILABLE RECORDS. VERIFICATION BY FIELD
OBSERVATION HAS BEEN CONDUCTED WHERE PRACTICAL,
HOWEVER, OXBOW ENGINEERING, INC. DOES NOT GUARANTEE
THE COMPLETENESS, NOR ACCURACY THEREOF.
7. CONTRACTOR SHALL VERIFY ELEVATIONS OF LATERAL
INVERTS IN THE FIELD PRIOR TO FOUNDATION EXCAVATION.
8. EROSION AND SEDIMENT-CONTROL PRACTICES TO BE
INSTALLED AS DESCRIBED IN THE RAIN WATER LAND
DEVELOPMENT MANUAL AS DIRECTED BY THE LAKE
COUNTY SOIL AND WATER CONSERVATION DISTRICT.
9. DISTURBED AREAS OF THE SITE THAT ARE TO REMAIN
IDLE FOR MORE THAN THIRTY (30) DAYS SHALL BE
PROPERLY SEEDED AND STRAW MULCHED WITHIN SEVEN
(7) DAYS OF COMPLETION OF INITIAL GRADING. TEMPORARY
SEEDING AND MULCHING OF A THIRTY (30) FOOT STRIP
OF THE ENTIRE FRONT OF THE LOT SHALL BE MAINTAINED
ON THE SITE ONCE INITIAL GRADING IS COMPLETE.
10. STRAW-MULCH SHALL BE APPLIED AT A RATE OF 1
BALE PER EVERY TEN (10) FEET OF CURB, AT A WIDTH
OF THIRTY (30) FEET OF THE ENTIRE LENGTH OF THE LOT.

CURVE	LENGTH	RADIUS	TANGENT	CHORD	BEARING	DELTA
C1	22.96'	120.58'	11.51'	22.92'	S22°31'17"W	10°54'29"
C2	86.57'	254.13'	43.71'	86.15'	N18°13'00"E	19°31'03"
C3	35.86'	25.00'	21.80'	32.86'	S49°32'56"W	82°10'55"

Stormwater Management Plan


As shown and/or

By R. GILLS, P.E.

County Drainage Engineer

By L.S. Date 5/4/05

LYNN M. EGENSERGER P.E. E-53262



SITE PLAN
LAKE TERRACE ESTATES NO. 2
SUBLOT 25
PAINESVILLE TOWNSHIP - LAKE COUNTY - OHIO

oxbow

Engineering, Inc.
10 York Road, Suite 201, Painesville, Ohio 44077
Phone (440) 332-8660 Fax (440) 332-8108
www.oxbowinc.com

