



REVISIONS	BY

Barrington
CONSULTING GROUP, INC.
9114 TYLER BLVD., MENTOR, OHIO 44060
PHONE 440.205.1260 FAX 440.205.1262
BCG@BarringtonCGI.com




SITE PLAN
SIL 198 OUTRIGGER COVE, PAINESVILLE TWP. OH. 44077
LAKE ERIE SHORES PH. 3 VOL. 48 PG. 4
CANTERBURY HOMES, INC.

DRAWN	WSO
CHECKED	DWN
DATE	JUNE 09, 2005
SCALE	1" = 20'
JOB NO.	04107-198
SHEET	1/2
OF	SHEETS



Barrington
CONSULTING GROUP, INC.

By *D.S.* Date *6/21/05*



- GENERAL NOTES:**
1. BENCHMARK - TOP STEM OF EXISTING FIRE HYDRANT LOCATED IN FRONT SUBLOT 244, ELEVATION = 623.66.
 2. DRIVEWAY APRON TO BE 6" THICK CONCRETE.
 3. ALL DOWNSPOUTS TO BE OUTLETED TO SPLASH BLOCKS.
 4. CONTRACTOR RESPONSIBLE FOR CONTACTING THE OHIO UTILITY PROTECTION SERVICE (1.800.362.2764) AND ALL UTILITY COMPANIES A MINIMUM OF 48 HOURS PRIOR TO CONSTRUCTION.
 5. THE LOCATION BOTH HORIZONTAL AND VERTICAL OF EXISTING UNDERGROUND UTILITIES SHOWN HEREON, HAVE BEEN OBTAINED BY A DILIGENT AND COMPREHENSIVE SEARCH OF AVAILABLE RECORDS. VERIFICATION BY FIELD OBSERVATION HAS BEEN CONDUCTED WHERE PRACTICAL, HOWEVER, BARRINGTON CONSULTING GROUP, INC. DOES NOT GUARANTEE THE COMPLETENESS, NOR ACCURACY THEREOF.
 6. CONTRACTOR SHALL VERIFY ELEVATIONS OF LATERAL INVERTS IN THE FIELD PRIOR TO FOUNDATION EXCAVATION.
 7. SEE SHEET 2 FOR EROSION AND SEDIMENT-CONTROL PLAN
 8. SEE SHEET 2 FOR SEEDING INFORMATION

CERTIFICATION:


I THE UNDERSIGNED HEREBY CERTIFIES THAT THIS TOPOGRAPHY INDICATED BY 1 FOOT CONTOURS AND ELEVATION SHOWN HEREON REPRESENTS AN ACTUAL SURVEY MADE BY ME ON THE 12th DAY OF NOVEMBER, 2004 AND THE ELEVATIONS WERE TAKEN AT AN APPROPRIATE INTERVAL AND AS OF THAT DAY THEY EXISTED AS INDICATED HEREON.

I HEREBY CERTIFY THAT THIS PLAN WAS PREPARED BY ME AND IS CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF

David W. Novak
DAVID W. NOVAK, P.S. No. 7507

APPROVED
Painesville Township
Zoning Department
2005/19/4

EX. SANITARY MH. #3 RIM=621.32 INV.=607.76	EX. STORM MH. #4 RIM=621.20 INV.=612.99	EX. STORM MH. #5 RIM=621.49 INV.=613.37
EX. STORM MH. #3A RIM=621.08 INV.=616.74	EX. STORM INLET. #4 RIM=622.23 INV.=618.50	



W:\2004\04\10704\107-198.dwg 06/09/2005 07:00:09 AM, Copying: Barrington Consulting Group