

## Example

### Erosion and Sediment Control Site Plan SIL #41 of the Conservation Hills Subdivision Concord Township, Ohio

#### Erosion and Sediment Control Schedule

##### Ingress-Exgress

A stone access drive complete with under lying geotextile fabric (20 feet wide and 50 feet long) for ingress and egress at the site shall be installed. This drive shall be the only entrance and exit to the site.

##### Silt Fence

All silt fence shall be installed prior to any earthwork activities at the site in locations shown on the site plan as well as along the front of any lot that slopes towards the street.

##### Temporary Seeding

Disturbed areas of the site that are to remain idle for more than twenty (20) days shall be properly seeded and straw mulched within seven (7) days of completion of initial grading.

Temporary seeding and mulching of a thirty (30) foot strip of the entire front of the site shall be maintained on the site once initial grading is complete.

Stabilization of critical areas within fifty (50) feet of any stream or wetland shall be complete within two (2) days of the disturbance date if the site is to remain inactive for longer than fourteen (14) days.

##### Mulching

Straw mulch shall be applied at a rate of 1 bale per every ten (10) feet of curb, at a width of thirty (30) feet of the entire length of the curb. Wood chips may also be used but must be spread at a minimum depth of four inches over the thirty-foot width and must be accompanied by a properly installed silt fence.

##### Maintenance

Erosion and sediment controls shall be inspected every seven (7) days or within 24 hours of a 0.5" or greater rainfall event. Necessary repairs shall be made at this time.

##### Notes:

All general sediment control specifications, applications, and timetables are the responsibility of the Ohio Department of Natural Resources' Bureau of Water and Soil Conservation. The specific requirements of the county, state, and local government, and the specific requirements of the developer, shall take precedence over those of the county in all cases.

##### Lake County Soil & Water Conservation District

##### Conservation Disturbance


##### Site Plan

Slotted construction entrance with underlain filter fabric. Temporary seeding and mulching of all disturbed areas (see details on sample sheet.)

Storm sewer inlet protection for rear yard drains and catch basins

Temporary seeding within 50 feet of any stream or wetland (as necessary)

##### Silt fencing (where necessary)



**SLOTTED FENCE IN GATE**  
**TEMP. SEEDING & MULCHING**  
**CONSTRUCTION ENTRANCE WITH**  
**UNDER LAIN FILTER FABRIC**

#### Slotted construction entrance with underlain filter fabric

Temporary seeding and mulching of all disturbed areas (see details on sample sheet.)

Storm sewer inlet protection for rear yard drains and catch basins

Temporary seeding within 50 feet of any stream or wetland (as necessary)

##### Silt fencing (where necessary)

