

GENERAL NOTES:

- 1. BENCHMARK MONUMENT BOX CENTER OF CUI-DE-SAC ELEVATION = 688.74
- 2. DRIVEWAY APRON TO BE 6" THICK CONCRETE.
- 3. ALL DOWN SPOUTS TO BE OUTLETTED TO SPLASH BLOCKS.
- 4. CONTRACTOR RESPONSIBLE FOR CONTACTING THE OHIO UTILITY PROTECTION SERVICE 1 (800) 362-2764 AND ALL UTILITY COMPANIES A MINIMUM OF 48 HOURS PRIOR TO CONSTRUCTION.
- 5. THE LOCATION BOTH HORIZONTAL AND VERTICAL OF EXISTING UNDERGROUND UTILITIES SHOWN HEREON, HAVE BEEN OBTAINED BY A DILIGENT AND COMPREHENSIVE SEARCH OF AVAILABLE RECORDS. VERIFICATION BY FIELD OBSERVATION HAS BEEN CONDUCTED WHERE PRACTICAL. HOWEVER, OXBOW ENGINEERING, INC. DOES NOT GUARANTEE THE COMPLETENESS, NOR ACCURACY THEREOF.
- 6. CONTRACTOR SHALL VERIFY ELEVATIONS OF LATERAL INVERTS IN THE FIELD PRIOR TO FOUNDATION EXCAVATION.
- 7. EROSION AND SEDIMENT-CONTROL PRACTICES TO BE INSTALLED AS DESCRIBED IN THE RAIN WATER LAND DEVELOPMENT MANUAL AS DIRECTED BY THE LAKE COUNTY SOIL AND WATER CONSERVATION DISTRICT.
- 8. DISTURBED AREAS OF THE SITE THAT ARE TO REMAIN IDLE FOR MORE THAN THIRTY (30) DAYS SHALL BE PROPERLY SEEDED AND STRAW MULCHED WITHIN SEVEN (7) DAYS OF COMPLETION OF INITIAL GRADING. TEMPORARY SEEDING AND MULCHING OF A THIRTY (30) FOOT STRIP OF THE ENTIRE FRONT OF THE LOT SHALL BE MAINTAINED ON THE SITE ONCE INITIAL GRADING IS COMPLETE.

(C1) R = 74.00L = 62.69C = 60.86... KOVED $\Delta = 48'32'00''$ LINES & SET BACK N 68'16'05" E YRY TOWNSHIP ZON'NG RMIT NO. 77.31

YONING INSPECTOR

Onding Plan Approved Thown and/or noted ⊿ES R. GILLS, Γ 🗆 Lake County Engineer

TE OF Frank E. Walland S-7556

FRANK E. WALLAND, P.S. NO. 7556

SITE PLAN LORETO LANDINGS SUBLOT 28	
---	--

[2]

രമ്പിനുപ്പു വമരം