

# TRAFFIC CONTROL QUANTITIES

CALCULATIONS		MADE BY _____ DATE _____	CHECKED _____ DATE _____	FHWA	STATE	PROJECT
5	OHIO					(106 171)
LAKE COUNTY LAK-2-0.00						

\* QUANTITIES CARRIED TO SHEET No. 116

## GROUND MOUNTED SIGNS

REF. NO.	STATION	SIDE	CODE	SIZE	GROUND MOUNTED SIGN SUPPORTS														REMOVAL OF GRD. MTD. SIGN AND STORAGE	REMOVAL OF GRD. MTD. MAJOR SIGN AND STORAGE	REMOVAL OF GRD. MTD. BEAM SUPPORT	REMOVAL OF GRD. MTD. POST SUPPORT	
					SIGNS		ONE WAY SUPPORT NO. POST	NO. 3 POST	NO. 4 POST	S4 X 7.7	W6 X 9	W10 X 12	W8 X 18	CONCRETE FOR EMBEDDED FOUNDATION	BREAKAWAY BEAM CONNECTION	REMOVAL OF GRD. MTD. SIGN AND STORAGE	REMOVAL OF GRD. MTD. MAJOR SIGN AND STORAGE	REMOVAL OF GRD. MTD. BEAM SUPPORT					REMOVAL OF GRD. MTD. POST SUPPORT
					FLAT SHEET	EXTRU. SHEET																	
CITY OF EASTLAKE (CONT'D)																							
145	265+00	C-4R	R-31J-42	3.5x2.5	8.75														2				
		C-4L	R-31J-42	3.5x2.5	8.75														2				
146	267+10	C-4R	R-41A-36	3.0x2.0	6.0														1				
146A	267+10	C-4L	R-41A-36	3.0x2.0	6.0														1				
147	268+00	C-4	N-29-30	2.5x2.5	6.25														1				
			N-15-30	2.5x.67	1.67														1				
147A	268+25	C-4R																	1				
		C-4L																	1				
148	268+50	C-4R	R-41B-36	3.0x3.0	9.0	15	14												2				
			R-43R-36	3.0x1.0	3.0																		
			R-43L-36	3.0x1.0	3.0																		
			R-31J-42	3.5x2.5	8.75														2				
		C-4L	R-41B-36	3.0x3.0	9.0	15	14																
			R-43R-36	3.0x1.0	3.0																		
			R-43L-36	3.0x1.0	3.0																		
			R-31J-42	3.5x2.5	8.75																		
149	229+50	SR.91	M-17-24	2.0x1.0	2.0														1				
			M-2-24-2	2.0x2.0	4.0																		
151A	240+00	SR.91L	R-31FF-48	4.0x2.5	10.0														2				
151B	240+50	SR.91R	R-31FF-48	4.0x2.5	10.0														2				
151C	243+60	SR.91L	R-31FF-48	4.0x2.5	10.0														2				
151D	244+25	SR.91R	R-31FF-48	4.0x2.5	10.0														2				
152	244+60	SR.91																	1				
154	248+00	SR.91																	1				
156	251+80	SR.91	M-17-24	2.0x1.0	2.0														1				
			M-2-24-2	2.0x2.0	4.0														1				
158	303+50	EB																	1				
158A	302+25	EB	GF-72	6.0x5.0		30.0				16-17			0.54	2					1				
159	303+85	WB																	1				
160	303+90	WB																	1				
161	304+15	EB																	1				
162	304+10	EB																	1				
162A	304+50	WB	GF-72	6.0x5.0		30.0				17-18			0.54	2			1	2					
165	309+40	WB	GN	11.0x3.5		38.5							2.20	2			1	2					
172	1+00	D-1	W-50R-48	4.0x4.0	16.0														1				
	2+50																		1				
172A	301+80	WB	W-50R-48	4.0x4.0	16.0														1				
173	7+50	D-1	R-150	2.5x2.5	6.25					13.0									2				
174	307+00	D-2	W-97-48	4.0x5.0	20.0														1				
175	2+50	D-2R	R-41A-36	3.0x2.0	6.0					12.5									1				
		D-2L	R-41A-36	3.0x2.0	6.0					12.5									1				
176	3+00	D-2	W-32-96	8.0x4.0		32.0							0.54	2			1	2	2				
177	6+30	D-2	R-41B-36	3.0x3.0	9.0														2				
			R-1-48	4.0x4.0	16.0					14													
177A	6+10	D-2	R-41B-36	3.0x3.0	9.0														2				
			R-43R-36	3.0x1.0	3.0																		
			R-43L-36	3.0x1.0	3.0																		
			R-121-36	3.0x3.0	9.0																		
189	7+00	D-7	R-41A-36	3.0x2.0	6.0					12.5									2				
190	7+00	D-7	R-41A-36	3.0x2.0	6.0					12.5									1				
193	110+40	VINE ST	M-17-24	2.0x1.0	2.0					13.5									1				
			M-2-24-2	2.0x2.0	4.0														1				
TOTALS - CITY OF EASTLAKE					499.39	309 *	60-No.3 15-No.4	526.5	284	209	66	43		6.88	18			62	6 *	12 *	83		

GROUND MOUNTED SIGN QUANTITIES