

ITEM 621-PAVEMENT MARKINGS

614 SUB-SUMMARY

BRIDGE	STATIONING (FROM - TO) (SIDE)	4" EDGE LINE		4" LANE LINE	4" DOUBLE YELLOW CENTER LINE	8" CHANNELIZING LINE	TEMPORARY LANE LINES, CLASS II	TEMPORARY CENTER LINES, CLASS II	TEMPORARY CHANNELIZING LINES, CLASS I
		WHITE	YELLOW						
		MILE				LIN. FT.	MILE	MILE	LIN. FT.
LAK-2-1.80 R	178+60 TO 187+70 R 183+00 TO 203+90 R 187+60 TO 203+50 R 192+10 TO 199+50 R	0.31	0.14	0.17 0.40					
LAK-2-1.80 L	187+95 TO 204+15 L 187+95 TO 208+85 L 192+35 TO 199+75 L 204+15 TO 213+25 L	0.31	0.14	0.40 0.14 0.17					
LAK-2-3.63 R	273+10 TO 300+45 R 273+65 TO 284+25 R 285+50 TO 298+70 R 288+70 TO 296+10 R <u>RAMP C-3</u> 276+85 TO 282+20 R 276+90 TO 279+70 L	0.25	0.14	0.52 0.20 0.14					
LAK-2-3.63 L	286+75 TO 296+80 L 286+75 TO 299+00 L 289+05 TO 296+45 L 296+80 TO 300+50 L 298+00 TO 304+15 L 299+60 TO 304+15 L	0.23	0.14	0.19 0.14 0.12		280			
LAK-2-5.42	22+75 TO 24+25 R 25+00 TO 33+60 R 26+50 TO 36+50 L 27+00 TO 27+35 R 27+00 TO 33+00 L 27+00 TO 33+60 R 27+35 TO 33+60 L	0.11 0.13	0.01 0.13	0.03 0.16 0.19					
LAK-2-10.29	28+42 TO 31+42 C				0.06				
SUB-TOTALS		1.53	0.82	3.11	0.06	650	3.11	0.06	650
* TOTALS		2.35							

THESE TOTALS HAVE BEEN TRANSFERRED TO THE GENERAL SUMMARY (SEE SHEET NO. 27).

TRAFFIC CONTROL NOTES

PAVEMENT MARKINGS

THIS WORK SHALL CONSIST OF FURNISHING AND APPLYING PAVEMENT MARKINGS IN ACCORDANCE WITH ITEM 621 OF THE O.D.O.T. SPECIFICATIONS. THESE PAVEMENT MARKINGS SHALL BE APPLIED AT THE SAME LOCATIONS AND IN THE SAME MANNER AS THE EXISTING PAVEMENT MARKINGS PRIOR TO THE BEGINNING OF CONSTRUCTION. LOCATION, TYPES, AND QUANTITIES CAN BE FOUND IN THE SUB-SUMMARY CHART, SEE THIS SHEET.

LAK-2-(1.80/10.29)