

C:\Project\lak\roadway\sheet\13486\13486C0402.dgn 6/24/2008 2:06:06 PM diozity

REF. NO.	SHEET NO.	STATION		SIDE	202					601					603					609					
					PAVEMENT REMOVED	WALK REMOVED	CURB REMOVED	PIPE REMOVED, 24" AND UNDER	PIPE REMOVED, OVER 24"	MANHOLE REMOVED	CATCH BASIN REMOVED	PAVED GUTTER, TYPE 1-6	6" CONDUIT, TYPE C	6" CONDUIT, TYPE F	12" CONDUIT, TYPE B	12" CONDUIT, TYPE C	15" CONDUIT, TYPE B	18" CONDUIT, TYPE B	24" CONDUIT, TYPE B	27" CONDUIT, TYPE B	CURB, TYPE 6				
					SO YD	SQ FT	FT	FT	FT	EACH	EACH	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT				
		FROM	TO																						
R1	650	119+00	15+80 (E. 365TH)	LT	75																				
R2	650	119+00	124+00	RT	202																				
R3	650	15+80 (E. 365TH)	124+00	LT	740																				
R4	650	119+00	124+00	RT/LT	466																				
R5	650	119+00	120+00	LT		614																			
R6	650	120+38	124+00	LT		1410																			
R7	650	119+00	124+00	RT		2057																			
R8	650	119+70	120+08	RT			12														10				
R9	650	121+36	121+70	RT			11														7				
R10	650	119+67	120+08	RT	38																				
R11	650	121+38	121+92	RT	48																				
RD1	650		119+38	RT				12																	
RD2	650		120+06	LT				19																	
RD3	650	120+06	120+40	LT				35																	
RD4	650	122+24	123+05	LT				81																	
RD5	650	123+28	123+57	LT				37																	
RD6	650	123+57	123+75	LT				20																	
RD7	650	123+14	123+27	RT				14																	
RD8	650	120+54	122+29	RT				171	8	1															
PG1	650	123+38.26	123+68.59	RT							31														
D1	650		119+36	RT								6			6										
D2	650		120+06	LT																					
D3	650	120+06	120+07	LT											19										
D4	650	120+07	120+37	LT											29										
D5	650	120+54	122+25	RT															171						
D6	650	122+25	122+28	RT																8					
D7	650	122+15	122+24	LT												16									
D8	650	122+24	122+73	LT																					
D9	650	122+58	122+73	LT																					
D10	650	122+73	123+05	LT																					
D11	650	122+73	123+04	LT																					
D12	650	123+23	123+28	RT																					
D13	650	123+15	123+29	RT																					
<b>TOTALS CARRIED TO VINE ST. SUB-SUMMARIES</b>					1483	4081	23	389	8	1	7	31	6	110	133	16	49	32	171	8	17				

ESTIMATED QUANTITIES - VINE STREET (S.R. 640)  
STA. 119+00.00 TO STA. 124+00.00

LAK-2-3.32

CALCULATED  
EMF  
CHECKED  
AOB

652  
1679