

REF. NO.	SHEET NO.	STATION		SIDE	202					603					604					605	608		609				
					PAVEMENT REMOVED	WALK REMOVED	PIPE REMOVED, 24" AND UNDER	MANHOLE REMOVED	CATCH BASIN REMOVED	GUARDRAIL REMOVED	6" CONDUIT, TYPE F	12" CONDUIT, TYPE B	12" CONDUIT, TYPE C	15" CONDUIT, TYPE B	15" CONDUIT, TYPE C	CATCH BASIN, NO. 3	CATCH BASIN, NO. 3A	CATCH BASIN, NO. 6	CATCH BASIN, NO. 2-2B	MANHOLE, NO. 3	MANHOLE ADJUSTED TO GRADE	MONUMENT ASSEMBLY	6" BASE PIPE UNDERDRAIN WITH FABRIC WRAP	4" CONCRETE WALK	CURB RAMP	CURB, TYPE 2-A	CURB, TYPE 6
FROM	TO																										
R1	676	28+80	31+00	LT/RT	723																						
R2	676	30+11	31+00	RT					97																		
RD1	676	27+44	30+45	LT			289	1																			
D1	676	27+44	28+93	LT									153					1									
D2	676		28+96	LT									23			1											
D3	676	28+85	28+96	RT/LT							29				1												
D4	676	28+96	29+50	LT							52					1											
D5	676	28+93	30+45	LT														1		1							
D6	676		30+45	RT/LT									47					1									
M1	676		29+11	C/L																1							
C1	676	28+80	31+00	LT						30											190		220				
C2	676	28+80	31+00	RT						20											200		220				
R1	677	31+00	33+75	RT/LT	1180																						
R2	677		32+70	LT	101																						
R3	677	31+00	31+80	RT					89																		
R4	677	31+89	32+41	RT	78																						
R5	677	32+94	33+32	RT	105																						
R6	677	32+83	33+72	LT		1187																					
R7	677	33+39	33+65	RT		145																					
RD1	677	32+38	30+45	LT			181	1																			
RD2	677		33+35	LT/RT			47	1																			
RD3	677	33+36	33+72	RT			37	1																			
D1	677	30+45	32+30	LT									167			1											
D2	677	33+35	33+40	LT/RT							60																
D3	677	33+40	33+67	RT							27					1											
D4	677	33+67	132+53 (VINE ST)	RT							6							1									
AJ1	677		32+03	RT																1							
AJ2	677		33+38	RT																1							
AJ3	677		33+53	RT																1							
W1	677	32+89	33+72	LT																		997	2				
W2	677	33+35	33+56	RT																		135	1				
C1	677	31+00	33+72	LT						30												265		295			
C2	677	31+00	33+72	RT						10												326		336			
C3	677	32+36	32+47	LT																				65			
C4	677	32+89	33+14	LT																				66			
TOTALS CARRIED TO VINE ST. SUB-SUMMARIES					2187	1332	554	1	3	186	90	174	190	47	289	1	3	1	1	3	3	1	981	1132	3	1071	131

CALCULATED
 EMF
 CHECKED
 ABS
ESTIMATED QUANTITIES - LAKELAND BLVD.
LAK - 2 - 3.32
 678
 1679

j:\LAK\13486\roadway\sheets\13486GQ430.dgn 03-JUL-2008 3:50PM lntn