SUPERELEVATION TABLE

P.I. STA. 205+17.35 | Dc = 23° 43′ 02.65″

REMARKS	OUTSIDE EDGE - ELEVATION	ELEVATION CORRECTION	CROSS SLOPE	TRANSITION RATE	WIDTH	CENTERLINE OF LANES ELEVATION	ELEVATION CORRECTION	CROSS SLOPE	TRANSITION RATE	WIDTH	INSIDE EDGE (PROFILE GRADE) ELEVATION	OFFSET	STATION	INSIDE EDGE (PROFILE GRADE) OFFSET	ELEVATION	CENTERLINE OF LANES WIDTH	TRANSITION RATE	CROSS SLOPE	ELEVATION CORRECTION	ELEVATION	OUTSIDE EDGE - WIDTH	TRANSITION RATE	CROSS SLOPE	ELEVATION CORRECTION	ELEVATION	REMARKS
R.C.	606.48	0.58	0.0160	▲	36.0						605.90	4.50	202+00.00	4.50	605.90						16.0		-0.0160	-0.26	605.64	
	605.89	0.13	0.0036	|	36.0						605.76	4.50	202+45.00	4.50	605.76						16.0	▲	-0.0160	-0.26	605.50	N.C.
	605.82	0.08	0.0022	|	36.0						605.74	4.50	202+50.00	4.50	605.74						16.0	|	-0.0139	-0.22	605.52	
½ LEVEL	605.73	0.00	0.0000	|	36.0						605.73	4.50	202+57.89	4.50	605.73						16.0	|	-0.0107	-0.17	605.56	
	605.44	-0.26	-0.0071	|	36.0						605.70	4.50	202+83.74	4.50	605.70						16.0	|	0.0000	0.00	605.70	½ LEVEL
	605.27	-0.42	-0.0116	▼	36.0						605.69	4.50	203+00.00	4.50	605.69						16.0	|	0.0067	0.11	605.80	
	604.94	-0.80	-0.0255	|	31.4						605.74	4.50	203+50.00	4.50	605.74						16.0	|	0.0274	0.44	606.18	
P.C	605.00	-0.82	-0.0340	▲	24.0						605.82	4.50	203+80.87	4.50	605.82						16.0	|	0.0401	0.64	606.46	P.C
	604.95	-0.94	-0.0393	|	24.0						605.89	4.50	204+00.00	4.50	605.89						16.0	|	0.0480	0.77	606.66	
	604.88	-1.14	-0.0473	|	24.0						606.02	4.50	204+29.00	4.50	606.02						16.0	▼	0.0600	0.96	606.98	F.S.
	604.87	-1.27	-0.0531	|	24.0						606.14	4.50	204+50.00	4.50	606.14						16.0	|	0.0600	0.96	607.10	
F.S.	604.86	-1.44	-0.0600	▼	24.0						606.30	4.50	204+75.00	4.50	606.30						16.0	|	0.0600	0.96	607.26	
	605.05	-1.44	-0.0600	|	24.0						606.49	4.50	205+00.00	4.50	606.49						16.0	|	0.0600	0.96	607.45	
	605.45	-1.44	-0.0600	|	24.0						606.89	4.50	205+50.00	4.50	606.89						16.0	▲	0.0600	0.96	607.85	F.S.
	605.85	-1.44	-0.0600	|	24.0						607.29	4.50	206+00.00	4.50	607.29						16.0	|	0.0416	0.67	607.96	
	606.08	-1.44	-0.0600	|	24.0						607.52	4.50	206+29.34	4.50	607.52						16.0	|	0.0309	0.49	608.01	P.T.
	606.25	-1.44	-0.0600	|	24.0						607.69	5.36	206+50.00	4.50	607.69						16.0	|	0.0234	0.37	608.06	
	606.65	-1.44	-0.0600	|	24.0						608.09	14.03	207+00.00	4.50	608.09						16.0	|	0.0052	0.08	608.17	
	606.76	-1.44	-0.0600	|	24.0						608.20	17.94	207+14.33	4.50	608.20						16.0	▼	0.0000	0.00	608.20	½ LEVEL

CALCULATED DES | CHECKED PSB

SUPERELEVATION TABLE
LOST NATION ROAD, RAMP B/F

LAK-2-3.32

775
1679

g:\project\lak\13486\roadway\sheets\13486CE_LNBF.dgn 7/11/2008 9:10:48 AM dshaner