

REF. NO.	LOCATION				SHEET NO.	ELEV. #1	ELEV. #2	ELEV. #3	ELEV. #4	ELEV. AT OUTLET	603	603	604	605	605	605	FOR INFORMATION ONLY							
	STATION		ROAD	SIDE							6" CONDUIT, TYPE F FOR UNDERDRAIN OUTLETS	6" CONDUIT, TYPE B	PRECAST REINFORCED CONCRETE OUTLET	6" SHALLOW PIPE UNDERDRAIN WITH FABRIC WRAP	6" UNCLASSIFIED PIPE UNDERDRAIN WITH FABRIC WRAP	6" BASE PIPE UNDERDRAIN WITH FABRIC WRAP	OUTLET TO CATCH BASIN	BENDS AND BRANCHES						END CAP
	FROM	TO									FT	FT	EACH	FT	FT	FT	EACH	6" x 6" TEE	6"x6"x6" CROSS	6" x 45° BEND	6" x 45° WYE	6" x 90° BEND	6" x 30° BEND	
U-1	370+10	*374+50	SR 2	LT	884			600.42	599.20	10					430	1						2		1
U-2	370+10	*374+50	SR 2	RT	884			600.61	599.20	10					320	1						2		1
U-3	370+10	*375+79	SR 2	LT	884		599.63		599.00	10			559				1					2		1
U-4	370+10	*375+79	SR 2	RT	884		599.63		599.00	10			559				1					2		1
U-5	370+05	*375+79	SR 2	LT	884		600.92		600.44	14			564					1				2		1
U-6	370+05	*374+50	SR 2	LT	884	601.71			600.90	10					442	1						2		1
U-7	370+05	*375+79	SR 2	LT	884		602.37		602.00	10			564					1				2		1
U-8	370+05	*375+79	SR 2	LT	884	602.47			602.00	10					564	1	2					2		1
U-9	370+05	*375+79	SR 2/RAMP F	RT	884		597.86		597.00	8			574				1			1	1			1
U-10	370+05	*374+50	SR 2/RAMP F	RT	884	598.49			597.00	10					435	1						2		1
U-11	374+60	*375+79	SR 2	LT	884			600.16	599.00	10					109	1	2					2		1
U-12	374+60	*375+79	SR 2	RT	884			600.35	599.00	10					109	1	2					2		1
U-13	374+60	*375+79	SR 2	LT	884	601.71			600.44	10					109							2		1
U-14	373+62	*375+79	SR 2	RT	884		598.33		597.00		29				147				2			1		1
U-15	*375+79	378+11	SR 2	RT	884		598.33		597.00		29		229					2				1		1
U-16	*375+79	376+90	SR 2	LT	884			600.16	599.00	10					101		2					2		1
U-17	*375+79	376+90	SR 2	RT	884			600.16	599.00	10					101		2					2		1
U-18	*377+00	379+30	SR 2	LT	884			600.39	599.10	10					220	1						2		1
U-19	*377+00	379+30	SR 2	RT	884			600.39	599.10	10					220	1						2		1
U-20	*375+79	379+94	SR 2	LT	884		599.63		599.00	10			405					1				2		1
U-21	*375+79	379+79	SR 2	RT	884			599.63	599.00	10			390					1				2		1
U-22	*375+79	380+17	SR 2	LT	884 & 886		600.92		600.44	14			428					2				1		1
U-23	*375+79	376+90	SR 2	LT	884	601.71			600.44	10					102	1						2		1
U-24	*377+00	379+68	SR 2	LT	884	601.94			601.00	10					268	1						2		1
U-25	*375+79	380+37	SR 2	LT	884 & 886		601.29		601.50		23		448					1				2		1
U-26	*375+79	80+23	SR 2/RAMP D	LT	884 & 886		602.37		601.50	8			424				1			1	1			1
U-27	*375+79	80+23	SR 2/RAMP D	LT	884 & 886	603.10			601.50	10			424			1	1			1	1			1
U-28	*378+21	378+92	SR 2	RT	884	599.70			597.00	10					61	1	2					2		1
U-29	*379+02	379+49	SR 2	RT	884	600.12			598.50	10					37	1						2		1
U-30	*378+21	379+54	SR 2	RT	884		599.10		597.00	10			124					1				2		1
U-1	*382+92	387+50	SR 2	LT	886			603.57	602.10	10					448	1	2					2		1
U-2	*382+92	387+50	SR 2	RT	886			603.76	602.10	10					448	1	2					2		1
U-3	*382+92	387+50	SR 2	LT	886		603.04		602.10	10			448						1			2		1
U-4	*382+92	387+50	SR 2	RT	886		603.04		602.10	10			448						1			2		1
U-5	*382+60	387+50	SR 2	RT	886		601.56		600.50	10			480						1			2		1
U-6	*382+60	387+50	SR 2	RT	886	602.16			600.50	10					480	1	2					2		1
U-7	*383+20	387+50	SR 2	LT	886		604.49		603.70	10			420						1			2		1
U-8	*383+20	387+50	SR 2	LT	886	605.28			603.70	10					420	1	2					2		1
U-9	*387+60	392+50	SR 2	LT	886			605.63	603.50	10					480	1	2					2		1
U-10	*387+60	392+50	SR 2	RT	886			605.82	603.50	10					480	1	2					2		1
SHEET TOTAL											374	81	0	7488	0	6641	20	29	0	15	3	74	0	40

\* DENOTES OUTLET LOCATION

CALCULATED  
CAP  
CHECKED  
PSB

UNDERDRAIN DETAILS AND SUBSUMMARY

LAK - 2 - 3.32

932  
1679