SHEET NO.	REFERENCE NO.	LOCATION	STATION	SIDE	CODE	SIZE (INCHES)	630 GROUND MOUNTED SUPPORT, #2 POST	630 GROUND MOUNTED SUPPORT, #3 POST	630 GROUND MOUNTED SUPPORT, #4 POST	630 GROUND MOUNTED SUPPORT, #6 POST	630 ONE WAY SUPPORT, #3 POST	630 STREET NAME SIGN SUPPORT, #2 POST	630 SIGN SUPPORT ASSEMBLY, POLE MOUNTED, AS PER PLAN	630 SIGN SUPPORT ASSEMBLY, BARRIER MOUNTED	630 SIGN, FLAT SHEET	630 SIGN, GROUND MOUNTED EXTRUSHEET	630 SIGN, DOUBLE-FACED, STREET NAME	630 CONCRETE MEDIAN BARRIER SIGN BRACKET	630 REMOVAL OF GROUND MOUNTED SIGN AND REERECTION	630 REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL	630 REMOVAL OF POLE MOUNTED SIGN AND DISPOSAL	630 REMOVAL OF GROUND MOUNTED POST SUPPORT AND REERECTION	630 REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL, AS PER PLAN
							FT	FT	EACH	FT	FT	FT	EACH	EACH	SQ FT	SQ FT	EACH	EACH	EACH	EACH	EACH	EACH	EACH
1135	S-2	LOST NATION	47+25	LT	R2-1-24	24 X 30	13.0								5.0								
	R-1		47+25																	1			1
	R-2		47+45	LT																1			2
	S-3		47+53	LT	W3-3-48	48 X 48		16.5/16.5							16.0								
	R-3		48+00	LT																1			1
	R-10		47+78	RT																1			1
	S-15		47+91	RT	R7-H1A-12	12 X 18	12.0								1.5								
	S-21		47+30	RT	D1-1C	18 X 6						12.5					1						
	S-4		47+98	LT	R7-H1A-12	12 X 18	12.0								1.5								
	R-4		48+56	LT																1			2
	R-9		48+01	RT																1			1
	R-11		48+01	RT																2			1
	S-16		48+03	RT	R5-1-36	36 X 36	13.5/13.5								9.0								
	S-16		48+03	RT	R1-1-30	30 X 30									6.3								
	R-12		48+52	RT																2			1
	S-17		48+53	RT	R5-1-36	36 X 36	13.5/13.5								9.0								
	S-17		48+53	RT	R1-1-30	30 X 30									6.3								
	S-5		48+56	LT	R3-H8BA-30	30 X 30	13.5								6.3								
	R-13		49+03	RT																1			1
	S-18		49+93	RT	R7-H1A-12	12 X 18	13.0								1.5								
	R-14		49+98	RT																1			1
	S-6		50+40	LT	R7-H1A-12	12 X 18	12.0								1.5								
	R-5		50+40	LT																1			1
	R-15		50+54	RT																1			2
	S-19		50+57	RT	R3-H8CG-48	48 X 30		15.0/15.0							10.0								
	S-9		50+63	LT	W4-2R-48	48 X 48							1		16.0								
	R-6		50+90	LT																2			1
	R-17		51+55	LT															7			2	
	S-11		51+69	LT	W9-1R-36	36 X 36							1		9.0								
	S-12		51+98	LT	R3-H8CG-48	48 X 30	13.5/13.5								10.0								
	S-13		52+45	LT	R4-4-36	36 X 30			17.0						7.5								
	S-13		52+45	LT	M4-12-12	12 X 4									0.3								
	S-13		52+45	LT	D11-1-24	24 X 18									3.0								
	S-20		52+76	RT	D11-1-24	24 X 18	16.5								3.0								
	S-20		52+76	RT	M4-11-12	12 X 4									0.3								
	S-20		52+76	RT	M7-2-12	12 X 9									0.8								
	S-14		54+60	LT	R3-H8CG-48	48 X 30	13.5/13.5								10.0								
	S-8	ST. CLAIR	113+26	LT	R3-H8BH-36	36 X 30	13.0/13.0								7.5								
	S-22	ST. CLAIR	114+10	LT	R2-1-24	24 X 30	15.5								5.0								
	S-10	ST. CLAIR	115+10	LT	R12-1-24	24 X 30	15.5								5.0								
	R-7	ST. CLAIR	115+10	LT																2			1
	S-7	ST. CLAIR	115+41	LT	R3-H8BH-36	36 X 30	13.0/13.0								7.5								
TOTALS CARRIED TO SHEET 1085							252.0	63.0	17.0			12.5	2		158.7			1	7	18		2	17

CALCULATED JMM
CHECKED DRJ

LOST NATION RD. GROUND MOUNTED SIGNING SUBSUMMARY

LAK-2-3.32

1084
1679

G:\Project\lak\13486\traffic\sheets\13486TSS010.dgn 6/24/2008 9:30:17 AM djozily