SHEET NUMBER															PARTICIPATION			ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
Office Calcs	1040	1168	1171	1174	1176	1178	1181	1184	1187	1190	1192	1195	1198	1200	I REHAB	II TRAC	III LOCAL						
																						TRAFFIC SIGNALS (CONTINUED)	
						1										1		632	81700	1	EACH	COMBINATION SIGNAL SUPPORT, MISC.: TYPE TC-12.30	1038
																						DESIGN 4 POLE, WITH MAST ARMS TC-81.20 DESIGN 11 AND	
																						DESIGN 1, WITH SIGN SUPPORT TC-12.30 DESIGN 4	
								1								1		632	81700	1	EACH	COMBINATION SIGNAL SUPPORT, MISC.: TYPE TC-12.30	1038
																						DESIGN 5 POLE, WITH MAST ARM TC-81.20 DESIGN 11 AND	
																						SIGN SUPPORT TC-12.30 DESIGN 5	
										1						1		632	81700	1	EACH	COMBINATION SIGNAL SUPPORT, MISC.: TYPE TC-12.30	1038
																						DESIGN 5 POLE, WITH MAST ARM TC-81.20 DESIGN 11 AND	
																						SIGN SUPPORT TC-12.30 DESIGN 5 WITH LUMINAIRE EXTENSION	
			1													1		632	81700	1	EACH	COMBINATION SIGNAL SUPPORT, MISC.: TYPE TC-12.30	1038
																						DESIGN 6 POLE, WITH MAST ARM TC-81.20 DESIGN 2 AND	
																						SIGN SUPPORT TC-12.30 DESIGN 1	
												1				1		632	81700	1	EACH	COMBINATION SIGNAL SUPPORT, MISC.: TYPE TC-12.30	1038
																						DESIGN 6 POLE, WITH MAST ARM TC-81.20 DESIGN 2 AND	
																						SIGN SUPPORT TC-12.30 DESIGN 3	
													1			1		632	81700	1	EACH	COMBINATION SIGNAL SUPPORT, MISC.: TYPE TC-12.30	1038
																						DESIGN 6 POLE, WITH MAST ARM TC-81.20 DESIGN 3 AND	
																						SIGN SUPPORT TC-12.30 DESIGN 1	
							1									1		632	81700	1	EACH	COMBINATION SIGNAL SUPPORT, MISC.: TYPE TC-12.30	1038
																						DESIGN 6 POLE, WITH MAST ARM TC-81.20 DESIGN 4 AND	
																						SIGN SUPPORT TC-12.30 DESIGN 6	
		1														1		632	81700	1	EACH	COMBINATION SIGNAL SUPPORT, MISC.: TYPE TC-12.30	1038
																						DESIGN 6 POLE, WITH MAST ARM TC-81.20 DESIGN 11 AND	
																						SIGN SUPPORT TC-12.30 DESIGN 3	
									1							1		632	81700	1	EACH	COMBINATION SIGNAL SUPPORT, MISC.: LOST NATION POLE P2-1	1038
						1										1		632	82100	1	EACH	STRAIN POLE, TYPE TC-81.10, DESIGN 1	
						2	2	1		2					2	5		632	89802	7	EACH	PEDESTAL, 5', TRANSFORMER BASE	
			1			2	2	4	2	2		3	3		5	14		632	89900	19	EACH	PEDESTAL, 8', TRANSFORMER BASE	
		1	1	1			1	1	1	1		1	1		2	7		632	90100	9	EACH	REMOVAL OF TRAFFIC SIGNAL INSTALLATION	
												1	1		1	1		633	01551	2	EACH	CONTROLLER UNIT, TYPE TS2/A2, WITH CABINET, TYPE TS2, AS PER PLAN	1040
		1	1	1		1	1								1	4		633	01580	5	EACH	CONTROLLER UNIT, TYPE TS2/A2, WITH CABINET, TYPE TS1	
									1	1					1	1		633	01581	2	EACH	CONTROLLER UNIT, TYPE TS2/A2, WITH CABINET, TYPE TS1, AS PER PLAN	1040
								1								1		633	39001	1	EACH	CONTROLLER MASTER, TRAFFIC RESPONSIVE, AS PER PLAN	1040
		1	1	1		1	1	1	1	1		1	1		2	8		633	67000	10	EACH	CABINET RISER	
		1	1	1		1	1	1	1	1		1	1		2	8		633	67100	10	EACH	CABINET FOUNDATION	
		1	1	1								1	1		1	4		633	67200	5	EACH	CONTROLLER WORK PAD	
						1	1	1	1	1					1	4		633	68500	5	EACH	TELEPHONE SERVICE	
						1	1	1	1	1					1	4		633	75000	5	EACH	UNINTERRUPTIBLE POWER SUPPLY (UPS), 1000 WATT	1039
		3	3	4		3	4	4	3	4		3	3		8	26		633	99000	34	EACH	CONTROLLER ITEM, MISC.: PREEMPTION RECEIVING UNIT	1039
		3	3	4		1	1	1	1	1		3	3		5	16		633	99000	21	EACH	CONTROLLER ITEM, MISC.: PREEMPT PHASE SELECTOR	1039
		3	3	4		3	4	4	3	4		3	3		8	26		633	99000	34	EACH	CONTROLLER ITEM, MISC.: PREEMPT CONFIRMATION LIGHT	1040
		1	1	1		1	1	1	1	1		1	1		2	8		633	99000	10	EACH	CONTROLLER ITEM, MISC.: PREEMPTION	1040
		548	478	782		484	1277	1472	687	752		483	623		1896	5690		633	99100	7586	FT	CONTROLLER ITEM, MISC.: PREEMPTION DETECTOR CABLE	1040
		1														1		816	30001	1	EACH	VIDEO DETECTION SYSTEM, AS PER PLAN	1041

CALCULATED DRJ
CHECKED TMD

GENERAL SUMMARY - TRAFFIC SIGNALS

LAK-2-3.32

G:\project\lak\13486\signals\sheets\13486GG105.dgn 9/12/2008 7:27:36 AM djozity