REFERENCE NO.	SHEET NO.	SIDE	ROADWAY	STATION TO STATION	202 PULL BOX REMOVED EA	202 LIGHT TOWER REMOVED, AS PER PLAN EA	202 POWER SERVICE REMOVED, AS PER PLAN EA	202 LIGHT TOWER FOUNDATION REMOVED EA	202 REMOVAL MISC.: UNDERPASS LIGHTING SYSTEM EA	625 CONNECTOR KIT, TYPE II EA	625 CONNECTOR KIT, TYPE III EA	625 CABLE SPLICING KIT EA	625 LIGHT POLE, DECORATIVE, AS PER PLAN EA	625 LIGHT POLE, MISC.: LOW MAST, DESIGN ATLM39 EA	625 LIGHT POLE, MISC.: LOW MAST, DESIGN ATLM20 EA	625 LIGHT POLE, MISC.: LOW MAST, DESIGN ALM35 EA	625 LIGHT POLE, MISC.: LOW MAST, DESIGN ALM15 EA	625 LIGHT POLE ANCHOR BOLTS, MISC.: SET FOR PILASTER OR BARRIER MOUNTED LIGHT POLE EA	625 LIGHT POLE FOUNDATION, 24"x8' DEEP EA	625 MEDIAN LIGHT POLE FOUNDATION, 10' DEEP EA	625 NO. 6 AWG 600 VOLT DISTRIBUTION CABLE FT	625 NO. 1/0 AWG 5000 VOLT DISTRIBUTION CABLE FT	625 NO. 4 AWG 5000 VOLT DISTRIBUTION CABLE FT	625 NO. 2 AWG 5000 VOLT DISTRIBUTION CABLE FT	625 NO. 10 AWG POLE AND BRACKET CABLE FT	625 1-1/2" DUCT CABLE WITH THREE NO. 4 AWG 5000 VOLT CABLES FT	625 1-1/2" DUCT CABLE WITH THREE NO. 2 AWG 5000 VOLT CABLES FT	625 CONDUIT, 1", 725.04 FT	625 CONDUIT, 2", 725.04 FT	625 CONDUIT, 1", 725.05 FT	SEE SHEET 1213 FOR CONTINUATION
VA-21	1244	CL	SR 2	322+85.75						2						1				1					70						
E-4	1244	CL	SR 2	322+85.75-324+24.38																				447	417						
VA-22	1244	CL	SR 2	324+24.38						2						1				1					70						
E-5	1244	CL	SR 2	324+24.38-325+64.14																				450	420						
VA-23	1244	CL	SR 2	325+64.14						2						1				1					70						
E-6	1244	CL	SR 2	325+64.14-326+98.13																				432	402						
VA-24	1244	CL	SR 2	326+98.13						2						1				1					70						
E-7	1244	CL	SR 2	326+98.13-328+34.53																				438	408						
VA-25	1244	CL	SR 2	328+34.53						2						1				1					70						
E-8	1244	CL	SR 2	328+34.53-329+69.16																				441	411						
VA-26	1244	CL	SR 2	329+69.16						2						1				1					70						
E-9	1244	CL	SR 2	328+34.53-330+00.00																				123	93						
E-10	1244	CL/LT	SR 2	320+08.31-320+27.50																				381							
PB-8V	1244	LT	RAMP D	320+27.50								3																			
VA-18	1244	LT	RAMP D	319+40.02						2				1					1						78						
E-11	1244	LT	RAMP D	319+40.02-320+27.50																								92			
E-12	1244	LT	RAMP D	320+27.50-323+07.32																								285			
VA-20	1244	LT	RAMP D	323+07.32						2				1					1						78						
VB-8	1244	RT	RAMP A	319+46.33						2					1				1						40						
E-13	1244	RT	RAMP A	319+46.33-321+66.59																								224			
PB-11V	1244	RT	RAMP A	321+66.59								3																			
E-14	1244	RT/LT	RAMP A	321+66.59-321+66.59																				159							
PB-12V	1244	LT	RAMP A	321+66.59								3																			
E-15	1244	LT	RAMP A	321+66.59-321+47.85																								30			
VB-9	1244	RT	RAMP A	321+47.85						2				1					1						78						
E-16	1244	RT/RT	RAMP A/SR 2	321+66.59-325+08.47																								347			
VB-10	1244	RT	SR 2	325+08.47						2				1					1						78						
E-17	1244	RT	SR 2	325+08.47-328+06.26																								308			
VB-11	1244	RT	SR 2	328+06.26						2				1					1						78						
E-18	1244	RT	SR 2	328+06.26-330+00.00																								199			
R-1	1245	CL	SR 2	330+41.27		1		1																							
R-2	1245	CL	SR 2	334+64.04		1		1																							
R-3	1245	CL	SR 2	338+91.00		1		1																							
E-1	1245	CL	SR 2	330+00.00-331+04.13																				342	312						
VA-27	1245	CL	SR 2	331+04.13						2						1				1					70						
E-2	1245	CL	SR 2	331+04.13-332+38.28																					402						
VB-13	1245	CL	SR 2	332+38.28						2						1				1					70						
E-3	1245	CL	SR 2	332+38.28-333+74.66																				441	411						
VB-14	1245	CL	SR 2	333+74.66						2						1				1					70						
E-4	1245	CL	SR 2	333+74.66-335+10.00																				438	408						
VB-15	1245	CL	SR 2	335+10.00						2						1				1					70						
E-5	1245	CL	SR 2	335+10.00-336+46.91																				441	411						
VB-16	1245	CL	SR 2	336+46.91						2						1				1					70						
E-6	1245	CL	SR 2	336+46.91-337+35.34																				297	267						
VB-17	1245	CL	SR 2	337+35.34						2						1				1					70						
E-7	1245	CL	SR 2	337+35.34-338+78.90																				462	432						
VB-18	1245	CL	SR 2	338+78.90						2						1				1					70						
E-8	1245	CL	SR 2	338+78.90-340+13.00																				432	402						
VB-19	1245	CL	SR 2	340+13.00						2						1				1					70						
E-9	1245	CL	SR 2	340+13.00-341+52.86																					417						
TOTALS CARRIED TO GENERAL SUMMARY					0	3	0	3	0	40	0	9	0	5	1	14	0	0	6	14	0	0	5724	5613	1410	1485	0	0	0	0	

CALCULATED JMS
CHECKED ZFB

LIGHTING SUBSUMMARY

LAK-2-3.32

1212
1679

g:\project\lak\13486\lighting\sheets\13486LSS009.dgn 7/11/2008 9:00:20 AM dshaner