REFERENCE NO.	SHEET NO.	SIDE	ROADWAY	STATION TO STATION	202 PULL BOX REMOVED EA	202 LIGHT TOWER REMOVED, AS PER PLAN EA	202 POWER SERVICE REMOVED, AS PER PLAN EA	202 LIGHT TOWER FOUNDATION REMOVED EA	202 REMOVAL MISC.: UNDERPASS LIGHTING SYSTEM EA	625 CONNECTOR KIT, TYPE II EA	625 CONNECTOR KIT, TYPE III EA	625 CABLE SPLICING KIT EA	625 LIGHT POLE, DECORATIVE, AS PER PLAN EA	625 LIGHT POLE, MISC.: LOW MAST, DESIGN ATLM39 EA	625 LIGHT POLE, MISC.: LOW MAST, DESIGN ATLM20 EA	625 LIGHT POLE, MISC.: LOW MAST, DESIGN ALM35 EA	625 LIGHT POLE, MISC.: LOW MAST, DESIGN ALM15 EA	625 LIGHT POLE ANCHOR BOLTS, MISC.: SET FOR PILASTER OR BARRIER MOUNTED LIGHT POLE EA	625 LIGHT POLE FOUNDATION, 24"x8' DEEP EA	625 MEDIAN LIGHT POLE FOUNDATION, 10' DEEP EA	625 NO. 6 AWG 600 VOLT DISTRIBUTION CABLE FT	625 NO. 1/0 AWG 5000 VOLT DISTRIBUTION CABLE FT	625 NO. 4 AWG 5000 VOLT DISTRIBUTION CABLE FT	625 NO. 2 AWG 5000 VOLT DISTRIBUTION CABLE FT	625 NO. 10 AWG POLE AND BRACKET CABLE FT	625 1-1/2" DUCT CABLE WITH THREE NO. 4 AWG 5000 VOLT CABLES FT	625 1-1/2" DUCT CABLE WITH THREE NO. 2 AWG 5000 VOLT CABLES FT	625 CONDUIT, 1", 725.04 FT	625 CONDUIT, 2", 725.04 FT	625 CONDUIT, 1", 725.05 FT	SEE SHEET 1223 FOR CONTINUATION
PB-7L	1250	LT	L. NATION	55+12.45								3																				
E-5	1250	LT	L. NATION	55+12.45-55+38.45																				111					27			
LE-13	1250	LT	L. NATION	55+38.45						2			1					1									24					
E-6	1250	LT	L. NATION	55+38.45-56+03.45																				225					65			
LE-11	1250	LT	L. NATION	56+03.45						2			1					1									24					
E-7	1250	LT	L. NATION	56+03.45-56+68.45																				225					65			
LE-9	1250	LT	L. NATION	56+68.45						2			1					1									24					
E-8	1250	LT	L. NATION	56+68.45-57+00.00																				111					32			
LE-18	1250	RT	L. NATION	52+84.50						2				1						1							78					
E-9	1250	RT	L. NATION	52+84.50-54+25.59																									151			
LE-16	1250	RT	L. NATION	54+25.59						2				1						1							78					
E-10	1250	RT	L. NATION	54+25.59-55+33.24																									118			
PB-8L	1250	RT	L. NATION	55+33.24								3																				
E-11	1250	RT	L. NATION	55+33.24-55+70.24																				141					37			
LE-14	1250	RT	L. NATION	55+70.24						2			1					1									24					
E-12	1250	RT	L. NATION	55+70.24-56+35.24																				225					65			
LE-12	1250	RT	L. NATION	56+35.24						2			1					1									24					
E-13	1250/ 1251	RT	L. NATION	56+35.24-57+00.24																				225					65			
LE-10	1250	RT	L. NATION	57+00.24						2			1					1									24					
E-14	1250	LT	L. NATION	50+60.00						1	1																60					
E-15	1250	LT	L. NATION	51+61.00						1	1																60					
E-16	1250	RT	L. NATION	51+14.00						1	1																60					
E-17	1250	LT	L. NATION	50+51.04-50+60.00																		75								15		10
R-1	1251	LT	RAMP E	100+18.97	1																											
R-2	1251	RT	RAMP E	99+98.39		1		1																								
R-3	1251	RT	L. NATION	61+65.52	1																											
R-4	1251	LT	L. NATION	64+34.84			1																									
R-5	1251	LT	L. NATION	64+43.83	1																											
E-1	1251	LT	L. NATION	57+00.00-57+33.45																				129					33			
LE-7	1251	LT	L. NATION	57+33.45						2			1					1									24					
E-2	1251	LT	L. NATION	57+33.45-57+98.45																				237					69			
LE-5	1251	LT	L. NATION	57+98.45						2			1					1									24					
E-3	1251	LT	L. NATION	57+98.45-58+62.85																				222					64			
PB-5L	1251	LT	L. NATION	58+62.85								3																				
E-4	1251	LT	L. NATION	58+62.85-58+85.00																									32			
LE-4	1251	LT	L. NATION	58+85.00						2				1						1							78					
E-5	1251	LT	L. NATION	58+85.00-60+25.00																									150			
LE-3	1251	LT	L. NATION	60+25.00						2				1						1							78					
E-6	1251	LT	L. NATION	60+25.00-61+70.01																									157			
LE-2	1251	LT	L. NATION	61+70.01						2				1						1							78					
E-7	1251	LT	L. NATION	61+70.01-62+26.02																									68			
PB-2L	1251	LT	L. NATION	62+26.02								3																				
E-8	1251	LT	L. NATION	62+26.02-63+88.32																				546								
E-9	1251	LT	L. NATION	63+88.32-64+00.67																										55		
PB-1L	1251	LT	L. NATION	64+00.67								6																				
E-10	1251	LT	L. NATION	64+00.67-65+82.02																										195		
LF-1	1251	LT	L. NATION	65+82.02						2				1						1							78					
E-11	1251	LT	RAMP D	86+56.98-88+83.77																										460		
TOTALS CARRIED TO GENERAL SUMMARY					3	1	1	1	0	31	3	18	8	6	0	0	0	8	6	0	75	0	2397	0	840	676	710	15	522	10		

CALCULATED JMS
CHECKED ZFB

LIGHTING SUBSUMMARY

LAK-2-3.32

1222
1679

g:\project\lak\13486\lighting\sheets\13486LSS019.dgn 7/11/2008 9:01:50 AM dshaner