REFERENCE NO.	SHEET NO.	SIDE	ROADWAY	STATION TO STATION	202 PULL BOX REMOVED	202 LIGHT TOWER REMOVED, AS PER PLAN	202 POWER SERVICE REMOVED, AS PER PLAN	202 LIGHT TOWER FOUNDATION REMOVED	202 REMOVAL MISC.: UNDERPASS LIGHTING SYSTEM	625 CONNECTOR KIT, TYPE II	625 CONNECTOR KIT, TYPE III	625 CABLE SPLICING KIT	625 LIGHT POLE, DECORATIVE, AS PER PLAN	625 LIGHT POLE, MISC.: LOW MAST, DESIGN ATLM39	625 LIGHT POLE, MISC.: LOW MAST, DESIGN ATLM20	625 LIGHT POLE, MISC.: LOW MAST, DESIGN ALM35	625 LIGHT POLE, MISC.: LOW MAST, DESIGN ALM15	625 LIGHT POLE ANCHOR BOLTS, MISC.: SET FOR PILASTER OR BARRIER MOUNTED LIGHT POLE	625 LIGHT POLE FOUNDATION, 24"x8' DEEP	625 MEDIAN LIGHT POLE FOUNDATION, 10' DEEP	625 NO. 6 AWG 600 VOLT DISTRIBUTION CABLE	625 NO. 1/0 AWG 5000 VOLT DISTRIBUTION CABLE	625 NO. 4 AWG 5000 VOLT DISTRIBUTION CABLE	625 NO. 2 AWG 5000 VOLT DISTRIBUTION CABLE	625 NO. 10 AWG POLE AND BRACKET CABLE	625 1-1/2" DUCT CABLE WITH THREE NO. 4 AWG 5000 VOLT CABLES	625 1-1/2" DUCT CABLE WITH THREE NO. 2 AWG 5000 VOLT CABLES	625 CONDUIT, 1", 725.04	625 CONDUIT, 2", 725.04	625 CONDUIT, 1", 725.05	SEE SHEET 1227 FOR CONTINUATION
					EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	
R-1	1252	LT	SR 2	394+63.51		1		1																								
R-2	1252	CL	SR 2	398+08.69		1		1																								
R-3	1252	RT	RAMP A	99+05.00	1																											
R-4	1252	CL	SR 2	402+48.00		1		1																								
E-1	1252	CL	SR 2	392+50.00-393+16.71																			216									
LB-19	1252	CL	SR 2	393+16.71						2						1				1					70							
E-2	1252	CL	SR 2	393+16.71-394+49.36																			429									
LB-20	1252	CL	SR 2	394+49.36						2						1				1					70							
E-3	1252	CL	SR 2	394+49.36-395+84.39																			438									
LB-21	1252	CL	SR 2	395+84.39						2						1				1					70							
E-4	1252	CL	SR 2	395+84.39-397+19.70																			435									
LB-22	1252	CL	SR 2	397+19.70						2						1				1					70							
E-5	1252	CL	SR 2	397+19.70-398+54.63																			435									
LB-23	1252	CL	SR 2	398+54.63						2						1				1					70							
E-6	1252	CL	SR 2	398+54.63-399+89.44																			435									
LB-24	1252	CL	SR 2	399+89.44						2						1				1					70							
E-7	1252	CL	SR 2	399+89.44-401+24.38																			435									
LB-25	1252	CL	SR 2	401+24.38						2						1				1					70							
LD-1	1252	CL	SR 2	402+48.00						2						1				1					70							
E-8	1252	CL	SR 2	402+48.00-403+94.31																				468								
LD-2	1252	CL	SR 2	403+94.31						2						1				1					70							
E-9	1252	CL	SR 2	403+94.31-405+00.00																				333								
E-10	1249/1252	RT	RAMP B	91+25.62-93+69.88																						248						
LC-12	1252	RT	RAMP B	93+69.88						2				1					1						78							
E-11	1252	RT	RAMP B	93+69.88-96+36.03																						267						
LC-13	1252	RT	RAMP B	96+36.03						2				1					1						78							
LB-26	1252	LT	RAMP A	93+48.19						2				1					1						78							
E-12	1252	LT	RAMP A	93+48.19-95+86.36																						245	235					
LB-27	1252	LT	RAMP A	95+86.36						2				1					1						78							
E-13	1252	LT	RAMP A	95+86.36-98+28.96																						247	237					
LB-28	1252	LT	RAMP A	98+28.96						2				1					1						78							
E-14	1252	LT	RAMP A	98+28.96-102+30.13																							405					
PB-16L	1252	LT	RAMP A	102+30.13								3																				
E-16	1252	LT/CL	RAMP A/SR 2	102+30.13-402+48.00																				270								
R-1	1253	CL	SR 2	406+72.93		1		1																								
R-2	1253	CL	SR 2	411+01.20		1		1																								
R-3	1253	CL	SR 2	415+26.73		1		1																								
E-1	1253	CL	SR 2	405+00.00-405+29.65																				105								
LD-3	1253	CL	SR 2	405+29.65						2						1				1					70							
E-2	1253	CL	SR 2	405+29.65-406+64.39																				435								
LD-4	1253	CL	SR 2	406+64.39						2						1				1					70							
E-3	1253	CL	SR 2	406+64.39-408+01.43																				444								
LD-5	1253	CL	SR 2	408+01.43						2						1				1					70							
E-4	1253	CL	SR 2	408+01.43-409+34.44																				429								
LD-6	1253	CL	SR 2	409+34.44						2						1				1					70							
E-5	1253	CL	SR 2	409+34.44-410+69.41																				435								
LD-7	1253	CL	SR 2	410+69.41						2						1				1					70							
TOTALS CARRIED TO GENERAL SUMMARY					1	6	0	6	0	38	0	3	0	5	0	14	0	0	5	14	0	0	2823	2919	1370	1007	877	0	0	0		

CALCULATED JMS
CHECKED ZFB

LIGHTING SUBSUMMARY

LAK-2-3.32

1226
1679

g:\project\lak\13486\lighting\sheets\13486LSS023.dgn 7/11/2008 9:02:41 AM dshaner