



NOTES:

1. ALL DIMENSIONS ARE PERPENDICULAR TO THE ℓ , UNLESS NOTED OTHERWISE.
2. ALL PHASES SHALL BE CONSTRUCTED IN STAGE 2 AS SHOWN, HOWEVER, LIMITED SUBSTRUCTURE WORK MAY PROCEED DURING STAGE 1 (PHASE B), AS APPROVED BY THE ENGINEER.
3. FOR LIST OF ABBREVIATIONS SEE SHEET 4/70.
4. PORTABLE CONCRETE BARRIER ANCHORS INCLUDED WITH ROADWAY QUANTITIES FOR PAYMENT.
5. ALL BARRIER SEGMENTS SHALL BE FASTENED TO THE BRIDGE DECK USING THREE (3) ONE INCH DIA. HIGH STRENGTH THROUGH BOLTS OR APPROVED RESIN ANCHORS. WHEN RESIN ANCHORS ARE USED THEY MUST BE EMBEDDED A MINIMUM OF 6 1/2" INTO FIRM CONCRETE. ALL ANCHORS SHALL BE PLACED ON THE TRAFFIC SIDE OF THE BARRIER WITH THE ANCHOR PATTERN SYMMETRICAL ABOUT THE CENTER OF EACH SEGMENT.



- DIMENSIONS ARE MEASURED ALONG CENTERLINE OF PIER



j:\LAK\13486\bridge\LAK002_0486\c_sheets\02_0486CPC002.dgn 03-JUL-2008 1:36PM lintn

DESIGNED	PJL	CHECKED	EJC
DRAWN	LEL	REVISED	
REVIEWED	RJO	STRUCTURE FILE NUMBER	4300686 (L) 4500726 (R)
DATE	6-19-08		