

j:\LAK\13486\bridge\LAK002_0486c\sheets\002_0486CSD015.dgn 03-JUL-2008 1:45PM lntn

SCREED TABLE																
	LOCATION	REAR ABUT.	0.25	0.50	0.75	SPLICE 1	PIER 1	0.25	0.50	0.75	PIER 2	SPLICE 2	0.25	0.50	0.75	FWD. ABUT.
RIGHT TOE OF BARRIER	STATION	356+64.47	356+76.97	356+89.47	357+01.97	357+02.47	357+14.47	357+28.22	357+41.97	357+55.72	357+69.47	357+81.47	357+81.97	357+94.47	358+06.97	358+19.47
	DECK ELEVATION	619.11	619.12	619.11	619.11	619.11	619.10	619.08	619.06	619.03	618.99	618.96	618.96	618.92	618.88	618.83
	DEFLECTION	0.00	0.02	0.03	0.02	0.01	0.00	0.00	0.00	0.00	0.00	0.01	0.02	0.03	0.02	0.00
	SCREED ELEVATION	619.11	619.14	619.14	619.13	619.12	619.10	619.08	619.06	619.03	618.99	618.97	618.97	618.98	618.95	618.90
BEAM 10	STATION	356+64.30	356+76.80	356+89.30	357+01.80	357+02.30	357+14.30	357+28.05	357+41.80	357+55.55	357+69.30	357+81.30	357+81.80	357+94.30	358+06.80	358+19.30
	DECK ELEVATION	619.12	619.12	619.12	619.11	619.11	619.10	619.08	619.06	619.03	619.00	618.97	618.97	618.93	618.88	618.84
	DEFLECTION	0.00	0.02	0.03	0.02	0.01	0.00	0.00	0.00	0.00	0.00	0.01	0.02	0.03	0.02	0.00
	SCREED ELEVATION	619.12	619.14	619.15	619.13	619.12	619.10	619.08	619.06	619.03	619.00	618.98	618.99	618.96	618.90	618.84
BEAM 9	STATION	356+60.57	356+73.07	356+85.57	356+98.07	356+98.57	357+10.57	357+24.32	357+38.07	357+51.82	357+65.57	357+77.57	357+78.07	357+90.57	358+03.07	358+15.57
	DECK ELEVATION	619.24	619.24	619.24	619.23	619.23	619.23	619.21	619.19	619.16	619.13	619.10	619.10	619.06	619.02	618.97
	DEFLECTION	0.00	0.03	0.03	0.02	0.02	0.00	0.00	0.01	0.00	0.00	0.02	0.02	0.03	0.03	0.00
	SCREED ELEVATION	619.24	619.27	619.27	619.25	619.25	619.23	619.21	619.20	619.16	619.13	619.12	619.12	619.09	619.05	618.97
PROFILE GRADE	STATION	356+58.87	356+71.37	356+83.87	356+96.37	356+96.87	357+08.87	357+22.62	357+36.37	357+50.12	357+63.87	357+75.87	357+76.37	357+88.87	358+01.37	358+13.87
	DECK ELEVATION	619.29	619.30	619.29	619.29	619.29	619.28	619.27	619.25	619.22	619.19	619.16	619.16	619.12	619.08	619.03
	DEFLECTION	0.00	0.03	0.03	0.02	0.02	0.00	0.00	0.01	0.00	0.00	0.01	0.02	0.03	0.03	0.00
	SCREED ELEVATION	619.29	619.33	619.32	619.31	619.31	619.28	619.27	619.26	619.22	619.19	619.17	619.18	619.15	619.11	619.03
BEAM 8	STATION	356+56.84	356+69.34	356+81.84	356+94.34	356+94.84	357+06.84	357+20.59	357+34.34	357+48.09	357+61.84	357+73.84	357+74.34	357+86.84	357+99.34	358+11.84
	DECK ELEVATION	619.35	619.36	619.36	619.36	619.36	619.35	619.33	619.31	619.29	619.26	619.23	619.23	619.19	619.15	619.10
	DEFLECTION	0.00	0.03	0.03	0.02	0.02	0.00	0.00	0.01	0.00	0.00	0.01	0.02	0.03	0.03	0.00
	SCREED ELEVATION	619.35	619.39	619.39	619.38	619.38	619.35	619.33	619.32	619.29	619.26	619.24	619.25	619.22	619.18	619.10
PHASE CONSTRUCTION JOINT	STATION	356+56.14	356+68.64	356+81.14	356+93.64	356+94.14	357+06.14	357+19.89	357+33.64	357+47.39	357+61.14	357+73.14	357+73.64	357+86.14	357+98.64	358+11.14
	DECK ELEVATION	619.38	619.38	619.38	619.38	619.38	619.37	619.36	619.34	619.31	619.28	619.25	619.25	619.22	619.18	619.13
	DEFLECTION	0.00	0.03	0.03	0.02	0.02	0.00	0.00	0.01	0.00	0.00	0.01	0.02	0.03	0.03	0.00
	SCREED ELEVATION	619.38	619.41	619.41	619.40	619.40	619.37	619.36	619.35	619.31	619.28	619.26	619.27	619.25	619.21	619.13
CROWN	STATION	356+52.90	356+65.40	356+77.90	356+90.40	356+90.90	357+02.90	357+16.65	357+30.40	357+44.15	357+57.90	357+69.90	357+70.40	357+82.90	357+95.40	358+07.90
	DECK ELEVATION	619.48	619.49	619.49	619.49	619.48	619.48	619.47	619.45	619.42	619.40	619.37	619.36	619.33	619.29	619.25
	DEFLECTION	0.00	0.03	0.04	0.02	0.02	0.00	0.00	0.01	0.00	0.00	0.01	0.02	0.03	0.03	0.00
	SCREED ELEVATION	619.48	619.52	619.53	619.51	619.50	619.48	619.47	619.46	619.42	619.40	619.38	619.38	619.36	619.32	619.25
BEAM 7	STATION	356+52.90	356+65.40	356+77.90	356+90.40	356+90.90	357+02.90	357+16.65	357+30.40	357+44.15	357+57.90	357+69.90	357+70.40	357+82.90	357+95.40	358+07.90
	DECK ELEVATION	619.48	619.49	619.49	619.49	619.48	619.48	619.47	619.45	619.42	619.40	619.37	619.36	619.33	619.29	619.25
	DEFLECTION	0.00	0.03	0.04	0.02	0.02	0.00	0.00	0.01	0.00	0.00	0.01	0.02	0.03	0.03	0.00
	SCREED ELEVATION	619.48	619.51	619.52	619.50	619.50	619.47	619.46	619.45	619.42	619.39	619.37	619.38	619.36	619.32	619.24
BEAM 6	STATION	356+48.72	356+61.22	356+73.72	356+86.22	356+86.72	356+98.72	357+12.47	357+26.22	357+39.97	357+53.72	357+65.72	357+66.22	357+78.72	357+91.22	358+03.72
	DECK ELEVATION	619.34	619.35	619.35	619.35	619.35	619.35	619.34	619.32	619.30	619.27	619.24	619.24	619.21	619.17	619.13
	DEFLECTION	0.00	0.03	0.04	0.02	0.02	0.00	0.00	0.01	0.00	0.00	0.01	0.02	0.03	0.03	0.00
	SCREED ELEVATION	619.34	619.38	619.39	619.37	619.37	619.35	619.34	619.33	619.30	619.27	619.25	619.26	619.24	619.20	619.13
BEAM 5	STATION	356+44.66	356+57.16	356+69.66	356+82.16	356+82.66	356+94.66	357+08.41	357+22.16	357+35.91	357+49.66	357+61.66	357+62.16	357+74.66	357+87.16	357+99.66
	DECK ELEVATION	619.21	619.22	619.22	619.22	619.22	619.22	619.21	619.19	619.17	619.15	619.12	619.12	619.09	619.05	619.01
	DEFLECTION	0.00	0.03	0.04	0.02	0.02	0.00	0.00	0.01	0.00	0.00	0.02	0.02	0.04	0.03	0.00
	SCREED ELEVATION	619.21	619.25	619.26	619.24	619.24	619.22	619.21	619.20	619.17	619.15	619.14	619.14	619.13	619.08	619.01
GRADE BREAK	STATION	356+40.98	356+53.48	356+65.98	356+78.48	356+78.98	356+90.98	357+04.73	357+18.48	357+32.23	357+45.98	357+57.98	357+58.48	357+70.98	357+83.48	357+95.98
	DECK ELEVATION	619.08	619.10	619.10	619.10	619.10	619.10	619.09	619.08	619.06	619.04	619.01	619.01	618.98	618.94	618.90
	DEFLECTION	0.00	0.03	0.04	0.02	0.02	0.00	0.00	0.01	0.00	0.00	0.02	0.02	0.04	0.03	0.00
	SCREED ELEVATION	619.08	619.13	619.14	619.12	619.12	619.10	619.09	619.09	619.06	619.04	619.03	619.03	619.02	618.97	618.90
BEAM 4	STATION	356+40.60	356+53.10	356+65.60	356+78.10	356+78.60	356+90.60	357+04.35	357+18.10	357+31.85	357+45.60	357+57.60	357+58.10	357+70.60	357+83.10	357+95.60
	DECK ELEVATION	619.07	619.08	619.09	619.09	619.09	619.09	619.08	619.06	619.05	619.02	619.00	619.00	618.97	618.93	618.89
	DEFLECTION	0.00	0.03	0.04	0.02	0.02	0.00	0.00	0.01	0.00	0.00	0.02	0.02	0.04	0.03	0.00
	SCREED ELEVATION	619.07	619.11	619.13	619.11	619.11	619.09	619.08	619.07	619.05	619.02	619.02	619.02	619.01	618.96	618.89
BEAM 3	STATION	356+36.54	356+49.04	356+61.54	356+74.04	356+74.54	356+86.54	357+00.29	357+14.04	357+27.79	357+41.54	357+53.54	357+54.04	357+66.54	357+79.04	357+91.54
	DECK ELEVATION	618.90	618.91	618.92	618.93	618.93	618.92	618.92	618.91	618.89	618.87	618.84	618.84	618.81	618.78	618.74
	DEFLECTION	0.00	0.03	0.03	0.02	0.02	0.00	0.00	0.01	0.00	0.00	0.02	0.02	0.04	0.03	0.00
	SCREED ELEVATION	618.90	618.94	618.95	618.95	618.95	618.92	618.92	618.92	618.89	618.87	618.86	618.86	618.85	618.81	618.74
BEAM 2	STATION	356+32.48	356+44.98	356+57.48	356+69.98	356+70.48	356+82.48	356+96.23	357+09.98	357+23.73	357+37.48	357+49.48	357+49.98	357+62.48	357+74.98	357+87.48
	DECK ELEVATION	618.73	618.75	618.76	618.76	618.76	618.76	618.76	618.75	618.73	618.71	618.69	618.69	618.66	618.63	618.59
	DEFLECTION	0.00	0.02	0.03	0.00	0.00	0.00	0.00	0.01	0.00	0.00	0.02	0.02	0.03	0.03	0.00
	SCREED ELEVATION	618.73	618.77	618.79	618.76	618.76	618.76	618.76	618.76	618.73	618.71	618.71	618.71	618.69	618.66	618.59
BEAM 1	STATION	356+30.14	356+42.51	356+54.89	356+67.27	356+67.76	356+79.64	356+93.26	357+06.87	357+20.49	357+34.10	357+45.99	357+46.48	357+58.86	357+71.23	357+83.60
	DECK ELEVATION	618.64	618.65	618.65	618.65	618.65	618.65	618.64	618.62	618.60	618.58	618.55	618.55	618.52	618.49	618.45
	DEFLECTION	0.00	0.02	0.02	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.01	0.01	0.03	0.02	0.00
	SCREED ELEVATION															