



D-503
STA. 26+85.00, 38.00' RT. (S.R. 91)
PROP. CB NO. 6
T/G ELEV. = 651.53'
E 12" (SE) = 647.69'
E 6" UD (S) = 648.69'

D-504
STA. 26+35.00, 34.00' LT. (S.R. 91)
PROP. CB NO. 6
T/G ELEV. = 651.42'
E 12" (W) = 647.59'
E 6" UD (S) = 648.59'

D-505
STA. 30+00.00, 34.00' RT. (S.R. 91)
PROP. CB NO. 6
T/G ELEV. = 645.89'
E 12" (E) = 642.00'
E 6" UD (S) = 643.06'

D-506
STA. 30+00.00, 40.00' RT. (S.R. 91)
PROP. MH NO. 3
T/G ELEV. = 645.75'
E 12" (W) = 641.91'
E 12" (N) = 641.91'

D-511
STA. 29+95.00, 46.00' LT. (S.R. 91)
PROP. CB NO. 6
T/G ELEV. = 645.70'
E 12" (W) = 641.85'
E 6" UD (S) = 642.85'

MH-1
STA. 26+71.00,
3.50' LT. (S.R. 91)
PROP. MH NO. 3
T/G ELEV. = 650.90'
E 12" (W) = 645.75' (S&E)
FIELD VERIFY PIPE INVERTS

D-512
STA. 29+95.00, 52.00' LT. (S.R. 91)
PROP. MH NO. 3
T/G ELEV. = 645.56'
E 12" (E) = 641.76'
E 12" (N) = 641.76'

D-506A
STA. 26+45.85, 9.00' LT. (S.R. 91)
PROP. CB NO. 3
T/G ELEV. = 651.17'
E 12" (E) = 646.07'

D-506B
STA. 26+45.85, 2.00' LT. (S.R. 91)
PROP. CB NO. 3
T/G ELEV. = 651.29'
E 12" (W&N) = 646.00'

EX-6
STA. 26+70.10,
3.07' LT. (S.R. 91)
EX. CB
T/G ELEV. = 650.60'
E 12" (E) = 645.75'

REVISION 04/07/10:
REMOVED MEDIAN REMOVAL
ADDED DRAINAGE WORK

TAPER CODE	BEGINNING STATION	ENDING STATION	SIDE	DESCRIPTION	BEGIN WIDTH	END WIDTH	TAPER RATE
GH	28+19.37	28+59.37	LT.	PAVEMENT	50.00'	46.00'	10:0:1
GI	26+03.47	26+30.00	LT.	PAVEMENT	38.69'	36.00'	9.9:1

[Symbol] = PROPOSED PAVEMENT WIDENING
SEE TYPICAL SECTIONS ON SHEET 35

[Symbol] = REMOVED / RELOCATED BY OTHERS

FOR SOM CENTER PROFILE, SEE SHEET 635
FOR INTERSECTION DETAILS, SEE SHEET 816
FOR UNDERDRAIN DETAILS, SEE SHEET 950

G:\Project\lak\13486\roadway\sheet\13486GP504.dgn 4/7/2010 2:13:08 PM PBerdis