| SHEET NO. | REFERENCE NO. | ELEVATION VIEW SHEET NO. | LOCATION | | | | CODE | SIZE | 630 | | | | | | | | | | | | | | 631 | | | | | 625 | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | ROUTE | DIRECTION | STATION | SIDE | | | GROUND MOUNTED SUPPORT, S4X7.7 BEAM | GROUND MOUNTED SUPPORT, W6X9 BEAM | GROUND MOUNTED SUPPORT, W12X30 BEAM | GROUND MOUNTED SUPPORT NO.3 POST | ONE WAY SUPPORT NO.3 POST | BREAKAWAY BEAM CONNECTION | SIGN, FLAT SHEET, TYPE G | SIGN, EXTRUSHEET, TYPE G | GROUND MOUNTED BEAM SUPPORT FOUNDATION | REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL | REMOVAL OF GROUND MOUNTED SIGN AND REERECTION | REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL | REMOVAL OF GROUND MOUNTED BEAM SUPPORT AND DISPOSAL | REMOVAL OF OVERHEAD SIGN SUPPORT AND DISPOSAL | RIGID OVERHEAD SIGN SUPPORT FOUNDATION | COMBINATION OVERHEAD SIGN SUPPORT, TYPE TC-12.30, DESIGN 5 | DISCONNECT SWITCH WITH ENCLOSUE, TYPE X | SIGN WIRED | SIGN SERVICE | BALLAST, TYPE CMRI-175-120, INTEGRAL | MERCURY VAPOR LUMINAIRE, TYPE TC-32.21, WITH 175 WATT LAMP | CONNECTOR KIT, TYPE II | CONNECTOR KIT, TYPE III | BRACKET ARM, 15' | NO. 10 AWG POLE AND BRACKET CABLE | LUMINAIRE, CONVENTIONAL, 200 W, HPS, TYPE II, 480 V | GROUND ROD |
| | | | | | | | | | LIN FT | LIN FT | LIN FT | LIN FT | LIN FT | EACH | SQ FT | SQ FT | EACH | EACH | EACH | EACH | EACH | EACH | EACH | EACH | EACH | EACH | EACH | EACH | EACH | EACH | LN FT | EACH | EACH |
| 69 | 1 | | SR-44 | NB | 253+25 | RT | R-9B-36 | 36"X72" | | | | 18.0-18.5 | | | 18 | | | 2 | | 4 | | | | | | | | | | | | | |
| 69 | 2 | 83 | SR-44 | SB | 256+00 | RT | | | | 16.5-18.0 | | | | 2 | | | 2 | | 1 | 2 | | | | | | | | | | | | | |
| 70 | 3 | 83 | SR-44 | SB | 293+90 | RT | GF | 72"X60" | 17.0-17.0 | | | | | 2 | | 30 | 2 | 1 | | 2 | | | | | | | | | | | | | |
| 71 | 4 | 83 | SR-44 | SB | 302+50 | RT | GE | 15'X9.5' | | | 28.0-32.5 | | | | | 142.5 | 2 | 1 | | | 2 | | | | | | | | | | | | |
| 73 | 5 | | SR-2 | | 586+50 | ℄ | | | | | | 13.5 | | | | | | | 2 | 1 | | | | | | | | | | | | | |
| 73 | 6 | | SR-2 | | 586+75 | ℄ | | | | | | 13.5 | | | | | | | 2 | 1 | | | | | | | | | | | | | |
| 73 | 7 | | SR-2 | EB | 602+10 | RT | | | | | | 14.5-15.0 | | | | | | | 1 | 2 | | | | | | | | | | | | | |
| 73 | 8 | | SR-2 | EB | 602+90 | RT | | | | | | 14.5-15.0 | | | | | | | 2 | 2 | | | | | | | | | | | | | |
| 73 | 9 | | SR-2 | WB | 604+50 | RT | | | | | | 13.5-14.0 | | | | | | | 1 | 2 | | | | | | | | | | | | | |
| 74 | 10 | | RAMP E | WB | 17+15 | RT | W-33-30 | 30"X36" | | | | | | | 7.5 | | | | | | | | | | | | | | | | | | |
| 74 | 11 | | SR-2 | EB | 618+90 | RT | | | | | | 13.5-14.0 | | | | | | | 1 | 2 | | | | | | | | | | | | | |
| 75 | 12 | | SR-2 | | 638+40 | ℄ | | | | | | 13.5 | | | | | | | 2 | 1 | | | | | | | | | | | | | |
| 75 | 13 | | SR-2 | | 638+75 | ℄ | | | | | | 13.5 | | | | | | | 2 | 1 | | | | | | | | | | | | | |
| 75 | 14 | | SR-2 | | 638+75 | ℄ | | | | | | | | | | | | | | 1 | | | | | | | | | | | | | |
| 75 | 15 | | SR-2 | EB | 644+90 | RT | R-9B-36 | 36"X72" | | | | 18.0-18.5 | | | 18 | | | 2 | | 4 | | | | | | | | | | | | | |
| 75 | 16 | 83 | SR-2 | WB | 646+10 | RT | | | | 19.0-19.5 | | | | 2 | | | 2 | | 1 | 2 | | | | | | | | | | | | | |
| 76 | 17 | | SR-44 | NB | 51+90 | RT | | | | | | 15.0-16.0 | | | | | | | 1 | 2 | | | | | | | | | | | | | |
| 77 | 18 | | SR-44 | SB | 59+60 | RT | | | | | | 15.0-16.0 | | | | | | | 1 | 2 | | | | | | | | | | | | | |
| 77 | 19 | | SR-44 | SB | 68+90 | RT | | | | | | | | | | | | | | 1 | | | | | | | | | | | | | |
| 77 | 20 | | SR-44 | SB | 69+00 | RT | | | | | | | | | | | | | | 1 | | | | | | | | | | | | | |
| 77 | 21 | | SR-44 | SB | 69+10 | RT | | | | | | | | | | | | | | 1 | | | | | | | | | | | | | |
| 77 | 22 | 84 | SR-44 | NB | 71+20 | RT | GF | 72"X60" | 17.0-17.0 | | | | | 2 | | 30 | 2 | 1 | | 2 | | | | | | | | | | | | | |
| 77 | 23 | | RAMP C | NB | 11+50 | RT | | | | | | 15.0-16.0 | | | | | | | 1 | 1 | | | | | | | | | | | | | |
| 77 | 24 | | RAMP B | SB | 3+75 | RT | | | | | | 14.0 | 15.0 | | | | | | 4 | 2 | | | | | | | | | | | | | |
| 77 | 25 | | RAMP B | SB | 6+00 | RT | | | | | | 13.0 | | | | | | | 1 | 1 | | | | | | | | | | | | | |
| 77 | 26 | | RAMP B | SB | 7+75 | RT | | | | | | | | | | | | | 3 | 2 | | | | | | | | | | | | | |
| 77 | 27 | | RAMP B | SB | 8+00 | RT | | | | | | 13.0 | | | | | | | 1 | 1 | | | | | | | | | | | | | |
| 77 | 28 | 84 | SR-283 | EB | 25+75 | RT | GE | 7'X5.5' | | 18.5-18.5 | | | | 2 | | 38.5 | 2 | 1 | | 3 | | | | | | | | | | | | | |
| 77 | 29 | 84 | SR-283 | EB | 27+25 | RT | GE | 7'X5.5' | | 18.5-18.5 | | 14.0 | | 2 | | 38.5 | 2 | 1 | 1 | 3 | | | | | | | | | | | | | |
| 77 | 30 | 84 | SR-283 | WB | 33+20 | RT | GE | 7'X5.5' | | 18.0-18.0 | | | | 2 | | 77 | 2 | 2 | | 4 | | | | | | | | | | | | | |
| 78 | 31 | 85 | SR-44 | SB | 80+80 | RT | GF | 72"X60" | 17.0-17.0 | | | | | 2 | | 30 | 2 | | | | | | | | | | | | | | | | |
| 78 | 32 | 85 | SR-44 | SB | 90+00 | RT | GN | 108"X36" | 13.5-15.5 | | | | | 2 | | 27 | 2 | 1 | | 2 | | | | | | | | | | | | | |
| 81 | 33 | 85 | SR-44 | SB | 132+10 | RT | GE | 13'X6.5' | | | | | | | | 84.5 | | | | | | 1 | 1 | 1 | 1 | 1 | 1 | 2 | 2 | 1 | 1 | 1 | 100 | 1 | 1 |
| 70 | 34 | | FERN ST | SB | 7+59 | RT | | | | | | 13.5 | | | | | | | 1 | 1 | | | | | | | | | | | | | |
| 70 | 35 | | FERN ST | | 8+34 | RT | | | | | | 14.5 | | | | | | | 3 | 1 | | | | | | | | | | | | | |
| 70 | 36 | | FERN ST | | 8+50 | RT | | | | | | 13.5 | | | | | | | 2 | 1 | | | | | | | | | | | | | |
| 70 | 37 | | JACKSON ST | | 8+66 | LT | | | | | | 14.5 | | | | | | | 3 | 1 | | | | | | | | | | | | | |
| 70 | 38 | | JACKSON ST | WB | 8+72 | LT | | | | | | 14.0 | | | | | | | 2 | 1 | | | | | | | | | | | | | |
| 70 | 39 | | RAMP I | SB | 15+10 | RT | | | | | | 14.5 | | | | | | | 3 | 1 | | | | | | | | | | | | | |
| 70 | 40 | | RAMP I | SB | 15+10 | LT | | | | | | 14.5 | | | | | | | 3 | 1 | | | | | | | | | | | | | |
| 70 | 41 | | RAMP I | SB | 15+00 | RT | R-31M-48 | | | | | 13.5-14.0 | | | 10 | | | | 1 | 1 | | | | | | | | | | | | | |
| 70 | 42 | | RAMP I | SB | 15+00 | LT | R-31M-48 | | | | | 13.5-14.0 | | | 10 | | | | 1 | 1 | | | | | | | | | | | | | |
| 70 | 43 | | RAMP I | SB | 14+00 | RT | | | | | | 14.0 | | | | | | | 2 | 1 | | | | | | | | | | | | | |
| 70 | 44 | | RAMP I | SB | 13+45 | RT | R-31M-48 | | | | | 13.5-14.0 | | | 10 | | | | 1 | 1 | | | | | | | | | | | | | |
| 70 | 45 | | RAMP I | SB | 13+45 | LT | R-31M-48 | | | | | 13.5-14.0 | | | 10 | | | | 1 | 1 | | | | | | | | | | | | | |
| SUB-TOTALS | | | | | | | | | 131.0 | 183.0 | 60.5 | 611.0 | 15 | 18 | 83.5 | 498 | 20 | 12 | 51 | 67 | 2 | 1 | 1 | 1 | 1 | 1 | 1 | 2 | 2 | 1 | 1 | 1 | 100 | 1 | 1 |

CALCULATED EMK
CHECKED LDH

# SIGN SUB-SUMMARY

LAKE COUNTY
LAK-2/44-13.05/4.14



PLOTTED FROM: I:\PROJECTS\Pidl8391\dgn\18391tsb.dgn