

ESTIMATED QUANTITIES

AS PER PLAN  
REFERENCE  
SHEET NO.

| ITEM    | ITEM EXT. | NHS  | STP | TOTAL | UNIT     | DESCRIPTION  |       |
|---------|-----------|------|-----|-------|----------|--|-------|
| 202     | 11201     | LUMP |     | LUMP  |          | PORTIONS OF STRUCTURE REMOVED, AS PER PLAN                                     | 2 / 8 |
| SPECIAL | 512E67510 | 182  |     | 182   | SQ. YD.  | SEALING OF CONCRETE SURFACES (EPOXY-URETHANE) *                                |       |
| 514     | 27700     | 50   |     | 50    | SQ. FT.  | FIELD PAINTING, MISC.: JOINT ARMOR   |       |
| 516     | 01300     | 13   |     | 13    | LIN. FT. | ELASTOMERIC STRIP SEAL WITHOUT STEEL EXTRUSIONS                                |       |
| 516     | 11900     | 13   |     | 13    | LIN. FT. | HORIZONTAL EXTENSION OF STRUCTURAL EXPANSION JOINT                             |       |
| 517     | 76201     | 216  |     | 216   | LIN. FT. | RAILING FACED, AS PER PLAN   | 3 / 8 |
| 607     | 35000     | 216  |     | 216   | LIN. FT. | FENCE REMOVED AND REBUILT  |       |
| 842     | 81300     | 10   |     | 10    | EACH     | CONCRETE, MISC.: DRILLING AND GROUTING DOWEL HOLES**                           |       |
| 842     | 81400     | 50   |     | 50    | POUNDS   | CONCRETE, MISC.: REPLACEMENT OF EXISTING REINFORCING STEEL**                   |       |
| 844     | 49500     | 12   |     | 12    | CU. YD.  | HIGH PERFORMANCE CONCRETE MISC.: DECK AND APPROACH SLAB EXTENSION, AS PER PLAN | 3 / 8 |
| 847     | 10000     | 138  |     | 138   | SQ. YD.  | MICROSILICA MODIFIED CONCRETE OVERLAY (1 3/4" THICKNESS)                       |       |
| 847     | 20000     | 2    |     | 2     | CU. YD.  | MICROSILICA MODIFIED CONCRETE OVERLAY (VARIABLE THICKNESS) **                  |       |

\* SEE PROPOSAL NOTE

\*\* CONTINGENCY QUANTITY TO BE USED AS DIRECTED BY THE ENGINEER

\$FILE\$ I:\PROJECTS\PI\B39\B&N\PLANS\B39\ISSA.DGN 09-NOV-2001 12:28PM fkomopk.d

DESIGN AGENCY  
BURGESS & NIPLE  
100 WEST ERIE STREET PAINESVILLE, OHIO 44077

DATE 2-28-01  
REVIEWED DWL  
DRAWN MKB  
DESIGNED MKB  
CHECKED SCT  
STRUCTURE FILE NUMBER 4302702

ESTIMATED QUANTITIES  
BRIDGE NO. LAK-44-0510  
JACKSON STREET OVER STATE ROUTE 44

LAKE COUNTY  
LAK-2/44-13.05/4.14  
4 / 8  
85D  
93