FED. RD. DIVISION	STATE	PROJECT	
2	OHIO	F-U-329 (15)	

LAK-2-4.42

288

8
18

R/W PLAN— LIMITED ACCESS

Lake County T-10-N City of Willoughby R-10-W

N

Sta. 154+54.33 Frontage Rd. = Sta. 31+84.26 Erie Rd.

LOT 113

LOT 115

RONALD S. PARSONS
5 LA Cont. 4.17 Ac.
P.R.O. = 0.45 Ac.

Cont. 0.083 Ac.

5 WA

Temporary Work Easement

5 Cont. 0.80 Ac.
P.R.O. = 0.74 Ac.

6 Cont. 0.26 Ac.
P.R.O. = 0.61 Ac.

HARRIET C. PARSONS
6 LA Cont. 0.89 Ac.
P.R.O. = 0.28 Ac.

6 WA Cont. 0.018 Ac.
P.R.O. = 0.007 Ac.

7 Cont. 0.90 Ac.
P.R.O. = 0.06 Ac.

EARL W. GILSON
7 LA Cont. 2.49 Ac.
P.R.O. = 0.20 Ac.

10 Cont. 0.05 Ac.

8 Cont. 0.47 Ac.

VETUS & SAM SYRACUSE
10A-LA Cont. 0.24 Ac.

ADOLPH & ADELE H. SCHWEERS
8 LA Cont. 2.14 Ac.

FELIX L. SYRACUSE
9 LA Cont. 1.55 Ac.

THE BOARD OF COUNTY COMMISSIONERS
4A LA P.R.O. = 0.25 Ac.
NO R/W Required

Sta. 28+23.00 Erie Road = Sta. 18+25.66 Reloc. St. Clair St.

R/W

Existing R/W

R/W FENCE

Limit of Construction

Partially Cleared Land

St. Clair St. (Gravel)

St. Clair St. (Avg. 24' Bit.)

℄ Reloc. St. Clair St.

Frontage Road

Constr. ℄

℄ Reloc. S.R.2

Match Line

Temporary Work Easement

Cellular Retaining Wall

Existing R/W

E.I.& E. Road

Storm Sewer Inlet

Fire Hyd.

Meter

Brush

Cultivated

Uncultivated

Partially Cleared Land

Gravel Pit Fill Ground Stockpiled

Scattered Evergreens Nursery Stock 18" High

Lawn

Flagstones

Concrete Slabs

Bldg. Cor.

Fr. Shed

Sty. Fr. Dwlg.

Barnyard

Chicken House

Chicken Run

Split Rail Fence

Locust Trees

Raspberry Area

Slag Dr.

Drive

(Earth) Drive

(Slag) Drive

(16' Gravel & Dirt)

Trail (9' Earth)

Road (24' Earth)

Pond

Chagrin River

Gilson Park
City of Willoughby
11 LA Cont. 0.78 Ac.

Pete Bere Zonsky
12 LA Cont. 17.34 Ac.
P.R.O. = 1.34 Ac.

Lot 13

The Cleveland Electric Illuminating Co.

R/W Easement Line

Limit of Construction

Existing R/W

High Voltage Transmission Towers

Conc. Mon.

Length of Arc = 723.41'
R = 4713.66'
Δ = 8° 47' 35.7"

Length of Arc = 877.84'
R = 4453.66'
Δ = 11° 17' 35.7"

CURVE DATA
P.I. Sta. 179 + 39.38
Δ = 28° 00' 00"
D = 1° 15' 00"
R = 4583.66'
L = 2240.00'
T = 1142.84'
E = 140.31'

S-24 REMOVAL OF STRUCTURES

PARCEL 5 LA	1	CHICKEN HOUSE
PARCEL 5 LA	1	BARN
PARCEL 5 LA	3	FRAME SHEDS
PARCEL 8 LA	1	1½ STY. BRICK HOUSE
PARCEL 8 LA	1	CONC. BLOCK GARAGE
PARCEL 8 LA	1	FRAME SHED

Clearance at Lowest Cable at Sta. 169+50 is 63.20'

(R) ROADWAY

REF NO.	STATION From	STATION To	SIDE	C.Y.	C.Y.	Fence Type "D" L.F.
1 R	150+00	180+00				5,592

DATE	REVISED
Jan. 16, 59	Submitted
Feb. 12, 59	Revised Area & Calls 7 LA, 7, 8 LA, 8. Add New Parcel 10A-LA. New Owner - 9 LA, 9
Apr. 6, 59	Revised R/W Line, Areas, Calls on 5 LA & 6 LA
Apr. 24, 59	FINAL

R/W PLAN STA. 150+00 TO STA. 180+00