GENERAL SUMMARY

SHEET NUMBER 4	5	7	9	12	13	14	ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION	AS PER PLAN DESIGNATION
											ROADWAY	
							201	11000	LUMP		CLEARING AND GRUBBING	
			179				202	22900	179	SQ.YD.	APPROACH SLAB REMOVED	
			465				202	23500	465	SQ.YD.	WEARING COURSE REMOVED	
						62.5	202	38000	62.5	LIN.FT.	GUARDRAIL REMOVED	
						4	202	42206	4	EACH	ANCHOR ASSEMBLY REMOVED	
						4	202	47000	4	EACH	BRIDGE TERMINAL ASSEMBLY REMOVED	
						32	202	75000	32	LIN.FT.	FENCE REMOVED	
10				76	30		203	12000	116	CU.YD.	EXCAVATION NOT INCLUDING EMBANKMENT CONSTRUCTION	
				34	25		203	20000	59	CU.YD.	EMBANKMENT	
			327				203	50000	327	SQ.YD.	SUBGRADE COMPACTION	
2							203	60000	2	STA.	LINEAR GRADING	
						112.5	606	13000	112.5	LIN.FT.	GUARDRAIL, TYPE 5	
						3	606	25000	3	EACH	ANCHOR ASSEMBLY, TYPE A	
						1	606	26500	1	EACH	ANCHOR ASSEMBLY, TYPE T	
						2	606	35000	2	EACH	BRIDGE TERMINAL ASSEMBLY, TYPE 1	
						2	606	35100	2	EACH	BRIDGE TERMINAL ASSEMBLY, TYPE 2	
						32	607	15000	32	LIN.FT.	FENCE, TYPE 47	
											DRAINAGE	
	50						603	01800	50	LIN.FT.	8" CONDUIT, TYPE B	
	50						603	02000	50	LIN.FT.	8" CONDUIT, TYPE C	
						4	604	34500	4	EACH	MANHOLE ADJUSTED TO GRADE	
											EROSION CONTROL	
131							207	10000	131	SQ.YD.	TEMPORARY SEEDING AND MULCHING	
200							207	30000	200	LIN.FT.	FILTER FABRIC FENCE	
100							207	70000	100	EACH	STRAW OR HAY BALES	
						533	601	21100	533	SQ.YD.	SLOPE PROTECTION, MISC.: GROUT FILLED FABRIC MATS	25, 31, 33
				505	148		659	10000	653	SQ.YD.	SEEDING AND MULCHING	
33							659	14000	33	SQ.YD.	REPAIR SEEDING AND MULCHING	
0.01			0.06				659	20000	0.07	TONS	COMMERCIAL FERTILIZER	
			0.29				659	30000	0.29	TONS	AGRICULTURAL LIMING	
2			1				659	35000	3	M.GAL.	WATER	
											PAVEMENT	
			29				301	46000	29	CU.YD.	BITUMINOUS AGGREGATE BASE, PG 64-22	
			50			6	304	20000	56	CU.YD.	AGGREGATE BASE	
10							304	20010	10	CU YD.	AGGREGATE BASE, GRADING A	
			35				407	10000	35	GAL.	TACK COAT	
			24				407	14000	24	GAL.	TACK COAT FOR INTERMEDIATE COURSE	
			41				448	46050	41	CU.YD.	ASPHALT CONCRETE, INTERMEDIATE COURSE, TYPE 2, PG 64-22	
			7				448	46060	7	CU.YD.	ASPHALT CONCRETE, INTERMEDIATE COURSE, TYPE 1, PG 64-22 (UNDER GUARDRAIL)	
			24				448	47020	24	CU.YD.	ASPHALT CONCRETE, SURFACE COURSE, TYPE 1, PG 64-22	
			112				609	26000	112	LIN.FT.	CURB, TYPE 6	
			156				611	25001	156	SQ.YD.	REINFORCED CONCRETE APPROACH SLAB (T=15"), AS PER PLAN	4