GENERAL SUMMARY

SHEET NUMBER 6	SHEET NUMBER 7	SHEET NUMBER 9	SHEET NUMBER 14	ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION	AS PER PLAN DESIGNATION
								MAINTENANCE OF TRAFFIC	
80				614	11100	80	HOUR	LAW ENFORCEMENT OFFICER WITH PATROL CAR	
50	50			614	13000	100	CU.YD.	BITUMINOUS CONCRETE FOR MAINTAINING TRAFFIC	
50	50			616	10000	100	M-GAL.	WATER	
5	5			616	20000	10	TONS	CALCIUM CHLORIDE	
		100		622	40020	100	LIN.FT.	PORTABLE CONCRETE BARRIER, 32"	
								TRAFFIC CONTROL	
	12			626	00100	12	EACH	BARRIER REFLECTOR, TYPE A	
	8			626	00200	8	EACH	BARRIER REFLECTOR, TYPE B	
			4	630	03100	4	LIN.FT.	GROUND MOUNTED SUPPORT, NO. 3 POST	
			1	630	08500	1	EACH	STREET NAME SIGN SUPPORT	
			5	630	75000	5	EACH	SIGN ATTACHMENT ASSEMBLY	
			10	630	80102	10	SQ.FT.	SIGN, FLAT SHEET, TYPE G	
			2	630	80506	2	EACH	SIGN, DOUBLE FACED, STREET NAME, TYPE G	
			3	630	86002	3	EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL	
	0.10			642	00302	0.10	MILE	CENTER LINE, TYPE 2	
	0.20			642	00102	0.20	MILE	EDGE LINE, TYPE 2	
	40			642	00502	40	LIN.FT.	STOP LINE, TYPE 2	
								STRUCTURE OVER 20' SPAN	
								BRIDGE LAK – 2 – 4.51	
								(FOR QUANTITIES SEE SHEET NO. 26)	
				614	11000	LUMP		MAINTAINING TRAFFIC	
				623	10000	LUMP		CONSTRUCTION LAYOUT STAKES	
				624	10000	LUMP		MOBILIZATION	
				806	16010	8	MONTH	FIELD OFFICE, TYPE B	