* - IN PLACE OF LANE LINE

LOCATION AND STATION		828												621		
		EDGE LINES		LANE LINES	CHANNELIZING LINES		STOP LINES	CROSSWALK LINES	TRANSVERSE LINES (WHITE)		LANE ARROWS	WORD ON PAVEMENT 96"		RAISED PAVEMENT MARKER, INSTALLATION ONLY		
		WHITE	YELLOW		GORE	*								W	W/R	Y/R
FROM	TO	LIN.FT.	LIN.FT.	LIN.FT.	LIN.FT.	LIN.FT.	LIN.FT.	LIN.FT.	LIN.FT.		EACH	EACH		EACH	EACH	EACH
S.R. 2 - EASTBOUND																
221+02.00	250+75.00	2973	2973	2973										26		
250+75.00	253+65.00	290	290	580										3		
253+65.00	254+90.00	125	125	125	250				120					2	7	
254+90.00	262+70.00	780	780	780										7		
262+70.00	265+75.00	305	305	610										3		
265+75.00	266+70.00	95	95	95	190				70					2	5	
266+70.00	273+10.00	640	640	640										6		
273+10.00	273+70.00	120	60	60	60									1	2	
273+70.00	276+90.00	320	320	640										3		
276+90.00	391+60.00	11470	11470	11470										98		
391+60.00	394+55.00	295	295	590										3		
394+55.00	395+60.00	105	105	105	210				95					1	6	
395+60.00	409+75.00	1415	1415	1415										12		
409+75.00	410+45.00	140	70	70	70									1	2	
410+45.00	413+85.00	340	340	680										3		
413+85.00	422+54.00	869	869	869										8		
422+35.00	549+05.00	12670	12670	12670										108		
549+05.00	551+70.00	265	265	530										3		
551+70.00	553+35.00	165	165	165	330				140					2	9	
553+35.00	570+40.00	1705	1705	1705										15		
570+40.00	571+25.00	170	85	85	85									1	2	
571+25.00	573+30.00	205	205	410										2		
573+30.00	586+47.00	1317	1317	1317										12		
S.R. 2 WESTBOUND																
221+02.00	252+35.00	3133	3133	3133										27		
252+35.00	255+55.00	320	320	640										3		
255+55.00	256+15.00	120	60	60	60									1	2	
256+15.00	262+85.00	670	670	670										6		
262+85.00	263+80.00	95	95	95	190				90					2	5	
263+80.00	266+90.00	310	310	620										3		
266+90.00	274+60.00	770	770	770										7		
274+60.00	276+20.00	160	160	160	320				160					2	8	
276+20.00	278+90.00	270	270	540										3		
278+90.00	391+75.00	11285	11285	11285										96		
391+75.00	395+05.00	330	330	660										3		
395+05.00	395+65.00	120	60	60	60									1	2	
395+65.00	410+80.00	1515	1515	1515										13		
410+80.00	411+90.00	110	110	110	220				100					2	6	
411+90.00	414+90.00	300	300	600										3		
414+90.00	422+54.00	764	764	764										7		
422+35.00	556+50.00	13415	13415	13415										114		
556+50.00	558+60.00	210	210	420										2		
558+60.00	559+35.00	150	75	75	75									1	2	
559+35.00	574+40.00	1505	1505	1505										13		
574+40.00	575+70.00	130	130	130	260				115					2	7	
575+70.00	578+55.00	285	285	570										3		
578+55.00	586+47.00	792	792	792										7		
S.R. 2 RAMPS																
RAMP K																
2+10.00	6+00.00	390	390													5
6+00.00	8+40.00	420	395			235	35	105			4	2			6	5
RAMP I																
1+10.00	7+05.00	595	595													8
RAMP I&J																
7+05.00	15+15.00	810	810				20	180								11
SHEET TOTAL		75753	75318	77173	2380	235	55	285	890		4	2		643	71	29
		= 28.61 MILE		= 14.62 MILE	2615									**	743	

** QUANTITY CARRIED TO SHEET 62

CALCULATED GJN
CHECKED LDH

PAVEMENT MARKING/RAISED PAVEMENT MARKER SUB-SUMMARY

LAKE COUNTY
LAK-2-6.12

PLOTTED FROM: I:\PROJECTS\P1d19530\DGN\19530tsa.dgn