SHEET NO.	REFERENCE NO.	ELEVATION VIEW SHEET NO.	LOCATION ROUTE	LOCATION DIRECTION	LOCATION STATION	LOCATION SIDE	CODE	SIZE	630 GROUND MOUNTED SUPPORT, S4X7.7 BEAM (LIN FT)	GROUND MOUNTED SUPPORT, W6X9 BEAM (LIN FT)	GROUND MOUNTED SUPPORT NO.3 POST (LIN FT)	ONE WAY SUPPORT NO.3 POST (LIN FT)		BREAKAWAY BEAM CONNECTION (EACH)	SIGN, FLAT SHEET, TYPE G (SQ FT)	SIGN, EXTRUSHEET, TYPE G (SQ FT)	GROUND MOUNTED BEAM SUPPORT FOUNDATION (EACH)		REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL (EACH)	REMOVAL OF GROUND MOUNTED SIGN AND REERECTION (EACH)	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL (EACH)	REMOVAL OF GROUND MOUNTED BEAM SUPPORT AND DISPOSAL (EACH)
67	1S		S.R. 2		234+38.00	RT		96"X48"		18.0X18.5				2			2			1	3	
68	2S		S.R. 2		256+08.00	LT					14.5-15.0									1	2	
68	3S		S.R. 2		259+00.00	LT					14.5-15.0									1	2	
68	4S		S.R. 2		263+28.00	LT					16.0-16.5									1	2	
69	6S		RAMP I&J		10+50.00	RT					14.5-15.0									1	2	
69	7S		RAMP O		6+79.00	RT					15.5-16.0									3	1	
69	8S		RAMP O		8+02.00	LT	R-41A-36	36"X24"			13.5				6							
69	9S		RAMP O		8+78.00	LT	R-41B-36	36"X36"			14.0	15.0			9						2	
							R-43R-36	36"X12"							3				1			
							R-121-36	36"X36"							9				1			
							R-43L-36	36"X12"							3				1			
																			1			
70	11S		RAMP K		5+50.00	RT					13.5-14.0									1	2	
70	12S		RAMP K		6+28.00	RT					14.5-15.0									2	1	
70	13S		RAMP K		7+03.00	RT	R-41A-36	36"X24"			13.5-14.0				6				1	2	1	
70	14S		RAMP K		7+03.00	LT	R-41A-36	36"X24"			13.5-14.0				6				1	2	1	
70	15S		RAMP M&N		1+20.00	LT	R-41B-36	36"X36"			14.5	15.5			9				3		2	
							R-31G-36	36"X24"							6							
							R-43L-36	36"X12"							3							
71	17S		S.R. 2		270+00.00	RT					14.5-15.0									1	2	
71	18S		RAMP O		6+00.00	RT	D-4A	132"X36"								33			1			
71	19S		RAMP O		3+48.00	RT	W-47-36	36"X36"			14.5-15.0				9				1		2	
71	20S		S.R. 2		288+07.00	RT					14.5-15.0									2	2	
71	21S		S.R. 2		292+28.00	℄					13.5									2	1	
71	22S		S.R. 2		292+65.00	℄					13.5									2	1	
74	24S		S.R. 2		370+00.00	LT					16.5-17.0									1	2	
74	25S		S.R. 2		371+16.00	℄					13.5									2	1	
74	26S		S.R. 2		371+74.00	℄					13.5									2	1	
75	28S		S.R. 2		380+00.00	LT					16.0-16.5									2	2	
75	29S		S.R. 2		396+19.00	RT	GF-72	72"X60"	17.5X18.0					2		30	2		1			2
75	30S		S.R. 2		398+39.00	LT					14.5-15.0									1	2	
77	32S		RAMP V		9+50.00	RT					14.5-15.0									1	2	
77	33S		S.R. 2		430+10.00	℄					13.5									2	1	
77	34S		S.R. 2		430+43.00	℄					13.5									2	1	
78	36S		S.R. 2		436+00.00	RT					16.5-17.0									1	2	
81	38S		S.R. 2		540+10.00	℄					13.5									2	1	
81	39S		S.R. 2		540+40.00	℄					13.5									2	1	
82	41S		RAMP S		4+70.00	RT					14.5-15.0									1	2	
82	42S		RAMP A		1+40.00	LT					16.5-17.0									1	2	
82	43S		S.R. 2		563+50.00	LT					14.5-15.0									1	2	
82	44S		RAMP D		4+50.00	LT					14.5-15.0									1	2	
85	46S		S.R. 2		582+23.00	RT					16.0-16.5									2	2	
					SUB-TOTALS				35.5	36.5	816.0	30.5		4	69	63	4		12	46	55	2

CALCULATED GJN
CHECKED LDH

SIGN SUB-SUMMARY

LAKE COUNTY
LAK-2-6.12

PLOTTED FROM: I:\PROJECTS\P1d19530\DGN\19530tsb.dgn