

I:\PROJECTS\PI19530\DGN\19530gga.dgn 22-AUG-2001 10:04AM fkonopka

SHEET NUMBER											ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
15	16	18	19	20	21	22	26	27	50							
											PAVEMENT					
1810											617	10101	1810	CU YD	COMPACTED AGGREGATE, TYPE A, AS PER PLAN	15
18											617	25000	18	M GAL	WATER	
	28.0										618	40600	28.0	MILE	RUMBLE STRIPS, TYPE 2 (ASPHALT)	
									147		830	26000	147	LIN FT	CURB, TYPE 6	
							14628	1688			858	10000	16316	CU YD	ASPHALT CONCRETE SURFACE COURSE, 12.5MM, TYPE A (446)	
							7312	829	11		858	20100	8152	CU YD	ASPHALT CONCRETE INTERMEDIATE COURSE, 9.5MM, TYPE A (448)	
											MAINTENANCE OF TRAFFIC					
			200								614	11100	200	HOOR	LAW ENFORCEMENT OFFICER WITH PATROL CAR	
				40							614	12470	40	EACH	WORK ZONE SPEED LIMIT SIGN	
				26							614	12480	26	EACH	DOUBLED FINES IN WORK ZONE SIGN	20
					200						614	13000	200	CU YD	BITUMINOUS CONCRETE FOR MAINTAINING TRAFFIC	18
					250						614	13001	250	CU YD	BITUMINOUS CONCRETE FOR MAINTAINING TRAFFIC, AS PER PLAN	
	12										614	18411	12	MONTH	PORTABLE CHANGEABLE MESSAGE SIGN, AS PER PLAN	
							43.86				614	20100	43.86	MILE	TEMPORARY LANE LINE, CLASS 1, 642 PAINT	
							96.78				614	22100	96.78	MILE	TEMPORARY EDGE LINE, CLASS 1, 642 PAINT	
							13695				614	23200	13695	LIN FT	TEMPORARY CHANNELIZING LINE, CLASS 1, 642 PAINT	
							720				614	26200	720	LIN FT	TEMPORARY STOP LINE, CLASS 1, 642 PAINT	
							108				614	30200	108	EACH	TEMPORARY LANE ARROW, CLASS 1, 642 PAINT	
							400				630	97800	400	SO FT	SIGNING, MISC.: ADDITIONAL SIGNS, GROUND MOUNTED, AS DIRECTED BY ENGINEER	
											TRAFFIC CONTROL					
											(SEE SHEET 64)					11
											614	11000	LUMP		MAINTAINING TRAFFIC	
											623	10001	LUMP		CONSTRUCTION LAYOUT STAKES, AS PER PLAN	
											624	10000	LUMP		MOBILIZATION	
											806	16010	12	MONTH	FIELD OFFICE, TYPE B	

GENERAL SUMMARY

LAK-2-6.12

CALCULATED
GJN
CHECKED
LDH