PAVEMENT PLANING AND RESURFACING QUANTITIES

STATION FROM	STATION TO	LENGTH	RESURFACING END WIDTHS (AVG.)	RESURFACING SURFACE AREA	254 PAVEMENT PLANING, AS PER PLAN		407 TACK COAT (0.1 GAL/SQ YD)	407 TACK COAT FOR INTERMEDIATE COURSE (0.05 GAL/SQ YD)	858 1 1/2" ASPHALT CONCRETE SURFACE COURSE, 12.5 MM, TYPE A (446)	858 1/2" ASPHALT CONCRETE INTERMEDIATE COURSE, 9.5 MM, TYPE A (448)	REMARKS
		LIN FT	LIN FT	SQ YD	SQ YD		GALLON	GALLON	CU YD	CU YD	
RAMP K											
2+07.17	3+07.53	50.00	29	161	161		16	8	7	3	
3+07.53	7+80.83	473.30	27	1420	1420		142	71	59	30	
7+80.83	8+15.45	34.62	26.25	101	101		10	5	4	2	
8+15.45	8+40.45	25.00	CADD	105	105		11	5	4	2	2" TO 1-1/2" OVERLAY
RAMP I											
1+83.73	3+11.72	127.99	26.875	382	382		38	19	16	8	
3+11.72	6+05.67	293.95	27	882	882		88	44	37	18	
6+05.67	6+64.14	58.47	27.875	181	181		18	9	8	4	
6+64.14	7+05.67	41.53	27	125	125		13	6	5	3	
RAMP I&J											
7+05.68	9+59.88	254.20	54	1525	1525		153	76	64	32	
9+59.88	10+59.95	100.07	52	578	578		58	29	24	12	
10+59.95	13+99.24	339.29	50	1885	1885		189	94	79	39	
13+99.24	14+64.82	65.58	25	182	182		18	9	8	4	
14+64.82	14+66.52	1.70	CADD	4	4		1	1	1	1	2" TO 1-1/2" OVERLAY
14+66.52	14+91.52	25.00	CADD	105	105		11	5	4	2	
RAMP I&J SPUR											
13+99.24	14+62.25	63.01	CADD	99	99		10	5	4	2	
14+62.25	14+91.52	29.27	CADD	65	65		6	3	2	1	2" TO 1-1/2" OVERLAY
RAMP J											
2+71.96	3+71.47	99.51	30	332	332		33	17	14	7	
3+71.47	6+69.00	297.53	29	959	959		96	48	40	20	
6+69.00	7+05.68	36.68	27	110	110		11	6	5	2	
RAMP M											
8+58.37	9+01.79	43.42	27	130	130		13	7	5	3	
9+01.79	11+83.88	282.09	29	909	909		91	45	38	19	
11+83.88	12+83.88	100.00	30	333	333		33	17	14	7	
RAMP N											
8+58.37	9+06.17	47.80	27	143	143		14	7	6	3	
9+06.17	9+58.37	52.20	28	162	162		16	8	7	3	
9+58.37	12+21.09	262.72	27	788	788		79	39	33	16	
12+21.09	13+48.93	127.84	26.875	382	382		38	19	16	8	
RAMP M&N											
0+48.93	0+73.93	25.00	CADD	97	97		10	5	3	2	1-1/2" TO 2" OVERLAY
0+73.93	0+81.17	7.24	CADD	15	15		2	1	1	1	
0+81.17	1+50.97	69.80	25	194	194		19	10	8	4	
1+50.97	5+10.14	359.17	52	2075	2075		208	104	86	43	
5+10.14	6+10.14	100.00	53	589	589		59	29	25	12	
6+10.14	8+58.37	248.23	54	1489	1489		149	74	62	31	
RAMP M&N SPUR											
0+48.93	0+77.20	28.27	CADD	93	93		9	5	3	2	1-1/2" TO 2" OVERLAY
0+77.20	1+50.97	73.77	CADD	164	164		16	8	7	3	
RAMP O											
2+54.62	3+54.62	100.00	29	322	322		32	16	13	7	
3+54.62	8+42.82	488.20	27	1465	1465		147	73	61	31	
8+42.82	8+72.12	29.30	CADD	82	82		8	4	3	2	
8+72.12	8+97.12	25.00	CADD	74	74		7	4	3	2	1-1/2" TO 2" OVERLAY
TOTAL (LEFT SIDE)					18707		1872	935	779	391	

ASPHALT TRANSITION (SEE ASPHALT TRANSITION DETAIL, SHEET 53.)

PAVEMENT PLANING AND RESURFACING QUANTITIES

STATION FROM	STATION TO	LENGTH	RESURFACING END WIDTHS (AVG.)	RESURFACING SURFACE AREA	254 PAVEMENT PLANING, AS PER PLAN		407 TACK COAT (0.1 GAL/SQ YD)	407 TACK COAT FOR INTERMEDIATE COURSE (0.05 GAL/SQ YD)	858 1 1/2" ASPHALT CONCRETE SURFACE COURSE, 12.5 MM, TYPE A (446)	858 1/2" ASPHALT CONCRETE INTERMEDIATE COURSE, 9.5 MM, TYPE A (448)	REMARKS
		LIN FT	LIN FT	SQ YD	SQ YD		GALLON	GALLON	CU YD	CU YD	
RAMP S											
5+56.48	6+56.48	100.00	29	322	322		32	16	13	7	
6+56.48	7+56.48	100.00	33	367	367		37	18	15	8	
7+56.48	8+50.00	93.52	39	405	405		41	20	17	8	
8+50.00	11+58.26	308.26	42	1439	1439		144	72	60	30	
11+58.26	11+83.26	25.00	CADD	156	156		16	8	5	3	2" TO 1-1/2" OVERLAY
RAMP O											
6+33.84	7+88.12	154.28	25.75	441	441		44	22	18	9	
7+88.12	13+11.30	523.18	27	1570	1570		157	79	65	33	
13+11.30	13+24.30	13.00	CADD	41	41		4	2	2	1	2" TO 1-1/2" OVERLAY
13+24.30	13+49.30	25.00	CADD	129	129		13	6	4	3	
RAMP V											
3+72.73	3+97.76	25.03	CADD	153	153		15	8	5	3	2" TO 3-1/2" OVERLAY
3+97.76	4+07.14	9.38	CADD	40	40		4	2	2	1	
4+07.14	9+00.00	492.86	42	2300	2300		230	115	96	48	
9+00.00	9+37.62	37.62	40.5	169	169		17	8	7	4	
9+37.62	9+65.38	27.76	37.5	116	116		12	6	5	2	
9+65.38	9+95.68	30.30	31.5	106	106		11	5	4	2	
9+95.68	10+95.68	100.00	29	322	322		32	16	13	7	
RAMP T											
1+78.47	2+03.47	25.00	CADD	86	86		9	4	3	2	2" TO 3-1/2" OVERLAY
2+03.47	7+70.69	567.22	27	1702	1702		170	85	71	35	
7+70.69	8+21.61	50.92	27.5	156	156		16	8	6	3	
RAMP A											
2+41.47	3+39.50	98.03	27	294	294		29	15	12	6	
3+39.50	12+05.01	865.51	27	2597	2597		260	130	108	54	
12+05.01	12+14.40	9.39	CADD	31	31		3	2	1	1	2" TO 1-1/2" OVERLAY
12+14.40	12+39.40	25.00	CADD	135	135		14	7	5	3	
RAMP B											
3+24.66	4+25.02	100.36	29	323	323		32	16	13	7	
4+25.02	8+03.88	378.86	27	1137	1137		114	57	47	24	
8+03.88	9+63.88	160.00	31	551	551		55	28	23	11	
9+63.88	10+73.72	109.84	35	427	427		43	21	18	9	
10+73.72	10+88.72	15.00	CADD	61	61		6	3	3	1	2" TO 1-1/2" OVERLAY
10+88.72	11+13.72	25.00	CADD	178	178		18	9	6	4	
RAMP C											
0+34.03	0+59.03	25.00	CADD	138	138		14	7	5	3	1-1/2" TO 2" OVERLAY
0+59.03	0+68.44	9.41	CADD	32	32		3	2	1	1	
0+68.44	9+14.88	846.44	27	2539	2539		254	127	106	53	
9+14.88	10+06.54	91.66	27.125	276	276		28	14	12	6	
RAMP D											
0+33.13	0+58.13	25.00	CADD	174	174		17	9	6	4	1-1/2" TO 2" OVERLAY
0+58.13	0+64.19	6.06	CADD	26	26		3	1	1	1	
0+64.19	1+92.50	128.31	35	499	499		50	25	21	10	
1+92.50	3+52.36	159.86	31	551	551		55	28	23	11	
3+52.36	5+53.41	201.05	27	603	603		60	30	25	13	
5+53.41	6+53.41	100.00	29	322	322		32	16	13	7	
U-TURN MEDIAN OPENINGS											
292+50.00			CADD	96			10		4		1-1/2" ASPHALT OVERLAY
371+60.00			CADD	327			33		14		1-1/2" ASPHALT OVERLAY
430+25.00			CADD	328			33		14		1-1/2" ASPHALT OVERLAY
540+25.00			CADD	339			34		14		1-1/2" ASPHALT OVERLAY
TOTAL (THIS SIDE)					20914		2204	1047	906	438	
TOTAL (LEFT SIDE)					18707		1872	935	782	391	
TOTAL TO GENERAL SUMMARY					39621		4076	1982	1688	829	

CALCULATED GJN
CHECKED LDH

RESURFACING QUANTITIES

LAKE COUNTY
LAK-2-6.12

PLOTTED FROM: i:\PROJECTS\Pid19530\DGN\19530gqa.dgn