

RAISED PAVEMENT MARKERS (RPM)

CALCULATIONS
MADE BY _____ DATE _____
CHECKED BY _____ DATE _____

FHWA REGION	STATE	PROJECT			
5	OHIO			102	153
LAKE COUNTY LAK-2 - 6.14					

ROADWAY	STATION TO STATION		SIDE	INTERVAL	ONE WAY		TWO WAY			
					WHITE	YELLOW	W/R	Y/R	W/W	Y/Y
CITY OF MENTOR										
SR-2	221+27.5	586+22.12	R	80						456
	253+23	253+63	R	40	2					
	253+63	254+80	R	20	6					
	254+80	255+60	R	40	2					
	265+10	265+50	R	40	2					
	265+50	266+55	R	20	5					
	266+55	267+35	R	40	2					
	272+00	274+45	R	40	7					
	294+20	294+60	R	40	2					
	294+60	295+60	R	20	5					
	295+60	269+40	R	40	2					
	407+70	411+61	R	40	10					
	550+95	551+35	R	40	2					
	551+35	553+30	R	20	10					
	553+30	554+10	R	40	2					
	568+85	571+40	R	40	7					
	SUB-TOTAL	CITY OF MENTOR			66					456
PAINESVILLE TWP.										
SR-2	586+22.12	652+30	R	80						83
	599+85	600+25	R	40	2					
	600+25	601+90	R	20	8					
	601+90	602+80	R	40	2					
	621+60	625+00	R	40	10					
	SUB-TOTAL	PAINESVILLE TWP.			22					83
CITY OF PAINESVILLE										
SR-2	652+30	658+00	R							7
	TOTAL	CITY OF PAINESVILLE								7
CITY OF MENTOR										
SR-2	221+27.5	586+22.12	L	80						456
	254+85	257+40	L	40	7					
	262+16	262+96	L	40	2					
	262+96	264+08	L	20	6					
	264+08	264+48	L	40	1					
	273+90	274+70	L	40	2					
	274+70	276+20	L	20	9					
	276+20	276+60	L	40	1					
	393+95	396+80	L	40	8					
	410+05	410+85	L	40	2					
	410+85	412+10	L	20	7					
	412+10	412+50	L	40	1					
	557+81	561+05	L	40	9					
	573+60	574+40	L	40	2					
	574+40	575+90	L	20	8					
	575+90	576+40	L	40	1					
	SUB-TOTAL	CITY OF MENTOR			66					456
PAINESVILLE TWP.										
SR-2	586+22.12	658+00	L	80						90
	598+55	601+10	L	40	7					
	624+89	625+69	L	40	2					
	625+69	627+20	L	20	8					
	627+20	627+60	L	40	1					
	SUB-TOTAL	PAINESVILLE TWP.			18					90

ROADWAY	STATION TO STATION		SIDE	INTERVAL	ONE WAY		TWO WAY			
					WHITE	YELLOW	W/R	Y/R	W/W	Y/Y
CITY OF MENTOR										
RAMP F-1	0+25	1+00	L	40	2					
	1+00	7+05	L	40		16				
	7+05	9+59	L	20		12				
	9+59	14+50	L	40		12				
RAMP F-2	1+80	2+70	L	20	5					
	2+70	7+05	L	40				11		
	7+05	9+59	L	20				12		
	9+59	14+50	L	40				12		
RAMP F-3	1+00	3+55	L	20	12					
	3+55	9+00	L	40				14		
RAMP F-4	0+60	6+20	R	40		15				
	6+20	8+60	R	20		12				
	8+60	14+20	R	40		14				
	14+20	15+20	R	40	3					
RAMP F-5	0+60	6+30	R	40					15	
	6+30	12+00	R	20					28	
	12+00	13+72	R	20	9					
RAMP F-6	0+90	3+00	R	20	10					
	3+00	8+30	R	40				14		
RAMP G-1	4+32	5+60	R	40	3					
	5+60	13+60	L	40		21				
RAMP G-2	4+00	10+00	L	40					16	
	10+00	12+10	L	20	10					
RAMP G-3	1+70	9+70	R	40		21				
	9+70	11+25	R	40	4					
RAMP G-4	4+60	6+60	R	20	10					
	6+60	11+70	R	40				13		
RAMP H-1	0+22	1+40	L	40	4					
	1+40	12+00	L	40		27				
RAMP H-2	0+50	2+00	L	20,40*	8				4*	
	2+00	5+50	L	40					8	
	5+50	8+00	L	20	12					
RAMP H-3	0+50	11+10	R	40		27				
	11+10	11+85	R	40	3					
RAMP H-4	1+30	4+25	R	20	14					
	4+25	9+63	R	40				13		
	9+63	11+00	R	20,40*	7			3*		
	SUB-TOTAL	CITY OF MENTOR			116	177				163
PAINESVILLE TWP.										
RAMP I-2	20+85	21+60	R	40	3	2				
	21+60	43+20	R	40		54				
	43+20	45+80	R	20	13					
RAMP I-4	1+00	3+60	R	20	13					
	3+60	16+65	R	40		32				
	SUB-TOTAL	PAINESVILLE TWP.			29	88				

ROADWAY	STATION TO STATION		SIDE	INTERVAL	ONE WAY		TWO WAY			
					WHITE	YELLOW	W/R	Y/R	W/W	Y/Y
CITY OF MENTOR										
HEISLEY RD.	22+60	23+75	R	20	6					6
OVER SR.2	24+25	25+60	R	20	7					7
	25+60	34+50	R	40	22					22
	34+50	35+90	R	20	14					7
	36+25	37+25	R	20	5					5
	22+60	23+75	L	20	5					5
	24+25	25+75	L	20	16					8
	25+75	34+50	L	40	21					21
	34+50	35+90	L	20	7					7
	36+25	37+25	L	20	5					5
	SUB-TOTAL	CITY OF MENTOR			108					93

CITY TOTALS	ONE WAY		TWO WAY				ITEM SPECIAL
	WHITE	YELLOW	W/R	Y/R	W/W	Y/Y	
CITY OF MENTOR	356	177	1005	163		93	RAISED PAV'T MARKERS
PAINESVILLE TOWNSHIP	69	88	173				1794
CITY OF PAINESVILLE			7				7

COLOR KEY FOR ABOVE:
W/R = WHITE / RED
Y/R = YELLOW / RED
W/W = WHITE / WHITE
Y/Y = YELLOW / YELLOW