

# TRAFFIC CONTROL QUANTITIES

PAVEMENT MARKINGS    ITEM 62I PAINT																					
ROADWAY	SIDE	STATION		EDGE LINE (WHITE)	EDGE LINE (YELLOW)	4" LANE LINE	8" CHANNEL LINE (WHITE)	24" STOP LINE	24" TRANSVERSE LINE (WHITE)	LANE ARROWS	WORD "ONLY" ON PAVEMENT										
		FROM	TO											LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	LIN. FT.	EACH	EACH
CITY OF MENTOR (CONT'D)																					
RAMP F-6		0+90	3+01	211			211														
		3+01	8+40	549	539		230			4	2										
		8+30						25													
RAMP G-1		4+08	5+62	154			154														
		5+62	13+60	798	798																
RAMP G-2		3+75	9+90	620	615																
		9+90	12+10	220		205	220			4	2										
		3+80	9+00				315	35													
RAMP G-3		1+67	9+70	823	806																
		9+70	11+45	175			175														
RAMP G-4		4+58	6+58	200			200														
		6+58	11+82	532	526																
		7+50	11+70				840	45		9	4										
RAMP H-1		0+00	1+42	142			142														
		1+42	12+30	1088	1088																
RAMP H-2		0+40																			
		0+40	2+00	160	160		160			4	2										
		2+00	5+50	350	350																
RAMP H-3																					
		5+50	8+00	250			250														
		0+30	11+15	1085	1085																
RAMP H-4		11+15	12+08	93			93														
		1+30	4+25	295			295														
		4+25	9+63	538	538					4	2										
	9+63	11+10	147	147			137														
	11+00							30													
HEISLEY RD. OVER S.R. 2																					
NORTHBOUND		21+70	23+75	205	205		205														
		24+10	34+50	1040	1040	1040				2	1										
		34+50	35+90	140	140	140															
SOUTHBOUND		36+25	37+24	99	99	99															
		22+40	23+75	135	135	135															
		24+10	25+75	165	165	165				2	1										
		25+75	35+90	1015	1015	1015															
		36+25	38+30	205	205	205															
TOTAL CITY OF MENTOR				88,850 = 16.83 MI.	88,057 = 16.68 MI.	79,813 = 15.12 MI.	6709	280	793	29	14										