

SUPERELEVATION TABLES

FED. RD. DIVISION	STATE	PROJECT	9
2	OHIO	F-329 (16)	268

LAKE COUNTY
LAK-2-7.39

P.I. STA. 413 + 94.11

RELOC. S. R. 2

SUPER=0.064'/FT.

STATION	66' LEFT	54' LEFT	42' LEFT	30' LEFT & RIGHT	42' RIGHT	54' RIGHT	66' RIGHT
404+50		651.31	651.50	651.31	651.50	651.31	
404+75		651.07	651.26	651.13	651.32	651.19	
405+00		650.83	651.02	650.95	651.14	651.07	
405+02.23		650.81	651.00	650.94	651.13	651.07	
405+25		650.56	650.75	650.75	650.94	650.94	
405+50		650.22	650.41	650.53	650.72	650.84	
405+63.5		650.04	650.23	650.42	650.61	650.80	
405+75		649.89	650.10	650.32	650.54	650.75	
406+00		649.51	649.79	650.07	650.35	650.63	
406+25		649.14	649.48	649.82	650.16	650.50	
406+50		648.74	649.14	649.54	649.94	650.34	
406+75		648.34	648.80	649.26	649.72	650.18	
407+00		647.92	648.44	648.96	649.48	650.00	
407+25		647.48	648.06	648.64	649.22	649.80	
407+50		647.03	647.68	648.32	648.96	649.61	
407+75		646.57	647.27	647.98	648.69	649.39	
408+00		646.09	646.86	647.62	648.38	649.15	
408+02.23		646.05	646.82	647.59	648.36	649.13	
408+25		645.71	646.48	647.25	648.02	648.79	
408+50		645.32	646.09	646.86	647.63	648.40	
408+75		644.92	645.69	646.46	647.23	648.00	
409+00		644.51	645.28	646.05	646.82	647.59	
409+25		644.08	644.85	645.62	646.39	647.16	
409+50		643.63	644.40	645.17	645.94	646.71	
409+75		643.18	643.95	644.72	645.49	646.26	
410+00		642.71	643.48	644.25	645.02	645.79	
410+25		642.23	643.00	643.77	644.54	645.31	
410+50		641.75	642.52	643.29	644.06	644.83	
410+75		641.28	642.05	642.82	643.59	644.36	
411+00		640.82	641.59	642.36	643.13	643.90	
411+25		640.38	641.15	641.92	642.69	643.46	
411+50		639.97	640.74	641.51	642.28	643.05	
411+75		639.56	640.33	641.10	641.87	642.64	
412+00		639.16	639.93	640.70	641.47	642.24	643.01
412+25		638.79	639.56	640.33	641.10	641.87	642.64
412+50		638.43	639.20	639.97	640.74	641.51	642.28
412+75		638.08	638.85	639.62	640.39	641.16	641.93
413+00	636.98	637.75	638.52	639.29	640.06	640.83	641.60
413+25	636.67	637.44	638.21	638.98	639.75	640.52	641.29
413+50	636.38	637.15	637.92	638.69	639.46	640.23	641.00
413+75	636.10	636.87	637.64	638.41	639.18	639.95	640.72
414+00	635.83	636.60	637.37	638.14	638.91	639.68	640.45
414+25	635.58	636.35	637.12	637.89	638.66	639.43	640.20
414+50	635.35	636.12	636.89	637.66	638.43	639.20	639.97
414+75	635.13	635.90	636.67	637.44	638.21	638.98	639.75
414+86.18	635.04	635.81	636.58	637.35	638.12	638.89	639.66
415+00		635.69	636.46	637.23	638.00	638.77	639.54
415+25		635.51	636.28	637.05	637.82	638.59	639.36
415+50		635.34	636.11	636.88	637.65	638.42	639.19
415+75		635.18	635.95	636.72	637.49	638.26	639.03
416+00		635.04	635.81	636.58	637.35	638.12	638.89
416+25		634.92	635.69	636.46	637.23	638.00	638.77
416+50		634.81	635.58	636.35	637.12	637.89	638.66
416+75		634.71	635.48	636.25	637.02	637.79	638.56
416+75.24		634.71	635.48	636.25	637.02	637.79	638.56
417+00		634.61	635.38	636.15	636.92	637.69	
417+25		634.51	635.28	636.05	636.82	637.59	
417+50		634.41	635.18	635.95	636.72	637.49	
417+75		634.31	635.08	635.85	636.62	637.39	
418+00		634.21	634.98	635.75	636.52	637.29	
418+25		634.11	634.88	635.65	636.42	637.19	
418+50		634.01	634.78	635.55	636.32	637.09	
418+75		633.91	634.68	635.45	636.22	636.99	
419+00		633.81	634.58	635.35	636.12	636.89	
419+25		633.71	634.48	635.25	636.02	636.79	
419+50		633.61	634.38	635.15	635.92	636.69	
419+53.48		633.60	634.37	635.14	635.91	636.68	
419+75		633.62	634.34	635.05	635.76	636.48	
420+00		633.64	634.29	634.95	635.61	636.26	
420+25		633.67	634.26	634.85	635.44	636.03	
420+50		633.69	634.22	634.75	635.28	635.81	
420+75		633.71	634.18	634.65	635.12	635.59	

STATION	66' LEFT	54' LEFT	42' LEFT	30' LEFT & RIGHT	42' RIGHT	54' RIGHT	66' RIGHT
421+00		633.74	634.14	634.55	634.96	635.36	
421+25		633.76	634.11	634.45	634.79	635.14	
421+50		633.79	634.07	634.35	634.63	634.91	
421+75		633.81	634.03	634.25	634.47	634.69	
421+87.29		633.82	634.01	634.20	634.39	634.58	
422+00		633.84	634.03	634.15	634.34	634.46	
422+25		633.86	634.05	634.05	634.24	634.24	
422+50		633.81	634.00	633.95	634.14	634.09	
422+53.48 Constr. G. Bk. =							
422+35.03 Survey G. Ahd.		633.81	634.00	633.94	634.13	634.07	
422+50		633.78	633.97	633.88	634.07	633.98	
422+75		633.73	633.92	633.78	633.97	633.83	
423+00		633.68	633.87	633.68	633.87	633.68	

P.I. STA. 28 + 32.51

SUPER = 0.025'/FT.

P.I. STA. 28 + 32.51

SUPER = 0.025'/FT.

RECONSTR. MUNSON ROAD

RECONSTR. MUNSON ROAD

STATION	12' LEFT	PROFILE GRADE	12' RIGHT
20+50	634.01	634.28	634.19
20+75	633.81	633.96	633.87
21+00	633.61	633.64	633.55
21+26.61	633.39	633.30	633.21
21+50	633.21	633.00	632.79
21+75	632.98	632.68	632.38
22+00	632.70	632.40	632.10
22+25	632.50	632.20	631.90
22+50	632.37	632.07	631.77
22+75	632.32	632.02	631.72
23+00	632.34	632.04	631.74
23+25	632.44	632.14	631.84
23+50	632.61	632.31	632.01
23+75	632.86	632.56	632.26
24+00	633.19	632.89	632.59
24+25	633.60	633.30	633.00
24+50	634.07	633.77	633.47
24+75	634.63	634.33	634.03
25+00	635.26	634.96	634.66
25+25	635.97	635.67	635.37
25+50	636.75	636.45	636.15
25+75	637.61	637.31	637.01
26+00	638.51	638.21	637.91
26+25	639.41	639.11	638.81
26+50	640.31	640.01	639.71
26+75	641.20	640.90	640.60
27+00	642.04	641.74	641.44
27+25	642.81	642.51	642.21
27+50	643.51	643.21	642.91
27+75	644.11	643.81	643.51
28+00	644.68	644.35	644.05
28+25	645.11	644.81	644.51
28+50	645.49	645.19	644.89
28+75	645.79	645.49	645.19
29+00	646.02	645.72	645.42
29+25	646.17	645.87	645.57
29+50	646.24	645.94	645.64
29+75	646.24	645.94	645.64
30+00	646.16	645.86	645.56
30+25	646.01	645.71	645.41
30+50	645.76	645.46	645.16
30+75	645.45	645.15	644.85
31+00	645.07	644.77	644.47
31+25	644.60	644.30	644.00
31+50	644.05	643.75	643.45
31+75	643.43	643.13	642.83
32+00	642.74	642.44	642.14
32+25	641.97	641.67	641.37
32+50	641.11	640.81	640.51
32+75	640.18	639.88	639.58
33+00	639.23	638.93	638.63
33+25	638.32	638.02	637.72
33+50	637.49	637.19	636.89
33+75	636.74	636.44	636.14

STATION	12' LEFT	PROFILE GRADE	12' RIGHT
34+00	636.08	635.78	635.48
34+25	635.50	635.20	634.90
34+50	635.00	634.70	634.40
34+75	634.58	634.28	633.98
35+00	634.24	633.94	633.64
35+25	633.99	633.69	633.39
35+50	633.82	633.52	633.22
35+75	633.60	633.39	633.01
36+00	633.35	633.26	632.79

P.I. STA. 36 + 88.92

SUPER = 0.0833'/FT.

RELOC. HOPKINS ROAD

STATION	12' LEFT	PROFILE GRADE	12' RIGHT
31+65	625.77	625.96	625.77
31+75	625.73	625.92	625.76
32+00	625.69	625.88	625.78
32+25	625.71	625.90	625.86
32+50	625.79	625.98	626.03
32+52.82	625.81	626.00	626.06
32+75	625.86	626.14	626.32
33+00	625.94	626.33	626.63
33+25	626.02	626.52	626.94
33+50	626.10	626.71	627.26
33+75	626.18	626.90	627.57
34+00	626.26	627.09	627.89
34+25	626.35	627.28	628.20
34+50	626.47	627.47	628.47
34+75	626.66	627.66	628.66
35+00	626.85	627.85	628.85
35+25	627.04	628.04	629.04
35+50	627.23	628.23	629.23
35+75	627.42	628.42	629.42
36			