



93 94 95 96 97 98 99 100 101 102 103 104 105 106 107 108 109 110 111 112 113 114 115 116 117 118 119 120 121 122 123 124

**EXTRA AREA**

Arbor Avenue	44 Sq. Yds. - Wickliffe
E. 305th Street	35 Sq. Yds. - Willowick
<b>Total</b>	<b>79 Sq. Yds.</b>

**SURFACE REMOVAL & DISPOSAL**

Extra Area	79 Sq. Yds.	Total	79 Sq. Yds.	Wickliffe	44 Sq. Yds.	Willowick	35 Sq. Yds.
Sta. 93+00 to Sta. 124+00 = 3100' x 8' = 24800 Sq. Ft. ÷ 9 =	2755.55 Sq. Yds.			2332.11 Sq. Yds.	423.44 Sq. Yds.		
(Sta. 93+00 to Sta. 116+25 = 2325' x 32' = 74400 ÷ 9 =	8266.67			7950.69 Sq. Yds.	315.98 Sq. Yds.		
* (Sta. 116+25 to Sta. 118+54 = 229' x 31' = 7099 ÷ 9 =	788.89			394.44 Sq. Yds.	394.45 Sq. Yds.		
(Sta. 118+54 to Sta. 124+00 = 546' x 30' = 16380 ÷ 9 =	1820.00			910.00 Sq. Yds.	910.00 Sq. Yds.		
2% of 10,875.56 =	217.51 Sq. Yds.			185.10 Sq. Yds.	32.41 Sq. Yds.		
<b>Total</b>	<b>3052.06 Sq. Yds.</b>			2561.21 Sq. Yds.	490.85 Sq. Yds.		

**MAN. BOX ADJUSTED TO GRADE** 1 Each - Willowick

**SEWERS**  
Catchbasin Casting adjusted to grade 2 Each Wickliffe  
Sanitary Manhole Casting adjusted to grade 1 Each Wickliffe

\* Note: - Surface Course in this area to be removed as directed by the Engineer