

ESTIMATED QUANTITIES FOR USR 20 (MENTOR AVE.)

ITEM	ITEM EXT.	TOTAL	UNIT	DESCRIPTION
254	01000	299	SQ. YD.	PAVEMENT PLANNING, BITUMINOUS
407	10000	22	GAL.	TACK COAT
448	47020	10	CU. YD.	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG 64-22
614	11000	LUMP		** MAINTAINING TRAFFIC
614	13000	1	CU. YD.	BITUMINOUS CONCRETE FOR MAINTAINING TRAFFIC
624	10000	LUMP		** MOBILIZATION
642	00202	0.05	MI.	4" DASHED WHITE LANE LINE, TYPE 2
642	00302	0.15	MI.	4" DOUBLE YELLOW CENTER LINE, TYPE 2
642	00402	227	LIN. FT.	8" WHITE CHANNELIZING LINE, TYPE 2
642	00502	52	LIN. FT.	24" WHITE STOP LINE, TYPE 2
642	00602	98	LIN. FT.	12" WHITE CROSSWALK LINE, TYPE 2
642	01002	1	EACH	RAILROAD SYMBOL MARKING, TYPE 2
642	01102	1	EACH	SCHOOL SYMBOL MARKING, 72", TYPE 2
642	01302	2	EACH	RIGHT TURN LANE ARROW, TYPE 2
642	01402	1	EACH	WORD "ONLY" ON PAVEMENT, 72" TYPE 2
SPECIAL	512 67520	259	SQ. YD.	SEALING OF CONCRETE SURFACES WITH TINTED SILANE
SPECIAL	512 71500	504	SQ. YD.	URETHANE TOP COAT SEALER
SPECIAL	512 67510	668	SQ. YD.	SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)
516	14600	104	LIN. FT.	STRUCTURAL JOINT OR JOINT SEALER, MISC: ELASTOMERIC STRIP SEAL
SPECIAL	519 12602	240	SQ. FT.	* LOW PRESSURE EPOXY INJECTING OF DELAMINATED CONCRETE - DECK BOTTOM SURFACE
SPECIAL	519 11704	45	LIN. FT.	* PATCHING CONCRETE STRUCTURES, MISC: PATCHING CURBS
SPECIAL	519 23000	LUMP		CATHODIC SYSTEM
530	00400	2	EACH	STRUCTURES MISC: REPLACEMENT PULL BOX COVER PLATE
530	00600	11922	SQ. FT.	STRUCTURES MISC: SOUNDING CONCRETE DECK BOTTOM AND REMOVING SPALLS
607	98000	240	LIN. FT.	FENCE, MISC: FENCE FABRIC REMOVED AND REPLACED
847	10000	1231	SQ. YD.	MICROSILICA MODIFIED CONCRETE OVERLAY, 2 1/4" THICK
847	20000	26	CU. YD.	MICROSILICA MODIFIED CONCRETE OVERLAY, (VARIABLE THICKNESS)
847	30000	LUMP		TEST SLAB
847	30300	15	SQ. YD.	WEARING COURSE REMOVED, ASPHALT
847	30400	1221	SQ. YD.	EXISTING CONCRETE OVERLAY REMOVED, 1 1/4" NOMINAL THICKNESS
843	50000	330	SQ. FT.	* PATCHING CONCRETE STRUCTURES WITH TROWELABLE MORTAR
848	20000	1221	SQ. YD.	SURFACE PREPARATION USING HYDRODEMOLITION
848	50000	137	SQ. YD.	HAND CHIPPING
863	10001	LUMP		STRUCTURAL STEEL MEMBERS, MISCELLANEOUS LEVEL FABRICATION, AS PER PLAN

* CONTINGENCY QUANTITY TO BE USED "AS DIRECTED BY THE ENGINEER".

** THE PRICE BID FOR THESE ITEMS SHALL INCLUDE THE COST OF PERFORMING THE WORK ON BOTH THE USR-20 BRIDGE OVER SR-44 AND THE JACKSON STREET BRIDGE OVER SR-44.

CONTINGENCY QUANTITIES

THE CONTRACTOR SHALL NOT ORDER MATERIALS OR PERFORM WORK FOR PLAN ITEMS SET UP TO BE USED "AS DIRECTED BY THE ENGINEER" UNLESS AUTHORIZED BY THE ENGINEER.

BURGESS & NIPLÉ

DATE: 4-28-00
 REVIEWED: DWL
 STRUCTURE FILE NUMBER: 4302133

DRAWN: DCF
 DESIGNED: DCF
 CHECKED: MAR
 REVISIONS:

ESTIMATED QUANTITIES
 BRIDGE NO. LAK-20-1434
 US ROUTE 20 OVER STATE ROUTE 44

LAK-20-14.34
 LAK-44-5.10

4 / 12

13
25