ESTIMATED QUANTITIES FOR JACKSON STREET

ITEM	ITEM EXT.	TOTAL	UNIT		DESCRIPTION
SPECIAL	512 67520	205	SQ. YD.		SEALING OF CONCRETE SURFACES WITH TINTED SILANE
SPECIAL	512 71500	705	SQ. YD.		URETHANE TOP COAT SEALER
SPECIAL	512 67510	385	SQ. YD.		SEALING OF CONCRETE SURFACES (EPOXY-URETHANE)
SPECIAL	519 12602	75	SQ. FT.	*	LOW PRESSURE EPOXY INJECTING OF DELAMINATED CONCRETE - DECK BOTTOM SURFACE
519	11600	80	SQ. FT.	*	PATCHING CONCRETE STRUCTURE, MISC: PATCHING CONCRETE BRIDGE DECK AS PER PLAN
530	00400	1	EACH		STRUCTURES MISC:, REPLACEMENT PULL BOX COVER PLATE
530	00600	7377	SQ. FT.		STRUCTURES MISC:, SOUNDING CONCRETE DECK BOTTOM AND REMOVING SPALLS
843	50000	382	SQ. FT.	*	PATCHING CONCRETE STRUCTURES WITH TROWELABLE MORTAR
863	10001	LUMP			STRUCTURAL STEEL MEMBERS, MISCELLANEOUS LEVEL FABRICATION, AS PER PLAN

* CONTINGENCY QUANTITY TO BE USED "AS DIRECTED BY THE ENGINEER".

CONTINGENCY QUANTITIES

THE CONTRACTOR SHALL NOT ORDER MATERIALS OR PERFORM WORK FOR PLAN ITEMS SET UP TO BE USED "AS DIRECTED BY THE ENGINEER" UNLESS AUTHORIZED BY THE ENGINEER.

NOTE: SEE THE NOTE ON SHEET 13/25 CONCERNING PAYMENT FOR MAINTAINING TRAFFIC AND MOBILIZATION.

BURGESS & NIPLE

DESIGNED	DRAWN	REVISED	DATE
DCF	DCF	DWL	4-28-00
CHECKED	REVISED	STRUCTURE FILE NUMBER	
WAR		4302702	

ESTIMATED QUANTITIES
BRIDGE NO. LAK-44-0510
JACKSON STREET OVER STATE ROUTE 44

LAK-20-14.34
LAK-44-5.10

3/4

24/25

p:\PR25940\CADD\21365SGJ.dgn May. 01, 2000 09:40:02