

SUMMARY OF VARIOUS WIDTHS

	40' WIDTH 6+68.6 to 16+50.58	43' WIDTH 16+50.58 to 77+87	41' WIDTH 77+87 to 144+43	TOTALS 6+68.6 to 144+43
<b>ROADWAY</b>				
Cu. Yds. Excavation unclassified, including removal of 3110 sq. yds. exist. monolithic bricks pav.	4228.7	6551.2	4316.3	15096
Cu. Yds. Excavation borrow	00	2045	0	2045
Lin. Ft. Finishing shoulders, slopes, etc. (both sides)	1110	6112	6656	13878
Cu. Yds. 4C stone, road approach	40	0	0	40
Monument casting reset	0	0	1	1
Lin. Ft. type D-1, D-2, D-3, D-4 guard rail	928	1216	392	2536
Lin. Ft. guard rail reset	100	309	0	409
Manhole complete	1	0	0	1
Lin. Ft. 12" V.S.P. or R.C.P.	260	1360	2864	4484
Lin. Ft. 15" V.S.P. or R.C.P.	348	1754	2621	4723
Lin. Ft. 18" V.S.P. or R.C.P.	100	2250	12	2362
Lin. Ft. 24" V.S.P. or R.C.P.	0	442	0	442
Lin. Ft. 24" V.S.P. relaid	0	442	0	442
Lin. Ft. 6" drain tile 30" deep, cinder backfill	500	500	500	1500
Cu. Yds. 1:5 1/2 concrete	3.3	4.35	0	7.65
Lbs. reinforcing steel	103	139	0	242
Trees to be removed	14	98	20	132
Trees to be planted	14	98	20	132
<b>PAVEMENT</b>				
Sq. Yds. 8" reinf. concrete pav. T-8 (40' width)	4954	0	0	4954
Sq. Yds. 10"x8"x8" reinf. concrete pav. T-8, 10'-6" width	0	14260	15533	29793
Sq. Yds. 7" concrete 1:5 1/2 mix, driveway replacement	40	25	0	65
Sq. Yds. 10"x8"x10" concrete base B-5	0	2322	0	2322
Sq. Yds. 8" concrete 1:7 1/2 mix, replacements at culverts etc.	0	162	162.77	324.77
Cu. Yds. 1:7 1/2 concrete, wedge course on curves	0	394	106	500
Sq. Yds. bituminous pavement, type B surface	0	15000	15133	30133
Cu. Yds. extra bituminous binder	0	310	290	600
Lin. Ft. 6"x4" integral concrete raised curb, 1:6 mix	1718	11948	13052	26718
<b>STRUCTURES (under 20' span)</b>				
Cu. Yds. excavation, including removal of 208 sq. yds. of existing pavement	13	130	267	410
Lin. Ft. 12" V.S.P. enc. or R.C.P.	42	585	688	1315
Lin. Ft. 42" R.C.P.	0	0	72	72
Cu. Yds. 1:5 1/2 concrete	0	0	9.75	9.75
Lbs. reinforcing steel	0	0	300	300
Cu. Yds. old masonry removed	0	0	33	33
Standard inlet basins	4	34	34	72