GENERAL SUMMARY

CALC. BY	JLT
DATE	2/93
CHKD. BY	SJS
DATE	2/93

LAKE COUNTY
LAK-20-15.75

OHIO
FHWA REGION 5

15
80

7	8	9	9A	10	11	12	13	14	18	19	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	74	75	76	ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION	AS PER PLAN SHT. NO.
																																		ROADWAY	
	LUMP																													201	11000	LUMP	LUMP	CLEARING AND GRUBBING	
					474			138	2,586	1,590		67	37	20	49	43	211	32	180		26	56	28	19	101	17				202	23000	5,674	SQ. YD.	PAVEMENT REMOVED	
				663																										202	23500	663	SQ. YD.	WEARING COURSE REMOVED	
											2,637	2,475	1,700	4,471	2,953	3,142	3,266	1,600	2,341	1,986	3,046	2,972	2,758	3,169	2,598	785				202	30000	41,899	SQ. FT.	WALK REMOVED	
				15249																										202	32000	15249	LIN. FT.	CURB REMOVED	
					5057																									202	32500	5057	LIN. FT.	CURB AND GUTTER REMOVED	
												27				10	12													202	35101	49	LIN. FT.	PIPE REMOVED, 24" AND UNDER, AS PER PLAN	9A
												1		3		1	1													202	58101	6	EACH	CATCH BASIN REMOVED, AS PER PLAN	9A
																					1		2	1						202	58701	4	EACH	MANHOLE ABANDONED, AS PER PLAN	9
																	LUMP													SPECIAL	20298000	LUMP	LUMP	REMOVAL MISCELLANEOUS: COMMERCIAL SIGN, TYPE A	9
																			LUMP											SPECIAL	20298000	LUMP	LUMP	REMOVAL MISCELLANEOUS: COMMERCIAL SIGN, TYPE B	9
																			LUMP											SPECIAL	20298000	LUMP	LUMP	REMOVAL MISCELLANEOUS: COMMERCIAL SIGN, TYPE C	9
											1									1										SPECIAL	20298600	2	EACH	ABANDON MISCELLANEOUS: FLUSH HOLE	9
									255	93	20	150	126	175	250	171	206	142	231	28										203	12000	1,847	CU. YD.	EXCAVATION NOT INCLUDING EMBANKMENT CONSTRUCTION	
											23	30	16	40	72	65	45	58	42	18										203	20000	409	CU. YD.	EMBANKMENT	
								501																						203	50000	501	SQ. YD.	SUBGRADE COMPACTION	
	63																													203	60000	63	STATION	LINEAR GRADING, METHOD B	
														1				1												604	39501	2	EACH	MONUMENT BOX ADJUSTED TO GRADE, AS PER PLAN.	9
																	1					1		1		1				604	40700	4	EACH	MONUMENT BOX FRAME	
																	1					1		1		1				604	40800	4	EACH	MONUMENT BOX COVER	
											2,448	2,511	1,800	3,778	2,963	3,003	3,294	1,915	2,572	1,945	2,994	2,829	2,688	3,108	2,771	708				608	10000	41,327	SQ. FT.	4" CONCRETE WALK	
											1			2			3		2			1				2				608	50000	11	EACH	CURB RAMP, TYPE 1	
											10			6	4	2	4		4	1		1			2					608	51000	34	EACH	CURB RAMP, TYPE 2	
																				40	97	30	60	181		65				608	54000	473	SQ. FT.	CURB RAMP, TYPE 2	
								15167																						609	26000	15167	LIN. FT.	CURB, TYPE 6	
																																		PAVEMENT	
	2,848																													251	01000	2,848	SQ. YD.	PARTIAL DEPTH PAVEMENT REPAIR	
	1,742																													252	01000	1,742	SQ. YD.	FULL DEPTH RIGID PAVEMENT REMOVAL AND FLEXIBLE REPLACEMENT	
	7,662																													252	01500	7,662	LIN. FT.	FULL DEPTH PAVEMENT SAWING	
					3,684																									254	01000	3,684	SQ. YD.	PAVEMENT PLANING, BITUMINOUS	
								82																						254	01010	82	SQ. YD.	PAVEMENT PLANING, PORTLAND CEMENT CONCRETE	
					369																									254	01600	369	SQ. YD.	PATCHING PLANED SURFACE	
								23				23	13	7	28	22	8	11	27		9	19	10	7	11	6				301	10002	224	CU. YD.	BITUMINOUS AGGREGATE BASE, AC-20	
								23																						304	20001	23	CU. YD.	AGGREGATE BASE, AS PER PLAN	8
						2982																								305	13000	2982	SQ. YD.	9" CONCRETE BASE	
						545																								310	12001	545	CU. YD.	SUBBASE, TYPE1, GRADING A, AS PER PLAN	8
						312		7																						402	20000	319	CU. YD.	ASPHALT CONCRETE, AC-20	
						744																								403	20000	774	CU. YD.	ASPHALT CONCRETE, AC-20	
							1178	6																						404	20000	1184	CU. YD.	ASPHALT CONCRETE, AC-20	
															4		2													404	25000	6	CU. YD.	ASPHALT CONCRETE, AC-20 (DRIVEWAYS)	
							2722																							407	10000	2722	GALLON	TACK COAT	
									1,463	626																				452	10000	2,089	SQ. YD.	6" PLAIN CONCRETE PAVEMENT	
									1,682	869					25															452	12000	2,576	SQ. YD.	8" PLAIN CONCRETE PAVEMENT	

PR10718/GEN1.DWG 2/18/93