GENERAL SUMMARY

CALC. BY JLT DATE 2/93	LAKE COUNTY LAK-20-15.75	OHIO
CHKD. BY SJS DATE 2/93		FHWA REGION 5

17/80

SHEET NUMBER																														ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION	AS PER PLAN SHT. NO.
7	8	9	9A	10	11	12	13	14	18	19	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	74	75	76						
																																		WATER WORKS	
											6																			638	00701	6	LIN. FT.	6" WATER MAIN DUCTILE IRON PIPE ANSI CLASS 52, MECHANICAL JOINTS AND FITTINGS, AS PER PLAN	9A,20
		200																												638	04800	200	LIN. FT.	3/4" COPPER SERVICE BRANCH	
		200																												638	04900	200	LIN. FT.	1" COPPER SERVICE BRANCH	
											1																			638	10501	1	EACH	FIRE HYDRANT REMOVED AND RESET, AS PER PLAN	9A,20
		71																												638	10800	71	EACH	VALVE BOX ADJUSTED TO GRADE	
		20																												638	10900	20	EACH	SERVICE BOX ADJUSTED TO GRADE	
		20																																	
		93																												638	98000	93	EACH	WATER WORK, MISC.: WATER METER CHAMBER ADJUSTED TO GRADE	9,20
																																		MAINTENANCE OF TRAFFIC	
600																														404	35000	600	CU. YD.	BITUMINOUS CONCRETE FOR MAINTAINING TRAFFIC	
500																														410	12000	500	CU. YD.	TRAFFIC COMPACTED SURFACE, TYPE A OR B	
0.32																														614	20400	0.32	MILE	TEMPORARY LANE LINE, CLASS II	
2.26																														614	21400	2.26	MILE	TEMPORARY CENTER LINE, CLASS II	
50																														616	10000	50	MGAL.	WATER	
5																														616	20000	5	TON	CALCIUM CHLORIDE	
																																		TRAFFIC CONTROL	
																									464					625	25100	464	LIN. FT.	CONDUIT, 1", 713.04	
																									370	1,082				630	03100	1,452	LIN. FT.	GROUND MOUNTED SUPPORT, NO. 3 POST	
																										15				630	08500	15	EACH	STREET NAME SIGN SUPPORT	
																									194					630	80100	194	SQ. FT.	SIGN, FLAT SHEET	
																									12					630	85000	12	EACH	REMOVAL OF GROUND MOUNTED SIGN AND STORAGE	
																										118				630	85100	118	EACH	REMOVAL OF GROUND MOUNTED SIGN AND REERECTION	
																									7	16				630	86002	23	EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL	
																									4					630	87000	4	EACH	REMOVAL OF OVERHEAD MOUNTED SIGN AND STORAGE	
																									2					630	88000	2	EACH	REMOVAL OF OVERHEAD SIGN SUPPORT AND STORAGE, TYPE TC-16.20	
																									951					632	27500	951	LIN. FT.	LOOP DETECTOR PAVEMENT CUTTING	
																									2,193					632	64900	2,193	LIN. FT.	LOOP DETECTOR WIRE, TYPE E	
																											1.272			642	00302	1.272	MILE	CENTER LINE, TYPE 2	
																											824			642	00402	824	LIN. FT.	CHANNELIZING LINE, TYPE 2	
																											562			642	00502	562	LIN. FT.	STOP LINE, TYPE 2	
																											2,889			642	00602	2,889	LIN. FT.	CROSSWALK LINE, TYPE 2	
																											1,043			642	00702	1,043	LIN. FT.	TRANSVERSE LINE, TYPE 2	
																											40			642	00902	40	SQ. FT.	ISLAND MARKING, TYPE 2	
																											28			642	01302	28	EACH	LANE ARROW, TYPE 2	
																											8			642	01402	8	EACH	WORD ON PAVEMENT, 72", TYPE 2	
																											1			642	01412	1	EACH	WORD ON PAVEMENT, 96", TYPE 2	
LUMP																														614	11000	LUMP	LUMP	MAINTAINING TRAFFIC	
																														619	15010	LUMP	LUMP	FIELD OFFICE, TYPE B	
																														623	10000	LUMP	LUMP	CONSTRUCTION LAYOUT STAKES	
																														624	10000	LUMP	LUMP	MOBILIZATION	

PR10718/GEN3.DWG 2/93