

SIGN QUANTITIES

 CALC. BY: JLT
 DATE: 6/92
 CHKD. BY: SJS
 DATE: 6/92

 LAKE COUNTY
 LAK-20-15.75

 OHIO
 FHWA REGION 5

 74
 80

SIGN REF.	SIGN LOCATION		SIGN CODE NO.	SIGN SIZE	NO. OF SUPPORTS	ITEM 630	
						SIGN, FLAT SHEET	GROUND MOUNTED SUPPORT, NO. 3 POST
	STATION	SIDE				S.F.	L.F.
1A	10+35 (ROCKWOOD DR.)	15'LT	R-1-30	30"X30"	1	6.25	13.0
1B	10+23 (PARMLY PL.)	15'LT	R-1-30	30"X30"	1	6.25	13.0
1C	10+35 (PARKVIEW DR.)	14'LT	R-1-30	30"X30"	1	6.25	13.0
1D	50+42 (PARKVIEW DR.)	14'LT	R-1-30	30"X30"	1	6.25	13.0
1E	9+64 (NOTTINGHAM PL.)	12.5'RT	R-1-30	30"X30"	1	6.25	13.0
1F	10+22 (BLAIR PL.)	12.5'RT	R-1-30	30"X30"	1	6.25	13.0
1G	9+63 (FOBES ST.)	17.5'RT	R-1-30	30"X30"	1	6.25	13.0
2A	546+70	49'RT	R-2-36	36"X36"	1	3.90	13.5
3A	532+90	21.5'RT	R-31A-36	36"X30"	1	7.50	13.0
3B	536+08	21.5'LT	R-31A-36	36"X30"	1	7.50	13.0
3C	548+16	29.5'LT	R-31A-36	36"X30"	1	7.50	13.0
3D	551+00	21.5'RT	R-31A-36	36"X30"	1	7.50	13.0
3E	552+08	24'RT	R-31A-36	36"X30"	1	7.50	13.0
3F	9+33 (STATE ST.)	23.5'RT	R-31A-36	36"X30"	1	7.50	13.0
3G	10+30 (STATE ST.)	23.5'LT	R-31A-36	36"X30"	1	7.50	13.0
3H	554+00	24'RT	R-31A-36	36"X30"	1	7.50	13.0
3I	555+01	21.5'RT	R-31A-36	36"X30"	1	7.50	13.0
3J	544+60	21.5'RT	R-31A-36	36"X30"	1	7.50	13.0
3K	548+35	23.5'LT	R-31A-36	36"X30"	1	7.50	13.0
3L	549+85	22.5'LT	R-31A-36	36"X30"	1	7.50	13.0
3M	546+30	22.5'RT	R-31A-36	36"X30"	1	7.50	13.0
4A	569+55	19'RT	R-31Q-36	36"X30"	1	7.50	13.0
4B	570+70	19'RT	R-31Q-36	36"X30"	1	7.50	13.0
5A	563+65	20'RT	W-1-30	30"X30"	1	6.25	14.0
5B	576+35	20'RT	W-1-30	30"X30"	1	6.25	14.0
6A	576+35	20'LT	W-2-30	30"X30"	1	6.25	14.0
6B	588+60	20'LT	W-2-30	30"X30"	1	6.25	14.0
7A	591+75	19.5'RT	M-39-24	24"X12"		2.00	
8A	537+25	22'RT	W-76P-30	30"X30"	1	6.25	14.0
SUBTOTAL					28	193.4	369.5

SIGN REF.	SIGN LOCATION		SIGN CODE NO.	ITEM 630			
				REMOVAL OF OVERHEAD SIGN SUPPORT & STORAGE **	REMOVAL OF OVERHEAD MOUNTED SIGN AND STORAGE	REMOVAL OF GROUND MOUNTED SIGN AND STORAGE	REMOVAL OF GROUND MOUNTED POST SUPPORT & DISPOSAL
	STATION	SIDE		EACH	EACH	EACH	EACH
X	546+70	RT	R-2			1	1
X	545+84	RT	R-26A R-29A	1	2		
X	549+26	LT	R-26A R-29A	1	2		
X	10+40 (ROCKWOOD DR.)	RT	R-1			1	1
X	10+18 (PARMLY PL.)	LT	R-1			1	
X	563+72	RT	W-1				1
X	576+55	LT	W-2				1
X	576+57	RT	W-1				1
X	10+31 (PARKVIEW DR.)	LT	R-1			1	1
X	50+40 (PARKVIEW DR.)	LT	R-1			1	
X	588+54	LT	W-2				1
X	9+62 (NOTTINGHAM PL.)		R-1			1	1
X	10+22 (BLAIR PL.)	LT	R-1			1	1
X	9+74 (FOBES ST.)	RT	R-1			1	1
SUBTOTAL				2	4	12	7

** TYPE TC-16.20

LOOP DETECTOR QUANTITIES

LOOP DETECTOR REFERENCE (SHEETS 71-73)	ITEM 625	ITEM 632	ITEM 632	DIMENSION
	CONDUIT 1" 713.04	LOOP DETECTOR WIRE, TYPE E*	LOOP DETECTOR PAVEMENT CUTTING	
	LIN.FT.	LIN.FT.	LIN.FT.	
LD-1	8	129	60	7x21
LD-2	15	148	69	7x21
LD-3	19	152	48	7x10
LD-4	15	147	44	7x10
LD-5	18	114	57	7x13
LD-6	45	218	106	7x25
LD-7	20	128	59	7x15
LD-8	25	138	64	7x15
LD-9	85	170	81	7x18
LD-10	30	148	71	7x15
LD-11	25	177	56	7x10
LD-12	82	130	80	7x18
LD-13	47	190	92	7x18
LD-14	30	204	64	7x12
TOTAL	464	2193	951	

* SPLICES NOT PERMITTED