



US-20 / SR-2 PAVEMENT MARKING QUANTITIES									
LOCATION **		SIDE	LENGTH		ITEM 828				
					EDGE LINE	LANE LINE	CENTER LINE	CHANNELIZING LINE	TRANSVERSE LINE
FROM	TO		LIN. FT.	MILE	MILE	MILE	MILE	LIN. FT.	LIN. FT.
19.29	19.58	RT	1531	0.29	0.29		0.29		
19.58	19.71	RT	686	0.13	0.26			742	279
19.71	19.76	RT	264	0.05	0.10	0.05			
19.29	19.52	LT	1214	0.23	0.23				
19.52	19.58	LT	317	0.06	0.12			637	450
19.58	19.61	LT	158	0.03	0.06			157	
19.61	19.76	LT	792	0.15	0.30	0.15			
TOTALS *					1.36	0.20	0.29	1536	729

* CARRIED TO GENERAL SUMMARY ON SHEET 22.

** SLM LOCATIONS ARE APPROXIMATE AND WILL REQUIRE FIELD ADJUSTMENT BY THE ENGINEER.



CALCULATED
CHECKED

TRAFFIC CONTROL
U.S. 20 & S.R. 2

LAKE COUNTY
LAK-20-17.40