

the clearing and grubbing operations.

(B) Installation of Control Features. Temporary erosion and sediment control items shall be installed as detailed and are to remain functional until the upper slope drainage areas are fully stabilized.

Temporary perimeter, ditch check or inlet filter fabric fence shall be constructed in accordance with Standard Drawing DM-4.4.

1. Temporary Perimeter Controls: Temporary perimeter filter fabric fence shall protect the following from sheet flow runoff: off right of way locations; off construction limit locations; around water bodies, wet lands or around other significant items designated on the plan.

Dikes shall be used to prevent flow from coming on to the project and to barren areas on the project.

The Contractor shall install perimeter filter fabric fence and dikes concurrent with the clearing and grubbing operations.

2. Inlet Protection: The Contractor shall use an 18 inch [0.5m] wide filter fabric fence supported around a storm drain inlet or manhole with securely nailed 2 x 4 inch (50 X 100 mm) lumber. The Contractor shall excavate a six inch (150 mm) trench around the inlet, and drive the posts six inches (150 mm) below the excavated trench bottom. The fabric shall be stretched around the frame, placing six inches of fabric in the trench and secure tightly. The fabric shall overlap on one side of the inlet so that the fabric ends are not attached to the same post. Backfill the excavated soil onto the fabric and compact tightly.

The Contractor shall construct the inlet protection as soon as the inlet is completed.

3. Temporary and Permanent Seeding: Use seed and mulch liberally during and after construction and before or during winter shut down. Temporary seeding areas shall be fertilized at one-half the specified rate of application in Item 659. Temporary seeding shall be annual ryegrass sown at 2 pounds per 1000 square feet [1 kg/100 m²] and mulched in accordance with Item 659. When project conditions prevent the incorporation of fertilizer into the soil and preparation of the seed bed cannot be performed in accordance with Item 659, these requirements may be waived. Temporary seed shall not be placed on frozen ground.

The Contractor shall place the permanent seed on all barren areas within 7 days of obtaining final grade. The Contractor shall place the temporary seed and mulch as stated under clearing and grubbing.

4. Slopes: Dikes, slope drains and ditches shall be installed to divert water from bare soil and to protect cut and fill slopes. The Contractor shall place dikes at the top of fill slopes to protect the sides slopes from erosion.

The Contractor shall install dikes and slope drains when no filling activity occurs for three or more weeks and when slope height is greater than 8 feet [2.5m].

The Contractor shall construct a ditch at the top of cut slopes prior to the cutting of the slope to reduce runoff potential.

5. Ditch Checks: Filter fabric fence or rock checks are placed to protect ditches from erosion and to filter sediment from flowing water. The checks are placed across the width of the ditch.

Filter fabric fences are installed for 2 acres (8,000 m²) or less of drainage area. Rock ditch checks are installed for 2 to 5 acres (8,000 to 20,000 m²) of drainage area. When no rock quantities are denoted for rock checks, use the calculated rock quantities from basins for the rock checks.

Ditch checks shall be installed in conjunction with sediment basins and dams when the above drainage areas are not exceeded.

The Contractor shall place the ditch checks as soon as the ditch is cut.

6. Bale Filter Dikes: Bale filter dikes shall be installed a few feet (meters) from the toe of a slope to filter and/or divert sediment to an appropriate control before it enters a water body on or off the project limits.

It is used to collect sediment for a maximum of:

- a) less than 1/4 acre [1,000 m²] without an outlet
- b) slope length of less than 100 feet [30 m] at a maximum slope of 2:1.
- c) use outlet or pit every 100 feet [30 m] for a 2:1 slope. Use a greater spacing for flatter slopes.

Bale filter dikes shall be constructed in accordance with Standard Drawing DM- 4.3. When filter fabric is used for the bale filter dike, the location is accordance with Standard Drawing DM-4.3 and the construction details shown in Standard Drawing DM-4.4 are used.

The Contractor shall construct the bale filter dikes concurrent with the grubbing operations.

7. Sediment Dams or Basins: Basins and dams are placed and used at concentrated and critical flow locations to settle sediment out before leaving the project. Use basins at the bottom of a ravine, at a culvert inlet or outlet, along or at the end of the ditch and at any concentrated sediment exit point of the project. Use a basin quantity of 67 cubic yards for every acre of drainage area (125 m³ per 10,000 m²).

The Contractor shall construct sediment dams and basins at the first step of grading and within 7 days of commencing grubbing operations.