

SHEET NUMBER											PARTICIPATION		ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.	CALCULATED BF	CHECKED CRP
4	5	9		12	13	14	15	16	17		PROJECT	LOCAL								
																	ROADWAY			
											LUMP		201	11000	LUMP		CLEARING AND GRUBBING			
						LUMP					LUMP		202	11000	LUMP		STRUCTURE REMOVED	4		
		10									10		202	23000	10	SQ. YD.	PAVEMENT REMOVED			
				88							88		202	32000	88	LIN. FT.	CURB REMOVED			
								55			55		202	32600	55	LIN. FT.	GUTTER REMOVED			
						10					10		202	35100	10	LIN. FT.	PIPE REMOVED, 24" AND UNDER			
				1							1		202	58100	1	EACH	CATCH BASIN REMOVED			
500											500		203	55000	500	LIN. FT.	DITCH CLEANOUT			
																	EROSION CONTROL			
									48		48		601	20000	48	SQ. YD.	CRUSHED AGGREGATE SLOPE PROTECTION			
							3	16			19		601	32200	19	CU. YD.	ROCK CHANNEL PROTECTION, TYPE C WITH FILTER			
50											50		601	34200	50	CU. YD.	ROCK CHANNEL PROTECTION, TYPE C WITHOUT FILTER			
	100										100		670	40000	100	SQ. YD.	DITCH EROSION PROTECTION			
	500										500		670	41000	500	SQ. YD.	SLOPE EROSION PROTECTION			
	2										2		870	00100	2	EACH	SOIL ANALYSIS TEST			
	9										9		870	00300	9	CU. YD.	TOPSOIL			
	833										833		870	10000	833	SQ. YD.	SEEDING AND MULCHING			
42											42		870	14000	42	SQ. YD.	REPAIR SEEDING AND MULCHING			
	0.11										0.11		870	20000	0.11	TON	COMMERCIAL FERTILIZER			
	0.35										0.35		870	30000	0.35	TON	AGRICULTURAL LIME			
1	9										10		870	35000	10	M GAL.	WATER			
	188										188		870	40000	188	M SQ. FT.	MOWING			
275											275		877	10000	275	SQ. YD.	TEMPORARY SEEDING AND MULCHING			
200											200		877	30100	200	LIN. FT.	TEMPORARY PERIMETER FILTER FABRIC FENCE			
50											50		877	30200	50	LIN. FT.	TEMPORARY DITCH CHECK FILTER FABRIC FENCE			
150											150		877	30300	150	LIN. FT.	TEMPORARY INLET PROTECTION FILTER FABRIC FENCE			
240											240		877	40000	240	LIN. FT.	TEMPORARY SLOPE DRAINS			
10											10		877	55500	10	SQ. YD.	TEMPORARY DITCH PROTECTION			
25											25		877	60000	25	CU. YD.	SEDIMENT REMOVAL			
																	DRAINAGE			
						0.43		0.69			1.12		602	20000	1.12	CU. YD.	CONCRETE MASONRY			
				69							69		603	05900	69	LIN. FT.	15" CONDUIT, TYPE B, 706.02 OR 707.33			
					12						12		603	06100	12	LIN. FT.	15" CONDUIT, TYPE C, 706.02 1250 D-LOAD MIN OR 707.33			
				87	169	50					306		603	10400	306	LIN. FT.	24" CONDUIT, TYPE B, 706.02 OR 707.33			
					58						58		603	13200	58	LIN. FT.	30" CONDUIT, TYPE A, 706.02 1250 D-LOAD MIN			
							18	168			186		603	13600	186	LIN. FT.	30" CONDUIT, TYPE C, 706.02 OR 707.33			
						202					202		603	13600	202	LIN. FT.	30" CONDUIT, TYPE C, 706.02 1750 D-LOAD MIN			
				1							1		604	00400	1	EACH	CATCH BASIN No. 3			
				2	1						3		604	00800	3	EACH	CATCH BASIN No. 3A			
					1	1			2		4		604	31500	4	EACH	MANHOLE No. 3			
				1							1		604	31500	1	EACH	MANHOLE No. 3, TYPE A	4		
						1					1		604	31500	1	EACH	MANHOLE No. 3, TYPE B	4		
				88	20						108		605	11110	108	LIN. FT.	6" SHALLOW PIPE UNDERDRAIN WITH FABRIC WRAP			

GENERAL SUMMARY

LAK-20-17.60