

If proper sediment and erosion controls are not being provided by the Contractor, progress estimates shall be withheld until proper controls are placed.

All temporary erosion control items shall be removed before the project is accepted. Removed materials shall become the property of the Contractor and shall be disposed of in accordance with Item 203.

**877.06 Method of Measurement.** Temporary erosion and sediment control work, completed and accepted, will be measured as follows:

- (A) All fertilized areas will be measured and paid for as Item 659 Commercial Fertilizer.
- (B) Temporary seeding and mulching will be measured by the square yard (square meter) of seeded and mulched area completed in accordance with these specifications.
- (C) Temporary slope drains will be measured by the linear foot (meter) complete in place.
- (D) Temporary Perimeter, Inlet Protection, Ditch Check, Filter Fabric Fence will be measured per linear foot (meter) in place. Bale filter dike will be paid under temporary perimeter fabric fence.
- (E) Rock required will be paid for under Item 601 Rock Channel Protection, Type C or D with or without filter.
- (F) Temporary sediment dams, and basins will be measured by the cubic yard (cubic meter) of excavation and embankment complete in place.
- (G) Temporary dikes will be measured by the cubic yard(cubic meter), of excavation and embankment complete in place.
- (H) Temporary slope or ditch protection will be measured by the square yard (square meter), complete in place.
- (I) Sediment Removal will be measured in cubic yards(cubic meters) completed in place. The sediment removed from dams, basins, inlet protection, ditch checks, perimeter filter fabric, bale filter dikes and all other types of filter fabrics, straw or hay bales or any other temporary sediment control items will be paid under this item.

In the event that temporary erosion and sediment control measures are required due to the Contractor's negligence, carelessness, or failure to install permanent controls as a part of the work as scheduled, such temporary work shall be performed by the Contractor at his expense.

**877.07 Basis of Payment:** Accepted quantities of temporary sediment and erosion control

work placed and measured as provided above, will be paid for under:

Item	Unit	Description
877	Square yard (square meter)	Temporary seeding and mulching
877	Linear foot (meter)	Temporary slope drains
877	Cubic yard (cubic meter)	Temporary sediment basins and dams
877	Linear foot (meter)	Temporary perimeter, ditch check or inlet protection filter fabric fence
877	Linear foot (meter)	Temporary perimeter filter fabric fence
877	Linear foot (meter)	Temporary ditch check filter fabric fence
877	Linear foot (meter)	Temporary inlet protection filter fabric fence
877	Cubic yard (cubic meter)	Temporary dikes
877	Square yard (square meter)	Temporary ditch protection
877	Square yard (square meter)	Temporary slope protection
877	Cubic yard (cubic meter)	Sediment removal