SHEET NUMBER											PARTICIPATION		ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
4	5	9		12	13	14	15	16	17		PROJECT	LOCAL						
																	PAVEMENT	
		2		2	1						5		304	20001	5	CU. YD.	AGGREGATE BASE, AS PER PLAN	4
		10		10	2						22		305	12001	22	CU. YD.	8" CONCRETE BASE, AS PER PLAN	4
		1		1	1						3		407	10000	3	GAL	TACK COAT	
		1		1	1						3		407	14000	3	GAL	TACK COAT FOR INTERMEDIATE COURSE	
		1		1	1						3		448	46020	3	CU. YD.	ASPHALT CONCRETE, INTERMEDIATE COURSE, TYPE 1, PG64-22	
		1		1	1						3		448	47001	3	CU. YD.	ASPHALT CONCRETE, SURFACE COURSE, TYPE 1 PG76-22, AS PER PLAN	4
		90		69	15						174		830	26000	174	LIN. FT.	CURB, TYPE 6	
																	TRAFFIC CONTROL	
				0.09							0.09		642	00300	0.09	MILE	CENTERLINE, TYPE 1	
																	MAINTENANCE OF TRAFFIC	
	25										25		614	13000	25	CU. YD.	BITUMINOUS CONCRETE FOR MAINTAINING TRAFFIC	
		0.17									0.17		614	21200	0.17	MILE	TEMPORARY CENTERLINE, CLASS 1, 740.06, TYPE 1	
		0.22									0.22		614	22200	0.22	MILE	TEMPORARY EDGELINE, CLASS 1, 740.06, TYPE 1	
		50									50		615	25000	50	SQ. YD.	TEMPORARY PAVEMENT, CLASS B	
											LUMP		614	11000	LUMP		MAINTAINING TRAFFIC	
											LUMP		623	10000	LUMP		CONSTRUCTION LAYOUT STAKES	
											LUMP		624	10000	LUMP		MOBILIZATION	

CALCULATED BF
CHECKED CRP

GENERAL SUMMARY

LAK-20-17.60