SHEET NUMBERS														GRAND			REF.
5	6	6A	7	12	13	14	36	37	37A	40	63	ITEM	EXT.	TOTAL	UNIT	DESCRIPTION	SHEET
																ROADWAY	
												201	11000	LUMP SUM		CLEARING AND GRUBBING	
	10											SPECIAL	690E50000	10	EACH	MAILBOX SUPPORT	6
						273						202	22901	273	S.Y.	APPROACH SLAB REMOVED, AS PER PLAN	6
					51	3446						202	23000	3497	S.Y.	PAVEMENT REMOVED	
						1588						202	32000	1588	L.F.	CURB REMOVED	
				334								202	38000	334	L.F.	GUARDRAIL REMOVED	
										12		202	54100	12	EACH	RAISED PAVEMENT MARKER REMOVED FOR STORAGE	
				4								202	58100	4	EACH	CATCH BASIN REMOVED	
700												SPECIAL	202E70100	700	L.F.	PIPE CLEANOUT	
50		371			46							203	12000	467	C.Y.	EXCAVATION NOT INCLUDING EMBANKMENT CONSTRUCTION	
100		578			26							203	20000	704	C.Y.	EMBANKMENT	
												203	45000	2	HOUR	PROOF ROLLING	
						3769						203	50000	3769	S.Y.	SUBGRADE COMPACTION	
											2	604	38500	2	EACH	MONUMENT ASSEMBLIES	
				125								606	13000	125	L.F.	GUARDRAIL, TYPE 5	
				4								606	26500	4	EACH	ANCHOR ASSEMBLY, TYPE T	
				4								606	35000	4	EACH	BRIDGE TERMINAL ASSEMBLY, TYPE I	
	LUMP SUM											SPECIAL	690E71000	LUMP SUM		ASBESTOS ABATEMENT	6
																EROSION CONTROL	
	2											870	00100	2	EACH	SOIL ANALYSIS TEST	
	204											870	00200	204	C.Y.	PLACING TOPSOIL	
		1936										870	10000	1936	S.Y.	SEEDING AND MULCHING	
	92											870	14000	92	S.Y.	REPAIR SEEDING AND MULCHING	
	0.25											870	20000	0.25	TON	COMMERCIAL FERTILIZER	
	0.76											870	30000	0.76	TON	AGRICULTURAL LIME	
	5											870	35000	5	M GAL	WATER	
	184											877	10000	184	S.Y.	TEMPORARY SEEDING AND MULCHING	
	1500											877	30100	1500	L.F	TEMPORARY PERIMETER FILTER FABRIC FENCE	
	413											877	30300	413	L.F	TEMPORARY INLET PROTECTION FILTER FABRIC FENCE	
	25											877	60000	25	C.Y.	SEDIMENT REMOVAL	
																DRAINAGE	
				587								603	04400	587	L.F.	12" CONDUIT, TYPE B	
				1								604	00800	1	EACH	CATCH BASIN NO. 3A	
				1								604	02400	1	EACH	CATCH BASIN, NO. 7	
				6								604	17500	6	EACH	INLET, 2-A-6	
				1								604	17900	1	EACH	INLET, 2-A-8	
				2								604	18300	2	EACH	INLET, 2-A-10	
				1307								605	13410	1307	LF.	6" UNCLASSIFIED PIPE UNDERDRAIN WITH FABRIC WRAP	
																PAVEMENT	
						353						254	01001	353	S.Y.	PAVEMENT PLANING, BITUMINOUS, AS PER PLAN	6
						831						301	46000	831	C.Y.	BITUMINOUS AGGREGATE BASE, PG 64-22	
		302				628						304	20000	930	C.Y.	AGGREGATE BASE	
						371						407	10000	371	GAL.	TACK COAT	
						278						407	14000	278	GAL.	TACK COAT FOR INTERMEDIATE COURSE	
						1332						408	10000	1332	GAL.	BITUMINOUS PRIME COAT	
		94			41							411	12000	135	C.Y.	STABILIZED CRUSHED AGGREGATE, GRAVEL	
						179						448	46030	179	C.Y.	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, PG 64-22	
						6						448	46060	6	C.Y.	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I, PG 64-22 (UNDER GUARDRAIL)	
						128						448	47020	128	C.Y.	ASPHALT CONCRETE SURFACE COURSE, TYPE I, PG 64-22	
					51							452	10000	51	S.Y.	6" PLAIN CONCRETE PAVEMENT	
					194							452	12000	194	S.Y.	8" PLAIN CONCRETE PAVEMENT	
						366						611	25001	366	S.Y.	REINFORCED CONCRETE APPROACH SLAB (T=15"), AS PER PLAN	5
						1551						830	26000	1551	L.F.	CURB, TYPE 6	

CALCULATED KNG CHECKED SM

GENERAL SUMMARY

LAK-20-18.07

L:\Projects\ODOT\24580_Lak-20\Drawings\GENSUM.dgn 14-NOV-2002 9:58AM Administrator