

L:\Projects\000T\24580_Lak-20\Drawings\GENSUM.dgn 14-NOV-2002 10:01AM Administrator

SHEET NUMBERS												ITEM	EXT.	GRAND TOTAL	UNIT	DESCRIPTION	REF. SHEET
5	6	6A	7	12	13	14	36	37	37A	40	63						
							100					202	35101	100	L.F.	PIPE REMOVED, 24" AND UNDER, AS PER PLAN	35
												502	11100	LUMP SUM		TEMPORARY STRUCTURE	
								4				510	11100	4	EACH	DOWEL HOLES	
								2				516	41100	2	EACH	1/8" PREFORMED BEARING PAD, 711.21	
							209					638	02504	209	L.F.	12" WATER MAIN DUCTILE IRON PIPE ANSI CLASS 53, MECHANICAL JOINTS AND FITTINGS	
							77					638	02505	77	L.F.	12" WATER MAIN DUCTILE IRON PIPE ANSI CLASS 53, MECHANICAL JOINTS AND FITTINGS, AS PER PLAN	35
							1					SPECIAL	63841300	1	EACH	12" GATE VALVE WITH VALVE BOX	
							1					SPECIAL	63843000	1	EACH	HYDRANT ADJUSTED TO GRADE	
							2					SPECIAL	63843800	2	EACH	VALVE BOX ADJUSTED TO GRADE	
							1					SPECIAL	63844200	1	EACH	BLOWOFF ASSEMBLY	
							4					SPECIAL	63898000	4	EACH	WATERWORK, MISC.: METER AND BOX ADJUSTED TO GRADE	
							2					SPECIAL	63898000	2	EACH	WATERWORK, MISC.: BULKHEAD ABANDONED PIPE	
									315			638	98600	315	L.F.	WATER WORK, MISC.: 12" PVC TEMPORARY WATER MAIN	
								4763				863	10200	4763	LBS.	STRUCTURAL STEEL MEMBERS, MISCELLANEOUS LEVEL FABRICATION, A709, GRADE 50W	
												863	95020	LUMP SUM		STRUCTURAL STEEL MISC.: ANCHOR BOLTS, U-BOLTS, NUTS AND WASHERS	
								6				863	95030	6	EACH	STRUCTURAL STEEL MISC. STEEL ROLLER STANDS	
																TRAFFIC CONTROL	
									12			621	00100	12	EACH	RAISED PAVEMENT MARKERS	
									71			630	03100	71	L.F.	GROUND MOUNTED SUPPORT, NO. 3 POST	
									18.3			630	80200	18.3	S.F.	SIGN, FLAT SHEET	
									5			630	84900	5	EACH	REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL	
									5			630	86002	5	EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL	
									0.08			828	10000	0.08	MILE	EDGE LINE	
									0.36			828	10100	0.36	MILE	LANE LINE	
									0.18			828	10200	0.18	MILE	CENTER LINE	
																MAINTENANCE OF TRAFFIC	
							40					614	11100	40	HOURS	LAW ENFORCEMENT OFFICER WITH PATROL CAR	
							50					614	12500	50	S.F.	REPLACEMENT SIGN	
							100					614	13000	100	C.Y.	BITUMINOUS CONCRETE FOR MAINTAINING TRAFFIC	
							20					614	13300	20	EACH	BARRIER REFLECTOR, TYPE B	
							2					616	10000	2	M.GAL.	WATER	
							0.20					616	20000	0.20	TON	CALCIUM CHLORIDE	
							100					617	10100	100	C.Y.	COMPACTED AGGREGATE, TYPE A	
							120					622	40020	120	L.F.	PORTABLE CONCRETE BARRIER, 32"	
							LUMP SUM					614	11000	LUMP SUM		MAINTAINING TRAFFIC	
							LUMP SUM					623	10000	LUMP SUM		CONSTRUCTION LAYOUT STAKES	
							LUMP SUM					624	10000	LUMP SUM		MOBILIZATION	
												806	16010	8	MONTH	FIELD OFFICE, TYPE B	
																FOR STRUCTURE QUANTITIES, SEE SHEET 50	

CALCULATED
KMG
CHECKED
SM

GENERAL SUMMARY

LAK-20-18.07