

100% LOCAL PARTICIPATION - LAKE COUNTY DEPARTMENT OF UTILITIES																		
ITEM	638	SPECIAL	SPECIAL	SPECIAL	SPECIAL	SPECIAL	SPECIAL	638	202	638	502	510	863	863	863	516		
EXT	02504	63841300	63844200	63898000	63843800	63898000	63843000	02505	35101	98600	11100	11100	10200	95020	95030	41100		
	12" WATER MAIN, DUCTILE IRON PIPE, ANSI CLASS 53, MECHANICAL JOINTS AND FITTINGS	12" GATE VALVE WITH VALVE BOX	BLOWOFF ASSEMBLY	WATERWORK MISC.: BULKHEAD ABANDONED PIPE	VALVE BOX ADJUSTED TO GRADE	WATERWORK MISC.: METER AND BOX ADJUSTED TO GRADE	HYDRANT ADJUSTED TO GRADE	12" WATER MAIN, DUCTILE IRON PIPE, ANSI CLASS 53, MECHANICAL JOINTS AND FITTINGS, AS PER PLAN	PIPE REMOVED, 24" AND UNDER, AS PER PLAN	WATERWORK, MISC.: 12" PVC TEMPORARY WATER MAIN	TEMPORARY STRUCTURE	DOWEL HOLES	STRUCTURAL STEEL MEMBERS, MISCELLANEOUS LEVEL FABRICATION, A709, GRADE 50W	STRUCTURAL STEEL, MISC.: ANCHOR BOLTS, U-BOLTS, NUTS AND WASHERS	STRUCTURAL STEEL, MISC.: STEEL ROLLER STANDS	1/8" PREFORMED BEARING PAD, 711.21		
	L.F.	EACH	EACH	EACH	EACH	EACH	EACH	L.F.	L.F.	L.F.	LUMP	EACH	POUND	LUMP	EACH	EACH		
36	W-1	STA. 7+77, LT.					1											
36	W-2	W/L STA. 0+38 TO STA. 0+50																
36	W-3	W/L STA. 0+50 TO STA. 1+10																
36	W-4	W/L STA. 1+10 TO STA. 1+17								10								
36	W-5	W/L STA. 1+17 TO STA. 1+74								57								
36	W-6	W/L STA. 1+74 TO STA. 1+81								10								
36	W-7	W/L STA. 1+81 TO STA. 2+43																
36	W-8	W/L STA. 2+43 TO STA. 2+53																
36	W-9	W/L STA. 2+47			1													
36	W-10	STA. 11+60, LT.							1									
36	W-11	STA. 11+81, LT.					1											
36	W-12	STA. 11+96, LT.								1								
36	W-13	STA. 7+41, RT.								1								
36	W-14	STA. 9+00, 27' LT.				1												
36	W-15	STA. 11+01, 27' LT.				1												
36	W-16	STA. 12+09, RT.								1								
36	W-17	STA. 13+23, RT.								1								
36	W-18	STA. 9+50 TO STA. 10+50, LT.									100							
36	W-19	W/L STA. 0+00 TO STA. 0+38, LT.																
36	W-20	W/L STA. 2+53 TO STA. 2+80, LT.																
36	W-21	W/L STA. 0+00																
37		ESTIMATED QUANTITIES											4	4,763	LUMP	6	2	
37A		ESTIMATED QUANTITIES											315	LUMP				
TOTALS CARRIED TO GENERAL SUMMARY			209	1	1	2	2	4	1	77	100	315	LUMP	4	4,763	LUMP	6	2

FOR PLAN VIEW SEE SHEET 36  
 FOR WATERWORK DETAILS SEE SHEET 37  
 FOR GENERAL SUMMARY SEE SHEET 11