

ITEM	SHEET NUMBER													ITEM	ITEM EXT.	TOTAL	UNIT	DESCRIPTION	AS PER PLAN DESIGNATION OR SPECIAL	CALCULATED B.L.B.	CHECKED W.D.B.		
	CODE 1 = NORMAL PARTICIPATION						CODE 2 = 100% LOCAL PARTICIPATION (LAKE COUNTY DEPARTMENT OF UTILITIES)															SUB-TOTALS	
	17	18	19	60	60A	61	63	64	70	74	312	316											
ROADWAY																							
201	LUMP																201	11000	LUMP	CLEARING AND GRUBBING			
202				1												1	202	11004	1	EACH	STRUCTURE REMOVED, HEADWALL		
202								7500	1232						8732	202	23000	8732	SQ. YD.	PAVEMENT REMOVED			
202				10,239											10,239	202	30000	10,239	SQ. FT.	WALK REMOVED			
202				584				17,764							18,348	202	32000	18,348	LIN. FT.	CURB REMOVED			
202				1766											1766	202	35100	2070	LIN. FT.	PIPE REMOVED, 24" AND UNDER			
202				34											34	202	38000	34	LIN. FT.	GUARDRAIL REMOVED			
202				15											15	202	38800	15	EACH	GUARD POST REMOVED			
202				8											8	202	58000	8	EACH	MANHOLE REMOVED			
202				62											62	202	58100	62	EACH	CATCH BASIN REMOVED			
202				1											1	202	58400	1	EACH	INLET ABANDONED			
202				11											11	202	60010	11	EACH	MONUMENT ASSEMBLY REMOVED			
202			1												1	202	67000	1	EACH	REGULATED UNDERGROUND STORAGE TANK REMOVED			
202				1183											1183	202	75000	1183	LIN. FT.	FENCE REMOVED			
				10											10	202	75200	10	LIN. FT.	FENCE REMOVED FOR REUSE			
202				52											42	202	98000	LUMP	LUMP	REMOVAL MISC.: CONC. RETAINING WALL			
202				205											205	202	98000	LUMP	LUMP	REMOVAL MISC.: R.R. TIE RETAINING WALL			
202				26											26	202	98100	26	EACH	REMOVAL MISC.: WOOD POST			
202				7											7	202	98100	7	EACH	REMOVAL MISC.: STEEL POST			
202				19											19	202	98100	19	EACH	REMOVAL MISC.: SIGN			
202				1											1	202	98100	1	EACH	REMOVAL MISC.: BILLBOARD SIGN			
202				3											3	202	98100	3	EACH	REMOVAL MISC.: LANDSCAPE GARDEN			
202				4											4	202	98100	4	EACH	REMOVAL MISC.: PLANTER			
202				1											1	202	98100	1	EACH	REMOVAL MISC.: SPOT LIGHTS			
202				2											2	202	98100	2	EACH	REMOVAL MISC.: LAMP POST			
202				1											1	202	98100	1	EACH	REMOVAL MISC.: WATER WELL			
202				1								315			315	202	98100	315	EACH	REMOVAL MISC.: RAISED PAVEMENT MARKERS REMOVED FOR STORAGE	316		
202				553											553	202	98200	553	LIN.FT.	REMOVAL MISC.: R.R. TIES			
203	2300					21,777						1161			25,340	203	12000	25,340	CU. YD.	EXCAVATION NOT INCLUDING EMBANKMENT CONSTRUCTION			
203						10,059									10,161	203	20000	10,161	CU. YD.	EMBANKMENT			
203	1000														1000	203	21000	1000	CU. YD.	EMBANKMENT USING GRANULAR MATERIAL			
203	15														15	203	45000	15	HOUR	PROOF ROLLING			
203															3.91	203	60000	3.91	STA.	LINEAR GRADING			
604					18										18	604	38500	18	EACH	MONUMENT ASSEMBLY			
606					87										87	606	12500	87	LIN. FT.	GUARDRAIL, TYPE 4			
606					275										275	606	13000	275	LIN. FT.	GUARDRAIL, TYPE 5			
606					2										2	606	22010	2	EACH	ANCHOR ASSEMBLY, TYPE E-98			
606					2										2	606	26500	2	EACH	ANCHOR ASSEMBLY, TYPE T			
608					18,311										18,311	608	10000	18,311	SQ. FT.	4" CONCRETE WALK			
608					31										31	608	49000	31	EACH	CURB RAMP			
608		240													240	608	98000	240	SQ. FT.	WALKWAY MISC.: TRUNCATED DOMES ON CURB RAMPS	19		
SPECIAL			55												55	SPECIAL	69065010	55	TON	WORK INVOLVING SOLID WASTE			
EROSION																							
601															13.3	601	32100	13.3	CU. YD.	ROCK CHANNEL PROTECTION, TYPE B, WITH FILTER			
836															56	836	10000	56	SQ. YD.	SEEDING AND EROSION CONTROL WITH TURF REINFORCING MAT, TYPE 1			

GENERAL SUMMARY

LAK - 20 - 18.72

H:\1998\98404\DWG\Censusum.DWG PLOT SCALE 1:1