

FOR TYPICAL SECTIONS SEE SHEETS 8 - 14
 * INCLUDES EXTRA AREA BY COMPUTER CALCULATION

PAVEMENT								203	254	255	301	304	407	407	408	448	448	448	451			
STATION TO STATION	SIDE	LENGTH (FEET)	PLANING		RESURFACING		WIDENING		SUBGRADE COMPACTION	PAVEMENT PLANING (BITUMINOUS)	FULL DEPTH PAVEMENT SAWING	6" BITUMINOUS AGGREGATE BASE	6" AGGREGATE BASE AS PER PLAN	TACK COAT @ 0.10 GAL/SQ. YD.	TACK COAT FOR INTERMEDIATE COURSE @ 0.05 GAL/SQ. YD.	BITUMINOUS PRIME COAT @ 0.40 GAL/SQ. YD.	1 1/4" ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG 64-22	1 3/4" ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, PG 64-22	1/2" ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, PG 64-22	9" REINFORCED CONCRETE PAVEMENT		
			AVE. WIDTH (FEET)	AVE. WIDTH (FEET)	P'MT AREA (SQ. YDS.)	AVE. WIDTH (FEET)	P'MT AREA (SQ. YDS.)	SQ. YDS.													SQ. YDS.	LIN. FT.
RELOCATED LANE ROAD																						
14+79.00 TO 15+39.00	LT & RT	60.00		23.50	156.67	24.50	163.33	170.00		21.0	27.22	28.33	15.67	7.84	65.33	5.44	7.62					
15+39.00 TO 17+04.00	LT & RT	165.00		31.50	577.50	31.50	577.50	632.50			96.25	105.42	57.75	28.88	231.00	20.05	28.07					
17+04.00 TO 18+84.29	LT & RT	180.29		37.00	741.19	37.00	741.19	801.29			123.53	133.55	74.12	37.06	296.48	25.74	36.03					
20+56.00	LT & RT									68.0												
LANE INTERSECTION																						
					562.59*		601.01	639.43			101.25	106.60	56.26	28.13	240.40	19.53	27.35					
CENTER ROAD																						
4+50.00 TO 6+72.00	LT	222.00		13.15	324.37	13.65	336.70	349.03		20.5	56.12	58.17	32.44	16.22	134.68	11.26	15.77					
4+50.00 TO 6+75.00	RT	225.00		14.75	368.75	15.25	381.25	393.75			63.54	65.63	36.88	18.44	152.50	12.80	17.93					
6+72.00 TO 8+85.97	LT	213.97		18.29	434.83	18.29	434.83	470.50			72.47	78.42	43.48	21.74	173.93	15.10	21.14					
6+75.00 TO 8+85.97	RT	210.97		18.50	433.66	18.50	433.66	468.82			72.28	78.14	43.37	21.68	173.46	15.06	21.08					
CENTER INTERSECTION(ASPHALT)																						
					510.85*		546.44	582.03			92.16	97.03	51.09	25.55	218.58	17.74	24.83					
11+18.59 TO 12+60.00	RT	141.41		24.00	377.09			400.66					66.78								384.95	
12+60.00 TO 15+00.00	RT	240.00		20.00	533.33			573.33					95.56								546.67	
11+18.59 TO 14+20.00	LT	301.41		24.00	803.76			854.00					142.33								820.51	
14+20.00 TO 15+00.00	LT	80.00		20.00	177.78			191.11		32.0			31.85								182.22	
CENTER INTERSECTION(CONCRETE)																						
					624.82*			668.56					111.42								661.17	
TOWNLINER ROAD																						
4+15.00 TO 8+05.00	LT	390.00		13.75	595.83	14.17	614.03	635.70		18.50	102.34	105.95	59.58	29.79	245.61	20.69	28.96					
8+05.00 TO 8+95.63	LT	90.63		18.50	186.30	18.50	186.30	201.40			31.05	33.57	18.63	9.32	74.52	6.47	9.06					
4+15.00 TO 7+55.00	RT	340.00		14.00	528.89	14.50	547.78	566.67			91.30	94.44	52.89	26.44	219.11	18.36	25.71					
7+55.00 TO 8+95.63	RT	140.63		18.50	289.07	18.50	289.07	312.51			48.18	52.09	28.91	14.46	115.63	10.04	14.05					
11+03.85 TO 12+30.00	LT	126.15		18.50	259.31	18.50	259.31	280.33			43.22	46.72	25.93	12.96	103.72	9.00	12.61					
12+30.00 TO 14+85.00	LT	255.00		14.25	403.75	14.25	403.75	432.08			69.65	72.01	40.38	20.19	167.17	14.02	19.63					
11+03.85 TO 11+80.00	RT	76.15		18.50	156.53	18.50	156.53	169.22			26.09	28.20	15.65	7.83	62.61	5.44	7.61					
11+80.00 TO 14+85.00	RT	305.00		14.25	482.92	14.67	497.15	514.09		20.00	82.86	85.68	48.29	24.14	198.86	16.77	23.48					
TOWNLINER INTERSECTION																						
					884.20*		949.49	1010.18			155.74	168.37	88.42	44.21	379.80	30.70	42.98					
GREEN ROAD																						
11+03.88 TO 12+50.00	LT	146.12		18.50	300.36	18.50	300.36	324.71			50.06	54.12	30.04	15.02	120.14	10.43	14.60					
12+50.00 TO 15+05.00	LT	255.00		13.90	393.83	14.40	408.00	422.17			68.00	70.36	39.38	19.69	163.20	13.67	19.14					
11+03.88 TO 12+00.00	RT	96.12		18.50	197.58	18.50	197.58	213.60			32.93	35.60	19.76	9.88	79.03	6.86	9.60					
12+00.00 TO 15+05.00	RT	305.00		15.00	508.33	15.50	525.28	542.22		20.80	87.55	90.37	50.83	25.42	210.11	17.65	24.71					
GREEN INTERSECTION																						
					409.87*		440.25	468.92			74.17	78.09	40.99	20.50	176.10	14.23	19.92					
QUANTITIES CARRIED TO GENERAL SUMMARY								13289		201	1668	2215	971	486	4002	337	472				2596	

CALCULATED
H.J.H.
CHECKED
W.D.B.

PAVEMENT SUB-SUMMARY

LAK - 20 - 18.72

69
441